



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines


Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.


About Google Book Search


Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>



**HOW TO BUILD
A HOME**







**HOW TO BUILD
A HOME**

HOW TO BUILD A HOME

28489

THE HOUSE PRACTICAL

BEING SUGGESTIONS AS TO
SAFETY FROM FIRE, SAFETY
TO HEALTH, COMFORT, CON-
VENIENCE, DURABILITY, AND
ECONOMY ♣ ♣ ♣ ♣ ♣

BY

FRANCIS C. MOORE




NEW YORK
DOUBLEDAY & McCLURE CO.


1897

Copyright, 1897, by
FRANCIS C. MOORE

5-12-11-13-15-17-19-21-23-25-27-29-31-33-35-37-39-41-43-45-47-49-51-53-55-57-59-61-63-65-67-69-71-73-75-77-79-81-83-85-87-89-91-93-95-97-99-101-103-105-107-109-111-113-115-117-119-121-123-125-127-129-131-133-135-137-139-141-143-145-147-149-151-153-155-157-159-161-163-165-167-169-171-173-175-177-179-181-183-185-187-189-191-193-195-197-199-201-203-205-207-209-211-213-215-217-219-221-223-225-227-229-231-233-235-237-239-241-243-245-247-249-251-253-255-257-259-261-263-265-267-269-271-273-275-277-279-281-283-285-287-289-291-293-295-297-299-301-303-305-307-309-311-313-315-317-319-321-323-325-327-329-331-333-335-337-339-341-343-345-347-349-351-353-355-357-359-361-363-365-367-369-371-373-375-377-379-381-383-385-387-389-391-393-395-397-399-401-403-405-407-409-411-413-415-417-419-421-423-425-427-429-431-433-435-437-439-441-443-445-447-449-451-453-455-457-459-461-463-465-467-469-471-473-475-477-479-481-483-485-487-489-491-493-495-497-499-501-503-505-507-509-511-513-515-517-519-521-523-525-527-529-531-533-535-537-539-541-543-545-547-549-551-553-555-557-559-561-563-565-567-569-571-573-575-577-579-581-583-585-587-589-591-593-595-597-599-601-603-605-607-609-611-613-615-617-619-621-623-625-627-629-631-633-635-637-639-641-643-645-647-649-651-653-655-657-659-661-663-665-667-669-671-673-675-677-679-681-683-685-687-689-691-693-695-697-699-701-703-705-707-709-711-713-715-717-719-721-723-725-727-729-731-733-735-737-739-741-743-745-747-749-751-753-755-757-759-761-763-765-767-769-771-773-775-777-779-781-783-785-787-789-791-793-795-797-799-801-803-805-807-809-811-813-815-817-819-821-823-825-827-829-831-833-835-837-839-841-843-845-847-849-851-853-855-857-859-861-863-865-867-869-871-873-875-877-879-881-883-885-887-889-891-893-895-897-899-901-903-905-907-909-911-913-915-917-919-921-923-925-927-929-931-933-935-937-939-941-943-945-947-949-951-953-955-957-959-961-963-965-967-969-971-973-975-977-979-981-983-985-987-989-991-993-995-997-999-1001-1003-1005-1007-1009-1011-1013-1015-1017-1019-1021-1023-1025-1027-1029-1031-1033-1035-1037-1039-1041-1043-1045-1047-1049-1051-1053-1055-1057-1059-1061-1063-1065-1067-1069-1071-1073-1075-1077-1079-1081-1083-1085-1087-1089-1091-1093-1095-1097-1099-1101-1103-1105-1107-1109-1111-1113-1115-1117-1119-1121-1123-1125-1127-1129-1131-1133-1135-1137-1139-1141-1143-1145-1147-1149-1151-1153-1155-1157-1159-1161-1163-1165-1167-1169-1171-1173-1175-1177-1179-1181-1183-1185-1187-1189-1191-1193-1195-1197-1199-1201-1203-1205-1207-1209-1211-1213-1215-1217-1219-1221-1223-1225-1227-1229-1231-1233-1235-1237-1239-1241-1243-1245-1247-1249-1251-1253-1255-1257-1259-1261-1263-1265-1267-1269-1271-1273-1275-1277-1279-1281-1283-1285-1287-1289-1291-1293-1295-1297-1299-1301-1303-1305-1307-1309-1311-1313-1315-1317-1319-1321-1323-1325-1327-1329-1331-1333-1335-1337-1339-1341-1343-1345-1347-1349-1351-1353-1355-1357-1359-1361-1363-1365-1367-1369-1371-1373-1375-1377-1379-1381-1383-1385-1387-1389-1391-1393-1395-1397-1399-1401-1403-1405-1407-1409-1411-1413-1415-1417-1419-1421-1423-1425-1427-1429-1431-1433-1435-1437-1439-1441-1443-1445-1447-1449-1451-1453-1455-1457-1459-1461-1463-1465-1467-1469-1471-1473-1475-1477-1479-1481-1483-1485-1487-1489-1491-1493-1495-1497-1499-1501-1503-1505-1507-1509-1511-1513-1515-1517-1519-1521-1523-1525-1527-1529-1531-1533-1535-1537-1539-1541-1543-1545-1547-1549-1551-1553-1555-1557-1559-1561-1563-1565-1567-1569-1571-1573-1575-1577-1579-1581-1583-1585-1587-1589-1591-1593-1595-1597-1599-1601-1603-1605-1607-1609-1611-1613-1615-1617-1619-1621-1623-1625-1627-1629-1631-1633-1635-1637-1639-1641-1643-1645-1647-1649-1651-1653-1655-1657-1659-1661-1663-1665-1667-1669-1671-1673-1675-1677-1679-1681-1683-1685-1687-1689-1691-1693-1695-1697-1699-1701-1703-1705-1707-1709-1711-1713-1715-1717-1719-1721-1723-1725-1727-1729-1731-1733-1735-1737-1739-1741-1743-1745-1747-1749-1751-1753-1755-1757-1759-1761-1763-1765-1767-1769-1771-1773-1775-1777-1779-1781-1783-1785-1787-1789-1791-1793-1795-1797-1799-1801-1803-1805-1807-1809-1811-1813-1815-1817-1819-1821-1823-1825-1827-1829-1831-1833-1835-1837-1839-1841-1843-1845-1847-1849-1851-1853-1855-1857-1859-1861-1863-1865-1867-1869-1871-1873-1875-1877-1879-1881-1883-1885-1887-1889-1891-1893-1895-1897-1899-1901-1903-1905-1907-1909-1911-1913-1915-1917-1919-1921-1923-1925-1927-1929-1931-1933-1935-1937-1939-1941-1943-1945-1947-1949-1951-1953-1955-1957-1959-1961-1963-1965-1967-1969-1971-1973-1975-1977-1979-1981-1983-1985-1987-1989-1991-1993-1995-1997-1999-2001-2003-2005-2007-2009-2011-2013-2015-2017-2019-2021-2023-2025-2027-2029-2031-2033-2035-2037-2039-2041-2043-2045-2047-2049-2051-2053-2055-2057-2059-2061-2063-2065-2067-2069-2071-2073-2075-2077-2079-2081-2083-2085-2087-2089-2091-2093-2095-2097-2099-2101-2103-2105-2107-2109-2111-2113-2115-2117-2119-2121-2123-2125-2127-2129-2131-2133-2135-2137-2139-2141-2143-2145-2147-2149-2151-2153-2155-2157-2159-2161-2163-2165-2167-2169-2171-2173-2175-2177-2179-2181-2183-2185-2187-2189-2191-2193-2195-2197-2199-2201-2203-2205-2207-2209-2211-2213-2215-2217-2219-2221-2223-2225-2227-2229-2231-2233-2235-2237-2239-2241-2243-2245-2247-2249-2251-2253-2255-2257-2259-2261-2263-2265-2267-2269-2271-2273-2275-2277-2279-2281-2283-2285-2287-2289-2291-2293-2295-2297-2299-2301-2303-2305-2307-2309-2311-2313-2315-2317-2319-2321-2323-2325-2327-2329-2331-2333-2335-2337-2339-2341-2343-2345-2347-2349-2351-2353-2355-2357-2359-2361-2363-2365-2367-2369-2371-2373-2375-2377-2379-2381-2383-2385-2387-2389-2391-2393-2395-2397-2399-2401-2403-2405-2407-2409-2411-2413-2415-2417-2419-2421-2423-2425-2427-2429-2431-2433-2435-2437-2439-2441-2443-2445-2447-2449-2451-2453-2455-2457-2459-2461-2463-2465-2467-2469-2471-2473-2475-2477-2479-2481-2483-2485-2487-2489-2491-2493-2495-2497-2499-2501-2503-2505-2507-2509-2511-2513-2515-2517-2519-2521-2523-2525-2527-2529-2531-2533-2535-2537-2539-2541-2543-2545-2547-2549-2551-2553-2555-2557-2559-2561-2563-2565-2567-2569-2571-2573-2575-2577-2579-2581-2583-2585-2587-2589-2591-2593-2595-2597-2599-2601-2603-2605-2607-2609-2611-2613-2615-2617-2619-2621-2623-2625-2627-2629-2631-2633-2635-2637-2639-2641-2643-2645-2647-2649-2651-2653-2655-2657-2659-2661-2663-2665-2667-2669-2671-2673-2675-2677-2679-2681-2683-2685-2687-2689-2691-2693-2695-2697-2699-2701-2703-2705-2707-2709-2711-2713-2715-2717-2719-2721-2723-2725-2727-2729-2731-2733-2735-2737-2739-2741-2743-2745-2747-2749-2751-2753-2755-2757-2759-2761-2763-2765-2767-2769-2771-2773-2775-2777-2779-2781-2783-2785-2787-2789-2791-2793-2795-2797-2799-2801-2803-2805-2807-2809-2811-2813-2815-2817-2819-2821-2823-2825-2827-2829-2831-2833-2835-2837-2839-2841-2843-2845-2847-2849-2851-2853-2855-2857-2859-2861-2863-2865-2867-2869-2871-2873-2875-2877-2879-2881-2883-2885-2887-2889-2891-2893-2895-2897-2899-2901-2903-2905-2907-2909-2911-2913-2915-2917-2919-2921-2923-2925-2927-2929-2931-2933-2935-2937-2939-2941-2943-2945-2947-2949-2951-2953-2955-2957-2959-2961-2963-2965-2967-2969-2971-2973-2975-2977-2979-2981-2983-2985-2987-2989-2991-2993-2995-2997-2999-3001-3003-3005-3007-3009-3011-3013-3015-3017-3019-3021-3023-3025-3027-3029-3031-3033-3035-3037-3039-3041-3043-3045-3047-3049-3051-3053-3055-3057-3059-3061-3063-3065-3067-3069-3071-3073-3075-3077-3079-3081-3083-3085-3087-3089-3091-3093-3095-3097-3099-3101-3103-3105-3107-3109-3111-3113-3115-3117-3119-3121-3123-3125-3127-3129-3131-3133-3135-3137-3139-3141-3143-3145-3147-3149-3151-3153-3155-3157-3159-3161-3163-3165-3167-3169-3171-3173-3175-3177-3179-3181-3183-3185-3187-3189-3191-3193-3195-3197-3199-3201-3203-3205-3207-3209-3211-3213-3215-3217-3219-3221-3223-3225-3227-3229-3231-3233-3235-3237-3239-3241-3243-3245-3247-3249-3251-3253-3255-3257-3259-3261-3263-3265-3267-3269-3271-3273-3275-3277-3279-3281-3283-3285-3287-3289-3291-3293-3295-3297-3299-3301-3303-3305-3307-3309-3311-3313-3315-3317-3319-3321-3323-3325-3327-3329-3331-3333-3335-3337-3339-3341-3343-3345-3347-3349-3351-3353-3355-3357-3359-3361-3363-3365-3367-3369-3371-3373-3375-3377-3379-3381-3383-3385-3387-3389-3391-3393-3395-3397-3399-3401-3403-3405-3407-3409-3411-3413-3415-3417-3419-3421-3423-3425-3427-3429-3431-3433-3435-3437-3439-3441-3443-3445-3447-3449-3451-3453-3455-3457-3459-3461-3463-3465-3467-3469-3471-3473-3475-3477-3479-3481-3483-3485-3487-3489-3491-3493-3495-3497-3499-3501-3503-3505-3507-3509-3511-3513-3515-3517-3519-3521-3523-3525-3527-3529-3531-3533-3535-3537-3539-3541-3543-3545-3547-3549-3551-3553-3555-3557-3559-3561-3563-3565-3567-3569-3571-3573-3575-3577-3579-3581-3583-3585-3587-3589-3591-3593-3595-3597-3599-3601-3603-3605-3607-3609-3611-3613-3615-3617-3619-3621-3623-3625-3627-3629-3631-3633-3635-3637-3639-3641-3643-3645-3647-3649-3651-3653-3655-3657-3659-3661-3663-3665-3667-3669-3671-3673-3675-3677-3679-3681-3683-3685-3687-3689-3691-3693-3695-3697-3699-3701-3703-3705-3707-3709-3711-3713-3715-3717-3719-3721-3723-3725-3727-3729-3731-3733-3735-3737-3739-3741-3743-3745-3747-3749-3751-3753-3755-3757-3759-3761-3763-3765-3767-3769-3771-3773-3775-3777-3779-3781-3783-3785-3787-3789-3791-3793-3795-3797-3799-3801-3803-3805-3807-3809-3811-3813-3815-3817-3819-3821-3823-3825-3827-3829-3831-3833-3835-3837-3839-3841-3843-3845-3847-3849-3851-3853-3855-3857-3859-3861-3863-3865-3867-3869-3871-3873-3875-3877-3879-3881-3883-3885-3887-3889-3891-3893-3895-3897-3899-3901-3903-3905-3907-3909-3911-3913-3915-3917-3919-3921-3923-3925-3927-3929-3931-3933-3935-3937-3939-3941-3943-3945-3947-3949-3951-3953-3955-3957-3959-3961-3963-3965-3967-3969-3971-3973-3975-3977-3979-3981-3983-3985-3987-3989-3991-3993-3995-3997-3999-4001-4003-4005-4007-4009-4011-4013-4015-4017-4019-4021-4023-4025-4027-4029-4031-4033-4035-4037-4039-4041-4043-4045-4047-4049-4051-4053-4055-4057-4059-4061-4063-4065-4067-4069-4071-4073-4075-4077-4079-4081-4083-4085-4087-4089-4091-4093-4095-4097-4099-4101-4103-4105-4107-4109-4111-4113-4115-4117-4119-4121-4123-4125-4127-4129-4131-4133-4135-4137-4139-4141-4143-4145-4147-4149-4151-4153-4155-4157-4159-4161-4163-4165-4167-4169-4171-4173-4175-4177-4179-4181-4183-4185-4187-4189-4191-4193-4195-4197-4199-4201-4203-4205-4207-4209-4211-4213-4215-4217-4219-4221-4223-4225-4227-4229-4231-4233-4235-4237-4239-4241-4243-4245-4247-4249-4251-4253-4255-4257-4259-4261-4263-4265-4267-4269-4271-4273-4275-4277-4279-4281-4283-4285-4287-4289-4291-4293-4295-4297-4299-4301-4303-4305-4307-4309-4311-4313-4315-4317-4319-4321-4323-4325-4327-4329-4331-4333-4335-4337-4339-4341-4343-4345-4347-4349-4351-4353-4355-4357-4359-4361-4363-4365-4367-4369-4371-4373-4375-4377-4379-4381-4383-4385-4387-4389-4391-4393-4395-4397-4399-4401-4403-4405-4407-4409-4411-4413-4415-4417-4419-4421-4423-4425-4427-4429-4431-4433-4435-4437-4439-4441-4443-4445-4447-4449-4451-4453-4455-4457-4459-4461-4463-4465-4467-4469-4471-4473-4475-4477-4479-4481-4483-4485-4487-4489-4491-4493-4495-4497-4499-4501-4503-4505-4507-4509-4511-4513-4515-4517-4519-4521-4523-4525-4527-4529-4531-4533-4535-4537-4539-4541-4543-4545-4547-4549-4551-4553-4555-4557-4559-4561-4563-4565-4567-4569-4571-4573-4575-4577-4579-4581-4583-4585-4587-4589-4591-4593-4595-4597-4599-4601-4603-4605-4607-4609-4611-4613-4615-4617-4619-4621-4623-4625-4627-4629-4631-4633-4635-4637-4639-4641-4643-4645-4647-4649-4651-4653-4655-4657-4659-4661-4663-4665-4667-4669-4671-4673-4675-4677-4679-4681-4683-4685-4687-4689-4691-4693-4695-4697-4699-4701-4703-4705-4707-4709-4711-4713-4715-4717-4719-4721-4723-4725-4727-4729-4731-4733-4735-4737-4739-4741-4743-4745-4747-4749-4751-4753-4755-4757-4759-4761-4763-4765-4767-4769-4771-4773-4775-4777-4779-4781-4783-4785-4787-4789-4791-4793-4795-4797-4799-4801-4803-4805-4807-4809-4811-4813-4815-4817-4819-4821-4823-4825-4827-4829-4831-4833-4835-4837-4839-4841-4843-4845-4847-4849-4851-4853-4855-4857-4859-4861-4863-4865-4867-4869-4871-4873-4875-4877-4879-4881-4883-4885-4887-4889-4891-4893-4895-4897-4899-4901-4903-4905-4907-4909-4911-4913-4915-4917-4919-4921-4923-4925-4927-4929-4931-4933-4935-4937-4939-4941-4943-4945-4947-4949-4951-4953-4955-4957-4959-4961-4963-4965-4967-4969-4971-4973-4975-4977-4979-4981-4983-4985-4987-4989-4991-4993-4995-4997-4999-5001-5003-5005-5007-5009-5011-5013-5015-5017-5019-5021-5023-5025-5027-5029-5031-5033-5035-5037-5039-5041-5043-5045-5047-5049-5051-5053-5055-5057-5059-5061-5063-5065-5067-5069-5071-5073-5075-5077-5079-5081-5083-5085-5087-5089-5091-5093-5095-5097-5099-5101-5103-5105-5107-5109-5111-5113-5115-5117-5119-5121-5123-5125-5127-5129-5131-5133-5135-5137-5139-5141-5143-5145-5147-5149-5151-5153-5155-5157-5159-5161-5163-5165



**HOW TO BUILD
A HOME**



CONTENTS

	PAGE
PREFACE	v
THE LAND AND GRADING	1
THE BUILDING	7
INSIDE THE HOUSE	31
THE COMFORTS OF HOME	54
FINISHING WORK	64
A PRACTICAL EXAMPLE	72
SAMPLE SPECIFICATIONS	85
SOME GENERAL FORMS OF CONTRACT FOR THE EN- TIRE WORK	130
RECAPITULATION	142
AUTHORITIES CONSULTED	153
INDEX	155

THE LAND AND GRADING

IN the following pages few suggestions will be found regarding what may be called ornamental architecture. Tastes vary, and each must and will follow his own inclination. It has been the aim of the writer to direct attention to those practical details which concern comfort, convenience, structural strength, and safety from fire, leaving entirely out of the question all discussion of such matters as colors of paints, hardwood finish, and style of architecture. Most of the suggestions will be found available, whether the building be brick, stone, or frame, or whether the style be Colonial or Romanesque or Byzantine or "Queen Anne in front and Mary Ann behind."

Select a competent architect; not merely one of taste and experience, but one who combines with these recommendations the somewhat rare quality of systematic preservation of discovered facts, with the view to improving and readjusting his blanks for plans and specifications. It is unsafe to rely upon memory, and the architect who neglects to make memoranda of his mistakes and discoveries in the course of his practice is a safe one to avoid.

Selecting an architect

Under no circumstances should a man of any other profession be his own architect. It is an old saying that a man who is his own lawyer has a fool for a client, and it may safely be asserted that the man who is his own architect will have a house whose mistakes will cost him more than twice the fee of a competent expert.* Select an honest architect, one who will not accept a commission from contractors or dealers in materials.

It will be well to stipulate that the architect is to employ a competent inspector, who is to be on the ground daily and see that every detail is attended to. It is not necessary to have a high-priced man for this work; most bright young men are thoroughly capable of undertaking it if they be good mechanics. Defective work is soon covered up if the contractor is dishonest, and casual visits of the architect himself are not sufficient to insure protection against fraud or errors. It should be remembered, too, that mistakes, even if honest, sometimes get to a point where correction is difficult, if not impossible.

The advice of a sensible, practical woman who is a thorough housekeeper should also be regarded as indispensable. Therefore, if a man's wife answers this description of helpmeet, her husband will make a serious mistake if he fails to consult her at every step and secure her revision of his plans, especially in the important matter of closets, arrangement of kitchen, butler's pantry, etc. Her experienced and practical eye will discover defects which would never occur to him. It should be remembered that she occupies the house dur-

* "One of the most difficult portions of an architect's business is precisely that which amateurs usually imagine to be the easiest—the superintendence of the work connected with a dwelling house."—Mr. T. M. Clark in "Building Superintendence," an instructive and valuable treatise.

ing the greater portion of the daylight hours, and it would be strange if she should not know proportionately more about what is needed for comfort and convenience than the head of the house. Her practical knowledge will be invaluable to him; she will see things that both he and the architect overlook: the need of a door here, a window there, a closet in this place, the fault of a door hung on the wrong side in another; such objectionable features as steps between the butler's pantry, dining-room, and kitchen, the floors of which should always be on the same level, to prevent the stumbling of servants with dishes, etc., etc. Women would make admirable architects, especially for dwelling-houses, if they were able to climb ladders and properly supervise buildings in process of construction.

Tell your architect the amount you are willing to spend. It is claimed that it is best to put one's figure at twenty-five per cent. less than the maximum amount contemplated, but this theory presupposes an incompetent or dishonest architect, and it is better to have no dealings whatever with such a one. Employ an honest man and be frank with him. A tricky man will assume that you are naming a less figure than you are willing to pay, and probably add fifty per cent. to it.

If the site is level and well drained, little needs to be done in the way of grading except to dig the cellar. If, however, the building is to be on a hill-side, whatever grading is necessary to *Lay of the land* secure a level site and the necessary terraces should be done before erecting the structure and at the same time that the cellar is being excavated. At such time the work can be prosecuted at much less expense than after the building has been erected, and after

it will stand as an obstruction to the removal of earth by the easier method of carts or earth-scoops.

It will be found economical in the end to consult a surveyor as to levels; and it is perhaps unnecessary to suggest, in the case of a house built upon a hillside, that it will be economical of excavation, and also of level ground, to arrange the long way of the house parallel with the face of the hill. In other words the style of the house should be wide rather than deep. This will save in expensive retaining walls and sod-work.

If the house is to be a summer home, its arrangement should have reference to the direction of the prevailing breeze of the summer months, and the

Prevailing winds dining-room should be on the side so indicated, for the obvious reason that it must necessarily be occupied at least three times a day, and should for this reason be the coolest and pleasantest room in the house, it being remembered that it is not necessary on warm days and evenings to stay in the library or drawing-room, but it is possible and preferable to seek relief from the heat on the piazza. In most localities the easterly and southerly exposure is the pleasantest side of a house.

For the same reason do not place your kitchen too near your dining-room; the butler's pantry and store-room should be between, not only on account of heat, but on account of flies and cooking odors. Even if a brick wall separates the kitchen from the dining-room, if the range or flue of the kitchen be next the dining-room, the latter will be heated to an uncomfortable degree. A kitchen under the dining-room is decidedly objectionable in a summer home.

The top soil is valuable, and should be carefully removed to one side (where it will not be in the way.

necessitating subsequent removal), to be readjusted upon the terraces or other surfaces for support of grass, flowers, and other vegetation. It is often foolishly mixed up with the clay and sand, necessitating the purchase afterward of good soil when top dressing is necessary.

Top soil

In the case of buildings on side-hills, very careful attention should be given to drainage, and the waterways should be intelligently studied by observation during storms before planning the gutters, road-boxes, and sub-

Drainage, gutters,
etc.

soil piping, if any. Either of the two systems—surface gutters or subsoil pipes—should be sufficient in capacity, each independently of the other, to carry off the water of a heavy rainfall or cloud-burst; but reliance should not be placed on the road-boxes and covered pipes alone, as road-boxes, even if of the best quality, are liable to be stopped up by dried grass or leaves. The surface gutters should be connected, therefore, so that a complete system of surface drainage for carrying off the water may be secured in addition to the underground pipes. Subsoil pipes, where used, should increase in size from the top of the hill to the bottom, commencing with four- or five-inch and increasing to six-inch, eight-inch, etc., not less than twelve-inch or larger pipe being used at the foot of the hill. While it is true that the smaller the pipe the more likely is it to clear itself and to prevent the accumulation of sand and rubbish, it should be remembered that its capacity must be equal to the maximum volume of water in exceptional storms, or damage will result.

Care should be taken to insure a safe flow of the water from the house on all sides, and it may be well to have a gutter two or three feet wide around the walls of the house, of brick, stone, or concrete, underneath the sod-

ding, so that in case of a cloud-burst and the washing away of the soil the gutter would then throw the water clear of the house walls. Blind drains

Grading of broken stone around the foundations are in some locations necessary.

Where the ground is damp or springy it is well to lay a course of dry stones on edge, at least six inches in width, the cellar bottom to be graded before the stones are laid, so as to pitch the water to holes left through the foundation walls, and around the outside of the walls on the exterior of the building. A dry stone drain should be laid as low as the foundation, so as to take the drip of the surrounding ground, the whole being connected with the drain on the outside of the building, so that the water may be carried off to a cesspool or to lower ground. If the house be in the city and the cellar below the level of the sewer, it can be drained to a cesspool and afterward pumped or siphoned out.

Where the building to be erected is within the jurisdiction of a municipal or State Building Department, it is

Building Department

best to have the plans approved by the department before awarding the contract. This precaution will cost nothing,

and may save charges for extra work. If such a clause as the following, "All work must be done in accordance with the requirements of the Department of Buildings, and any changes in the work made by the order of said department will form a part of this contract, and will be done by the contractor without cost to the owner," is relied upon to protect the owner, he may rest assured that the contractor will make due allowance in his estimate price for all possibilities, and take the benefit of any doubt, when in fact there need be no doubt.

THE BUILDING

IT is wise to have the cellar under the entire house. It will cost little more than to dig a smaller cellar, and will insure not merely greater storage room (always convenient and desirable), but better ventilation, as well as dryness, in the house itself.

Money well spent
on the cellar

The cellar ceiling should not be less than seven feet high—better eight feet. It is mistaken economy to have a low-studded cellar. The ceiling should be plastered on metallic lathing. This will be an effectual fire-stop in case of fire starting in the cellar, where fires frequently originate, and will hold a fire long enough to insure the escape of a family.

The side-walls should be whitewashed with two good coats of lime-wash.

The floor should be covered with not less than three inches of good concrete, and a final coat of one inch of Portland cement and good sharp sand, in the proportion of one of cement to two of sharp sand. The concrete should be mixed in the following proportion: one part of some good domestic cement, one part clean, sharp, grit sand, and five parts of best clean, coarse gravel, thoroughly washed, or clean, broken stone (small enough to pass in all directions through a two-inch ring)—the lat-

ter preferable; all to be, by measure, thoroughly mixed dry, and water added afterward. It is necessary to have the stone or gravel carefully washed, so that the cement may "bite" thoroughly, as any soil or dirt adhering to the stone will prevent a proper union.

To secure a thoroughly dry cellar where the surrounding soil is damp, it is said that a damp-proofing of three-ply sized paper and asphalt under the concrete is an important and economical precaution. It is also well, as already stated, to have blind drains around the footing of the foundation. These are made by broken stone pounded in, through which the water finds its way to some lower and safer point.

It is well to have a drain at some point in the cellar, running out under the walls, with a perforated iron plate or bell-trap, so that any unusual flood of water in the cellar would be immediately carried away beyond the point of danger or annoyance. A four-inch cast-iron pipe, carried out under the wall in this way when the cellar is being built, the floor being inclined slightly to the drain, will cost very little and may save serious trouble, especially in the case of buildings on side-hills. Do not connect it with the sewer-pipe.

It is mistaken economy to lay cellar walls in other than cement mortar, or to neglect concreting the floor. It is an old saying that a wet cellar is better than a damp cellar, and that "a damp cellar weaves shrouds for the upper chambers."

It is desirable, in getting estimates, to have the specifications provide for coal-bins, closets, etc., in cellar. Attention to such matters will save considerable money as compared with what the expense will be if left for subsequent contracts.

It is well to have a room for milk, food, etc., in the cellar, made of a light framework of wood covered with a wire netting,—either the green netting or copper netting; the latter is better on account of immunity from rust,—the interior fitted with shelves. It will cost little, especially if included in the specifications and estimate for the house.

Cold room

The storage of fire-wood in the cellar is objectionable on account of harboring insects and the danger of ignition from the furnace, etc.

The underpinning of the house (by which is meant that portion of the wall above the surface of the ground) should be sufficiently high (not less than eighteen inches) above the surface to afford windows at least sixteen inches wide for lighting the cellar—an important matter—and also to insure a dry wall for the wooden sill to rest upon, so that water may not be forced through in a beating rain and the sill decayed—a serious matter. In city houses “areas” should be constructed to secure light for cellar windows.

Underpinning

It may be well to explain here that what is meant by “sharp sand” is a sand the particles of which have facets with sharp edges, easily discerned by a good eye, or by the use of an ordinary magnifying-glass, as contrasted with smooth, rounded grains, such as are usually to be found in sand taken from the beds of rivers, where continual abrasion rounds the surfaces. River sand is seldom fit for mortar. On the sharpness of the sand-grains depends the tenacity of the mortar, the resulting mixture of sharp sand and lime being a silicate of lime, a chemical union,

Sharp sand

and not a mere mechanical mixture such as ignorant mortar-mixers usually prepare. The mixing of mortar is too frequently intrusted to an ignorant laborer without instruction or supervision. It should be carefully watched.

The sand should be clean and free from loam. It should not soil the hands when rubbed in the palm, and should have a gritty sound when rubbed.

Trenches two feet deep should be dug under all foundations, and dry stone rammed in for footing courses eighteen inches deep, on which the

Foundation walls foundation wall should be laid.

Foundation walls should not be less than twelve inches thick if of brick, nor less than eighteen inches if of stone. If the walls of the building throughout are of stone or brick, the walls of the foundation should be four inches thicker, i.e., sixteen and twenty-two inches. In the case of a damp soil the outside of the bricks should be covered with a thick coating of liquid asphalt or pitch, as bricks are porous and absorb moisture. It will be well to apply in two coats after a good plaster coating of Portland cement has also been applied. Be careful to see that the bricks are well burned. This can be determined from their appearance, especially when broken in two. "Pale," improperly burned bricks are useless for foundations, or, for that matter, for any purpose.

The foundation walls, if of stone, should be carefully laid by competent stone-masons, each stone to be laid on its natural bed; and whether of stone or brick, only cement mortar should be used for all walls below ground. This is very important. Let no one persuade you to the contrary. The building law requirement of New York city for "cement mortar" is one part of cement to three

of sand. I think this hardly rich enough for foundation walls below ground, or for covering concrete floors, one to two being preferable. Neither brick nor stone should be laid in freezing weather, especially in weather alternately freezing and thawing; but if it be unavoidable to lay brickwork in freezing weather, it is claimed that a mortar consisting of three parts of lime to one of Portland cement, with ten parts of sharp sand, will stand well, the bricks being laid dry and warm. Most experts prefer cement mortar, the bricks laid dry and warm. The addition of about two per cent. of salt to the water used will improve the mixture. Sugar also strengthens mortar. Some experiments made in Riga, Russia, recently indicated that bricks laid with Portland cement and five parts of sand, the bricks being laid dry and warm, insure good results.

A New York builder of large experience, and for whose judgment I have great respect, writes me, after reading proof of this book: "I have found, during many years of experience, that good cement, with dry bricks, is the proper material for mortar in freezing weather—never lime." I am of his opinion, and find most other experts think so too.

It is the generally accepted opinion that stone is a better material for foundations below ground than brick; but stone is seldom laid properly, and good stone-masons are scarce. It is a quite common practice to let the stone project beyond the rear line of the wall, and sometimes to break it off with a hammer after the wall is dry—a most vicious practice. Moreover, sufficient mortar and cement are not always used. Taking into account that it is easier to lay bricks and bring them to a proper face, it is questionable whether a brick wall well laid in

cement mortar, plastered with Portland cement on the outside, and afterward covered with two coats of liquid asphalt, is not, on the average, a better wall than one of stone. It certainly is unless the latter is exceptionally well laid. It should be remembered also that stone, especially limestone, is liable to disintegrate if water to extinguish fire is thrown upon it while hot. For this reason stone piers and stone columns may be dangerous in cellars; they are particularly so in warehouses.

Where these are necessary for "retaining" or sustaining earthen banks, they should be constructed of heavy stone, what is known as "two-man"

Retaining-walls stone (requiring two men to handle it), and the wall should be "battered"

back; that is, it should lean back against the bank, and not be constructed with a plumb or vertical face. It should be one fourth of its height in thickness, but at least two feet six inches thick at the bottom if seven feet high, and should go at least one foot below the level of the ground and should be laid in cement mortar; but the middle of the wall should be laid dry for a large portion of its face, so that any water accumulating behind it may drain off, and not freeze to throw out the wall. Some experts prefer to build the entire wall in cement mortar, leaving "weepers," so called, or small drain-holes, through the wall every four feet at the bottom. The upper portion of the wall two or three feet from the top should also be laid in cement, and the whole should be coped with stone laid in cement mortar, or the wall should have a coping of cement in the proportion of one part Portland cement to two of sharp sand, smoothly troweled. Retaining-walls, as a rule, should not be less than eighteen inches in thickness at the top.

It is the generally accepted opinion that the healthiest dwelling-house for the climate of America is one of frame, especially where the building is located near enough to the sea-shore to be subject to the dampness incident to the location—an important consideration.

There are two methods of framing the beams, joists, and vertical timbers of wooden dwellings, viz., the "braced" frame and the "balloon" frame, illustrated in later pages.

Frame dwellings
Framing and timber work

In the braced frame "girts," or beams for carrying the floor-beams of the floors above the first, are framed into the corner posts (which should extend to the wall-plate), those supporting the ends of beams being dropped to secure a level with the side-girts (for this reason they are called "dropped girts"). On these girts the studs of the outer wall and partitions are framed, so that each story has a separate set of studs. At all angles, also, there are angle-braces, tending to strengthen the structure. The whole matter is fully illustrated in later pages. (See Index.)

In the balloon frame the studs as well as the corner posts are carried from the "sill" (i.e., the flat timber which lies along the top of the foundation wall) continuously to the wall-plate (usually called the "plate") at the top of the wall; and the floor-beams of the second and third stories are carried by pieces, two by six inches, called "ribbons," spiked securely to the studs. They are stronger if let into the posts and studs. This form, or balloon frame, costs somewhat less than the braced frame, and if well braced with long struts and interties is strong enough for all practical purposes. Indeed, for country houses it forms a very rigid structure.

In the case of both the braced and the balloon frame the outer or "inclosing" studding is sheathed with sheathing-boards for the reception of the shingles or clapboards, and if this sheathing is put on properly it is an additional element of strength. The whole matter may be understood by referring to the diagram, page 91.

As already stated, the vertical timbers are in single lengths from the sill to the wall-plate. Where it is necessary, however, to splice two pieces of joist together it should be done by "fish-plates," so called, or splices of inch board, three feet in length, nailed, like splints for a broken limb, securely on both sides of the splice. If the bearing is true and square a spliced stud is strong enough, but there should not be more than two or three in a side-wall or partition.

It is important to avoid the footing of joists or partitions on floor-beams, so as to have as little shrinkable timber as possible in the line of a vertical support. Wherever possible, therefore, the studs should pass down between the floor-beams and foot upon the sill itself, or upon the cap of a partition below. Where the stud of one partition foots upon a brick or stone wall, and the studs of a parallel partition foot upon wooden girders or floor-beams, unequal settling will occur, due to unequal shrinking, throwing the floors out of level and cracking the plastering. The architect and builder should provide for this, as it can easily be remedied by letting the studs into the girder, or by building up one side or the other so that equal quantities of shrinkable timber come under both sets of studs. This is a very important matter, sometimes overlooked. It has been provided for in the accompanying specifications.

Where it is necessary for a partition to foot upon a

tier of floor-beams, it should foot upon a sole or strip of yellow pine one inch thick, of the width of the studs, the studs being so arranged that each stud will come over a beam. The less timber under a stud, for reasons already explained, the better, to avoid the effects of shrinking.

Each pair of floor-beams should also be "cross-bridged" at intervals of seven feet in their length. (See page 92.)

The studs of partitions should be bridged or braced, as this adds to their strength and very little to the expense.

The framing of the roof should be carefully attended to, as suggested on page 28.

A very durable side-wall, as well as a tasteful one, is a shingle wall. Cedar shingles change with the weather to an artistic gray tint which is decidedly pleasing to the eye; but creosote stains of various shades of color are obtainable, so that the owner may gratify any preferences he may have for other colors than "weather gray."

Side-walls

If creosote stains are to be used, the shingles should be dipped and allowed to drain dry into a gutter or tub before being nailed on the roof.

As a preparation for the shingle finish, the outside of the house should be sheathed with boards,—hemlock will answer,—preferably not over six inches

wide. The sheathing should be tongued and grooved and planed on one side. It

Sheathing

costs little more and is a great advantage, not merely because more weather-proof, but because the lumber is planed to a uniform thickness. It should be driven closely together before nailing. Differences of opinion prevail as to whether sheathing-boards should be attached to the upright timbers or studs by being nailed horizontally or diagonally. It is claimed that where side-

walls are covered with clapboards the joints between the clapboards may sometimes be coincident with the joints between the sheathing-boards underneath. With shingled side-walls it makes little difference. I am inclined to think, after careful investigation of the subject and consultation with experts, that with shingled walls especially greater strength will be secured in the framework of the house if the boards are nailed horizontally to the upright studding.* On this outer sheathing should be fastened a heavy quality of waterproof building paper, and upon this surface the shingles should be carefully nailed with galvanized-iron nails. They cost little more than the ordinary cut nails, while they will last much longer. Probably fifteen dollars, in the case of a good-sized house, would pay the extra cost of using galvanized nails.

An admirable and inexpensive feature of either a summer or winter house is "back-plastering," by which is meant an extra coat of rough brown plaster on lath between the outer sheathing and the inner or finish plaster, thus securing two air-spaces. The lath should be furred out from the sheathing so as to secure a good "clinch" or "key" to the plaster, and an air-space between it and the sheathing. Such a house will keep out the heat of summer and the cold of winter, while the extra expense will not be great, and will be fully justified

Back-plastering in
wooden houses

* Probably, for the same amount of material, a dry-goods packing-box will show as much structural strength as any form of building. Its side-boarding is nailed horizontally. I doubt if any one would claim that it would be as strong if it were nailed diagonally. A properly constructed building, with horizontal sheathing and the framework securely braced and nailed, is sometimes turned end over end by a wind-storm without breaking it to pieces, in tornado sections.

by the comfort secured for the entire lifetime of the building. Under no circumstances should it be omitted. It is customary in some localities to fill in the space between the inner plastering and the outer shingle sheathing or clapboard finish with bricks and mortar; lime mortar, not cement mortar, should be used, on account of the danger of dry-rot. Back-plastering, while not so effective a fire-stop, is less expensive, and the two air-spaces form a good non-conductor.

Probably no subject deserves more thoughtful consideration at the hands of architects, builders, and underwriters than that of improving the fire-resisting properties of ordinary frame or brick dwellings, especially

Fire-stops in hollow partitions, floors, etc.


in isolated locations where they are beyond the reach of fire-departments. Under present methods a frame dwelling, or, for that matter, a brick dwelling of ordinary construction, once on fire, is seldom saved. With defective floors, hollow partitions, open staircases, and hollow spaces in side-walls from cellar to roof, affording drafts and flues for carrying flames, modern dwelling-houses are actually constructed on the principle of lungs for breathing flame. Even if the outer walls are of brick or stone they do not retard combustion, since the conditions for it are simply those of an ordinary stove, whose contents are not more judiciously arranged to insure rapid combustion than are such interiors. It rarely happens that a fire starting at night in the cellar or in the lower story of a dwelling is extinguished short of loss of life and property. This ought not to be the case, as it is due to criminal indifference to precautions which are comparatively inexpensive and which ought naturally to occur to any intelligent mind.

Even a wooden dwelling may be so constructed, at slight expense, as to resist the progress of fire, and prove slower in burning than the average brick or stone structure. It should be remembered that fire finds rapid runways from the cellar or lower portions of a building to the garret or roof through the hollow spaces behind furring-strips nailed for plastering on brick walls, and behind the plastering and between the studs or upright joists or timbers of the structure. If not provided with a draft, fire makes little progress, and if not supplied with air, will go out. It is therefore only necessary to cut off all of these upright air-spaces, which otherwise become flues for its rapid progress, so that there will be a fire-stop at every floor, and it can be inexpensively secured.

At each story where stud-walls or partitions rest on walls or other partitions, the spaces between the floor-joists immediately under such walls or partitions, and between the sides of such joists, and to a line six inches above the top of such joists, should be filled solid or flush, with face of plastering on both sides, with bricks laid in mortar, or mortar mixed with proper proportions of plaster of Paris to harden it; and if such studs or partitions rest on solid timber or joists for the whole length thereof, such fillings should be placed from the top of such joists to the same height as above specified, or a strip of tin or galvanized iron at least one inch wider than the width of said studding, and continuing under the footing of such walls or partitions, may be substituted for the filling above described where there is no partition or wall under.

The building law of New York requires that in all furred walls the course of brick above the under-side and below the top of each tier of floor-beams shall project

the thickness of the furring, more effectually to prevent the spread of fire.



FIRE STOPS IN FLOORS AND PARTITIONS.

A wooden house constructed in this manner, with all air-passages cut off, with metallic lathing for the ceilings, and salamander, asbestos, or other fire-proof material between the floors, will resist a fire much longer than ordinary brick or stone buildings in which such simple and inexpensive but most important precautions are omitted. It will not cost one hundred dollars extra to construct a building in such a way that ample time would be secured for the escape of a family even if a fire should start in the night, and it is almost criminal to erect buildings for the habitation of human beings on modern fire-trap principles.

Take, for instance, the simple precaution of throwing a few shovelfuls of ordinary lime-mortar into the hollow spaces at the feet of ordinary "fore-and-aft" partitions, such as those which divide the rooms from the hallways of dwellings; it would seem that a conscientious builder, even if he were not paid under his contract for taking this precaution, would not neglect it. If at every floor he should let his workmen cast in the broken bits of brick, loose mortar, and incombustible material which he afterward carts away at an expense, he would make a

partition almost as fire-proof as if filled in with brick from top to bottom, it being borne in mind that the danger of an ordinary partition lies, not in the fact that it is not filled in solidly with brick, or that it has an air-space, but that this air-space extends from one story to another, creating a flue for a draft. This matter is more fully explained by the accompanying illustration on page 19.

It is an admirable precaution to have a two-inch stand-pipe from the tank in the attic, with one length of fire-hose, and a nozzle attached, at each floor, near the staircase. This may insure the extinction of a fire in its incipency at a time when a little water, promptly applied, is worth a whole fire-department later. This suggestion comes to me, strange as it may seem, not from an underwriter, but from a practical builder. The stand-pipe and the hose may be covered in with a neat cabinet finish, or the attachment may be in the bath-room, with a sufficient length of hose to reach any portion of the floor.

Filled pails of water are admirable precautions also. There should be a supply of these in the attic, so that in case plumbers or other mechanics are working with fire-pots about the water-tank or on the roof, the water may be available, care being taken to empty them in case the house is closed during cold weather. A little salt in the water, however, will tend to prevent it from freezing in ordinary low temperatures. Few persons realize how efficient for extinguishing fire are ordinary pails of water, with long-handled tin dippers, one of which should be provided with each pail. Water can be easily thrown on the roofs of ordinary dwellings or to remote corners of an attic.

Floor-beams are usually only two inches thick and ten inches wide, merely two-inch planks on edge, but the extra cost of using timber three inches thick and twelve inches wide for floor-beams, Floor-beams or joists * set sixteen inches on centers (i.e., sixteen inches from center to center or thirteen inches apart), will be fully justified by the stiffness of the floors, the prevention of cracks in plaster ceilings and in walls, due to vibration, and also by the resistance to fire which such beams would present, withstanding combustion sufficiently long, as a rule, to enable the family to escape. Floor-beams, moreover, have to be cut from one to two inches deep for the passage of gas-pipes, etc. These often invade a two-by-ten-inch beam to the point of danger. Georgia yellow pine is the best material for beams, but either spruce or hemlock makes fairly good floor-beams, and, if well seasoned, neither is apt to twist seriously, especially where of the size recommended. I think yellow-pine beams well worth the difference in cost, however.

It is best to support interior girders in cellars with eight-inch brick walls. If supported by girders on piers these should be at least twelve inches square—sixteen inches is better.

Flooring, where the extra expense (and it is not great) is not objectionable, should be double. The lower floor may be of hemlock or of other cheap wood, while the upper should be of Georgia Floors pine (unless oak, maple, or other hardwood floors are preferred). Where comb-grain pine is specified (so named because the grain is straight and in appearance like the artificial graining done by the grain-

* In some sections of the country they are called joists altogether.

er's comb) the best results may be secured as to wear and appearance. If wood-filled and then waxed it makes a neat border for rugs. This arrangement of the grain is secured by sawing the logs quartering, so that the growth-rings are seen on edge, instead of sawing the log by cuts parallel with the tangent of the circumference, by which process the cuts nearest the bark are less valuable and the planks less hard as they approach the bark. Of course comb grain, while more durable, is more expensive. If the entire floor is to be covered with matting or carpet, the ordinary North Carolina pine, which has been deprived of its pitch for rosin, turpentine, etc., is cheaper; it is harder and better for floors than either spruce or white pine. It should be clear of knots and free from sap, shakes, etc.; that is to say, the sap side or softest side of a board, i.e., that side which in the tree comes nearest the bark, should not be the top or exposed surface (although it is hardly necessary to examine for faults where comb grain is specified in the contract). Where a piece of flooring is planed on the sap side it will sliver under the foot and wear out rapidly, soon becoming unsightly. These objectionable pieces may be easily detected, as the growth-rings of the tree show plainly if the wrong or sap side of the board is the one which has been planed. A careful mechanic will not make the mistake of planing a plank on the sap side, but enough of such carelessly planed lumber is to be found in every lot to warrant careful assorting. The specifications should require "the best-seasoned, clear, comb-grain Georgia pine, free from sap, shakes, and knots, seven eighths of an inch thick, not over two and one half inches in width, tongued, grooved, planed, and blind-nailed," i.e., the nails being driven in the tongue of each

piece as the floor is laid, so that the head of the nail does not show in the top of the floor.

Flooring should be carefully dried; the best kiln-dried or time-seasoned material only should be used. Care should be taken, also, to protect it from the weather after it has been brought on the premises, for even if seasoned, if it becomes wet afterward from rain-storms it may be seriously injured and develop faults long after the floors are laid. It is so easy to protect it from rains that neglect to do so is inexcusable.

The under-floor planks should be nailed diagonally, but, if parquet flooring is to be used, crosswise of the beams.

It will be found advisable to put between the two floors—the lower of hemlock and the upper of pine—a layer of asbestos paper or of salamander. The latter is both waterproof and fire-resisting; it will delay the progress of fire through a floor for hours. It is made of strong, tough building-paper board, coated with a waterproof and fire-proof cement on both sides. When finished it is not unlike a sheet of slate. It is not expensive, and forms an excellent filling for floors, and has some deafening properties.

While the lumber specified for the floors should all be according to standard, that for the main hall, library, and drawing-room should be the pick of all for obvious reasons, and a builder taking proper interest in his work would naturally see that these floors were carefully selected. The “cull” lumber (although strictly there should be no choice) should be put in the closets, store-rooms, and upper or attic rooms. It is therefore desirable when the flooring lumber is on the ground to have it carefully sorted, so as to take the choice pieces for the best rooms.

The floor of the kitchen need not be of clear lumber, but should be of the best quality of hard lumber, free from sap and shakes. It should be finished in oil so that it can be scrubbed often. Many housekeepers prefer linoleum on kitchen floors.

It is advisable to have a small "quarter-round" or other molding where the base-boards join the floors, to insure clean and easy sweeping.

There are numerous plans for deafening floors so as to prevent sound from traveling from story to story. One

of the best is to have a layer of cinders
Floor-deafening and concrete underneath the top floor,
carried by thin deafening-boards resting
on cleats fastened on the side of beams or joists as
shoulders. The mixture for this purpose should be one
of cement, two of sand, and five of well-screened cinders
mixed with as little water as possible. Mineral wool is
also available for this purpose. The most important floor
of all to deafen, however, is the one which, strangely
enough, is generally overlooked by builders and archi-
tects, viz., that on which the servants' rooms are located.
The noise made by servants is generally more disturbing
than that made by the family, because of their earlier
rising.

THE PIAZZA should be wide, not less than twelve feet,
depending, however, upon size of house. It will cost

little more than a narrower one, and
Piazza will add materially to the pleasure of
the home. It is well to carry it, for a
short distance at least, around each of the two sides of
the house, as well as in front, so as to secure sheltered
nooks no matter which way the wind may blow or the
sun may shine. If carried entirely around the sides it

will darken the first-floor rooms and prove objectionable on that account.

Under no circumstances should sap lumber be allowed in a piazza floor, as it decays when exposed.

In finishing the ceilings, eaves, and fascia of the piazza, resting-places should be avoided where birds, especially sparrows, would be tempted to construct nests.

The flooring should be of Georgia pine, well seasoned, not more than two and one half inches in width and not less than one and one eighth inches thick when dressed; and the joints, tongued and grooved, should be laid in lead paint mixed thick. There should be a fall of at least three inches between the front of the piazza and the back, if twelve feet wide, or one fourth of an inch to the foot, to carry off rain-water.

The flooring of the piazza should be carefully "blind-nailed," i.e., nailed in the tongue of each piece, and at its junction with the house, especially if it is a stone house, should be carefully calked to prevent leaks. It is best to dress the stone to a smooth edge at the piazza level to insure a water-tight joint.

It is advisable, if the outside steps of the piazza are of wood, to have them bored with small auger-holes in some ornamental pattern, to insure the running off of rain-water, which otherwise will stand on the steps after they have been warped into curved shapes by the sun, and lead to their decay. If this precaution is provided for in the specifications it will save half the expense of having it done later.

Probably a better method still is to make the outside steps of strips one and one fourth inches thick and two inches wide, placed one eighth of an inch apart and blind-nailed, the outer strip being three inches wide, to allow

for the projection or nosing. This will obviate the necessity for boring auger-holes, and will secure a dry step which will not warp.

The piazza columns, where they set upon the piazza, are apt to rot from moisture getting underneath. It is best to putty the joints between the base of the pillar and the floor-plank for this reason.

THE ROOF may be either of slate, tin, copper, or shingles, according to the taste or purse of the owner. If copper

is used tinned copper is necessary for soldering. If shingles are used they will be improved both as to fire-resisting

Roof properties and leakage if laid in mortar. This is expensive, however. Slate should also be laid in mortar; it forms a good bed and tends to insure against breakage of the slates. The slate should be laid with not more than seven inches "to the weather," even if nine by eighteen inches in size (i.e., with not exceeding seven inches of each slate uncovered by the one above). A difference of opinion exists as to whether small slates or large slates, nine by eighteen inches, are the best. Probably nine by eighteen inches are preferable. The expense of rounding the points is not justified by the improvement, if any, in the appearance of the roof. Slate makes a hot roof in summer, but if laid in mortar, which is possible where the roof is slated in non-freezing weather, the upper rooms of the house will be much cooler. A rough coat of brown plaster on the under side of the rafters will make an attic cooler in summer and warmer in winter.

If shingles are used they should be specified to be of "first quality" of cedar or cypress. Split shingles, hand-shaven, are, as a rule, better than sawed shingles, but

there is little difference, and some advantage in uniformity of thickness in the case of the sawed shingles. "First quality" implies uniform sizes as well as freedom from cross-grain, and great care should be taken to see that the shingles come up to the specifications, and that they are not laid with a greater number of inches to the weather (i.e., uncovered) than called for by the specifications. Basswood shingles are decidedly objectionable and should not be used in any case; they feather or fur up under the influence of the weather, and are very liable to ignite in dry seasons from chimney-sparks, besides being liable to leak. If shingles are laid in lime mortar they not only form a cooler roof, but a more durable one, and afford better protection against fire in case of ignition from chimney-sparks, etc.; indeed, a roof of shingles laid in lime mortar is almost as good for resisting fire as one of metal. The mortar should be lime mortar, which does not rot wood. Cement mortar is objectionable because it is apt to rot the shingles by confining the moisture and preventing its escape.

The attic in the peak of the roof above the upper rooms should be ventilated so as to secure a circulation of air—an important precaution for houses built in warm climates. The ventilating windows may be protected from the weather by the projecting eaves, the openings being on the under side, as shown in the specimen plan. It is usual to neglect this simple precaution, for the reason that the space next the roof is over the servants' rooms; but inasmuch as upon the health and comfort of the servants largely depend the health and comfort of the proprietor and his family, it is well to be considerate of them in a matter which costs so little money.

All pitch roofs should be securely braced and supported. The wind-pressure in severe storms is tremendous, and unless the roof is thoroughly staid, leaks will develop. Such precautions add little to the expense of the building if provided for in the specifications. It requires only a few cheap timber-braces applied horizontally and vertically in the attic to secure protection against unusual storms.

In small frame-houses, where the roof rafters do not exceed twelve feet in length, it is sufficient to notch them securely to the wall-plate, spiking them strongly. Where greater lengths of rafters are necessary, various forms of trussing or bracing are provided. The simplest is to nail a beam below the apex of the roof between every alternate pair of rafters, thus tying them together. This is called a "collar-beam." The rafters and the collar-beam take the form of the letter A—the collar-beam being the cross-stroke. If it is desired to still further strengthen this, an upright piece known as a "king-post" may go from the collar-beam to the ridge-board. If it is desired still further to strengthen the roof, a tie-beam is carried across the building from the butts of the rafters, and two posts known as "queen-posts" are carried from this tie-beam up to the collar-beam, from which the king-post ascends to the peak of the roof. This form of truss, however, is necessary only in the case of very large roofs with rafters of spans of fifty feet or more.

It is quite customary in pitch-roof houses to frame servants' rooms with horizontal ceilings inside of the peak. Where this is done the attic-ceiling joists correspond in tying and bracing qualities to the collar-beam, while the upright studding for the side-walls correspond

with the queen-posts, so called, and even a very large roof would need no other bracing. Even after a house is finished, where this important and simple provision has been omitted, it would cost very little (probably not exceeding fifteen dollars for an attic forty feet long) to brace the rafters in this manner with three-inch spruce strips. If included in the specifications it would probably not add five dollars to the builder's estimate.

By "flashing" is meant the sheet-metal used on roofs where there are angles or valleys in which the shingles or slate come in contact with a chimney, Flashings, gutters, dormer-window, or other vertical projections through the roof. leaders, ridge-rolls, etc. The flashing in this case should be of "16-oz. H. C." sheet-copper—half-cold rolled copper—instead of tin or galvanized iron; it costs little more, and is preferable on account of its immunity from rust. It is much cheaper than it used to be. The sheet-metal should come well up under the shingles or slate on each side, not less in any case than ten inches, so that water cannot back up and leak through. Where a long roof adjoins a vertical chimney or the side of a dormer-window, the flashing should extend up under the slate or shingles fully eighteen inches on the upper side.

All ridge-rolls, flashings, hangers for gutters, etc., should be nailed with copper nails; if the expense is objectionable galvanized nails may be used.

Ledges, hollows, or level surfaces which would afford lodgments for snow should be avoided in roofs. If they are unavoidable, as, for example, the valley or shoulder formed on the upper side of a chimney against a higher peak roof, snow may be prevented from lodging by constructing small angular sheds, or "crickets," so called,

covered with copper or lead, so that if snow finds a lodgment it will, the moment it begins to melt, slide off and not back-water up under the shingles, slate, or flashings.

By "ridge-roll" is meant the roll along the ridges of the roof and on the peaks of dormer-windows, etc. These should always be covered with metal, preferably of copper.

BALCONY DECKS are often covered with wood or heavy painted canvas. A better material is sheet-lead. It will

Decks for balconies,
or porticoes over
bay-windows, etc.

stand the wear and tear of walking, and can be easily repaired if a leak should develop. It is almost universally used in the older countries of Europe, and especially in England. The quality specified should be four pounds to the square foot. Where, however, the lead is exposed in a warm climate to very high temperatures and the full effect of the sun it is apt to expand; in such locations copper or zinc is preferable. Decks should be inclined, of course, to throw all water free of the house.

Where tin, copper, or zinc is used for decks of balconies a slat floor should be provided, laid in suitable sections, to save the wear and tear of walking over the surface.

INSIDE THE HOUSE

ALL chimneys should be built from the ground; the walls should not be less than eight inches in thickness, and the flues will be improved from fire-resisting and draft view-points if lined with a burnt-clay or terra-cotta flue-lining. It is quite common to erect chimney-flues only *Chimneys and flues* four inches, or half a brick, in thickness. Such flues are very dangerous. Careful examination of the statistics of fires throughout the United States shows that one fifth of the fire loss in dwellings is caused by defective flues. In view of the fact that it costs very little more to make the flue-wall eight inches in thickness instead of four, such neglect is simply criminal. A chimney with only four inches of brickwork, especially in the side next the weather, makes a cold, chilled flue and a bad draft.

Carpenters not infrequently fasten their work in process of construction by driving wooden pegs into chimney-breasts. In the case of a four-inch flue-wall there can be but one result.

Before deciding upon a "half-brick" chimney, ask your architect how much additional it would cost you to

build an eight-inch chimney. You will probably not only build an eight-inch chimney, but you will line it with burnt-clay pipe. If, after learning the extra expense, you are willing to risk your own life for the difference, and do not regard the safety of your family, read what kind of a man St. Paul says is "worse than an infidel."

Be sure to decide upon the number of fireplaces and chimneys required before getting estimates. They cannot be introduced after the building has been begun without risk of dangerous construction and the certainty of added expense.

All floor-timbers should be "trimmed" clear of the hearths and brickwork of the chimney, so as not to be in contact with it at any point. This is easily secured by what are known as "header"-beams, carried in front of the fireplace and at least twenty inches from the chimney-breast, supported by the "trimmer"-beams, which enter the wall on each side of the chimney. These should not approach the side of the chimney closer than four inches. The intervening "tail"-beams, as they are called, are mortised into the header. Where more than three tail-beams are framed into the header, however, it should be supported in "stirrup"-irons (sometimes called "bridle"-irons), by which the weight is carried on the trimmer-beams without mortising into them by "tenon-and-tusk" joints, which sacrifice material and carrying capacity. In this way the floor-beams are free of contact with chimney-flues. The building law of New York city requires (what should not in any case be neglected) that all hearths shall be laid on trimmer-arches of brick carried across from the chimney-breast to the header-beam already described, so that the hearth shall not rest upon or near wooden beams in any

case. This whole matter is more fully explained by accompanying illustrations to follow.

Where a chimney passes through the roof it should be flashed with copper to prevent leakage. Under no circumstances should the brickwork of the chimney be extended out over the roof by the projection of the course of brick nearest to it. Such a shoulder or overhanging projection will inevitably cause cracks in the chimney in case the chimney settles, the roof in such event lifting the upper portion by means of the overhang, or shoulder, and causing a crack at the most dangerous of all places. The chimney should be carried up of uniform thickness to the top, copper flashing being relied upon to prevent leaks.

The chimney should be coped with a three-inch bluestone, and it is important to see that the holes cut in the capstone correspond in size with the flues; otherwise shoulders will be formed and the draft of the flue interfered with.

Flues in throat capacity should not be less than eight inches square on the inside, and for fireplaces in which wood is to be used they should be eight by twelve inches in the clear. Green or unseasoned firewood will require a flue of this size to insure a good draft and prevent smoking. The furnace-flue should also be not less than eight by twelve inches in any case.

Be careful to see that the flues are built according to the specifications, and that details recommended are not ignored by the mason. If not watched at the time the chimney is being constructed faults cannot be remedied afterward. The chimney should be so planned as to carry the flues as nearly straight as may be to the top. A horizontal or flat flue built in a straight way should

never be allowed. All flues should be as nearly vertical as possible.

Masons are often careless about lining the flue even where the specifications call for it, and are apt to omit it until they get to the straight part of the flue. This makes the flue dangerous at its hottest point, near the fireplace, especially where it is surrounded by only four inches of brickwork, and it is important to caution your architect and his inspector, and perhaps to look after the matter yourself, in order to make sure that the flue-lining is carried up from the throat of the fireplace, as called for in the specifications.

Where flue-linings are not provided be careful to see that all joints are struck smooth on the inside, and that projections of bricks or mortar are not allowed, and also that no parging or plastering of the inside of the flue is permitted under any circumstances. The plastering is liable to fall afterward, under the influence of heat and rain, and not only to stop up the flue, but to tear out the plaster between the joints of the bricks. The flue-lining will prove the cheapest in the end, for it will maintain a smooth throat for the entire life of the flue, and, moreover, will tend to prevent the building of nests by chimney-swallows, which prefer rough interiors.

If a stove should be placed in a room in which there is no smoke-flue, and the stovepipe has to pass through a lath and plaster partition to connect with one, great care is required to make it safe. This may be done by placing a smoke-pipe guard-casing (at least eight inches larger in diameter than the pipe) through the partition, perforated with holes in its ends. If the smoke-pipe should be connected to a furnace and heated to a high tem-

Stove- or smoke-
pipes

perature, then the diameter of the guard-casing should be increased to a suitable size. The stovepipe should not be placed closer than six inches to woodwork, and at this distance it is always well to shield it. In all cases where metal is used to protect wood there should be an air-space between the metal and the woodwork to be protected.

Be sure that your architect and contractor understand the importance of building the fireplace and flue correctly, or a smoking chimney will be the result. The fireplace should not, as *Smoking fireplaces* a rule, be higher than twenty-six inches above the floor,—twenty-five would be better,—as the higher the fireplace the more cold air will enter to prevent a good draft. The flue should ascend directly from the center of the fireplace, and if it is necessary because of fireplaces on floors above to carry the flue to one side, it should be drawn by easy inclines to the side, and, as already stated, if wood is to be used, an eight-by-twelve-inch burnt-clay lining-pipe should be inserted. Round flues usually draw better than square flues. Wherever possible a ten-inch round flue should be used, and the flue-lining should be put together with collar-joints tightly cemented, the same as for drain-pipe. Fireplaces for burning cord-wood are often desired. These should be four feet six inches wide and from two feet six inches to three feet six inches high. For these large fireplaces circular flues twelve inches in diameter are advisable. A rough rule by which to gage the size of a flue is to construct it with a capacity about one tenth of that of the fireplace opening. For instance, a fireplace two feet high by forty inches wide would have an opening of nine hundred and sixty square inches, and therefore a flue eight by twelve inches, or

ninety-six square inches, would be the proper size. Where the flue has a smooth throat and is lined with terra-cotta pipe, it will answer for a somewhat larger fireplace. In fireplaces height counts for more as an objection than width; the lower the fireplace the better will be the draft. You cannot be too watchful of the building of your flues.

The brickwork of the back of the fireplace should be brought forward, commencing at a point six courses of brick from the hearth. This tends to contract the flue toward the top of the fireplace, and to insure that the air at this important point is thoroughly heated, which greatly improves the draft.

Where these precautions have been neglected and the fireplace is too high, a smoking chimney may sometimes be corrected at small expense by a sheet of metal carried across the top, four or five inches wide, folded over at the top, so that the flap will fasten in behind the brass frame and hold it in place. This serves as a curtain and prevents the smoke from puffing out in front at the top of the fireplace. A more permanent and sightly arrangement will be to have the brass frame of the opening made wider at the top, or the tile-work may be carried down even after the brickwork has been finished; but it is well to experiment with metal of different widths until the proper height is ascertained.

A smoking fireplace is often caused by an eight-inch-thick top to the opening or front of the fireplace. The brickwork crossing the top should be beveled back so as to run from four inches thick at the front back and upward. This may be secured by brick made two and a half by twelve by eight inches, beveled off from four inches at the bottom to eight inches. The same effect

may be secured by a brass hood for the frame, beveled back so that the tendency of smoke and air will be upward and without obstruction. Insist on having your chimneys and fireplaces built as per illustration on a later page.

It will be found true economy to have fireplaces in all rooms where it is possible. They are not only desirable for heating a room in an emergency, but are valuable for purposes of ventilation. It is best to line them with fire-brick (or cast-iron), and cheapest, also, in the end.

Where the chimney-breast over the fireplace or mantel is "furred out" and finished with lath and plaster, as is sometimes the case, only metallic lathing should be used. It is well to fur out *Chimney-breasts* the breast with metallic lathing in this way, in order that the paper of the room may be kept dry; otherwise on damp days, when the percentage of humidity in the atmosphere is high, the warm, moist air of the room will condense on the cold chimney-breast and in time injure the paper; so that furring out with metallic lathing, leaving an air-space behind, will correct this fault.

Under no circumstances should there be any wooden furring or lathing on a chimney-breast.

The specifications should provide for one joist or strip in the middle wall of every room, so that in case it is desired to hang a heavy mirror, a deer's head, an armor trophy, or other object too heavy for picture-molding, this center stud may be used for the purpose. (Remember, however, that no stud or other wood should be nearer to the inside of any smoke-flue than eight inches. Four inches of brickwork, even with terra-cotta or cast-iron flue-lining, are not sufficient as a fire-stop separation.)

Builders and architects do not always think of such matters of detail, and permit the joists to come where they will. It will be observed that in the accompanying specifications provision has been made for this simple but desirable feature. Any one who has tried to find such a joist by sounding the plaster, only to discover that there is no joist where it is most needed, will appreciate the value of this suggestion. Picture-moldings are not strong enough for heavy mirrors, etc.

In the case of chimney-breasts the wooden stud must not be let into the brickwork, but must be secured with a tinned back so that it cannot be ignited.

In selecting mantels, especially of wood, be sure to see that the projection of the mantel is not so great as to result in its being blistered, if not ignited, by the fire. This is a matter too commonly lost sight of. Not only will the mantel soon be ruined, but there is great danger of fire. Two thirds of the wooden mantels sold to-day have this serious fault.

Mantels

The accompanying specifications will indicate the rules for lathing, etc. Metallic lathing, while it costs more than wooden lathing, is admirable to prevent passage of fire, and also passage of rats, mice, and other vermin.

Plastering

There are several kinds of excellent patent plasters, which should be mixed in the proper manner before coming to the ground, and there is less danger of careless and ignorant work incident to the old-fashioned plaster with cattle or goat hair.

If metallic lathing be used for partitions instead of wooden lathing, greater safety will be secured. Not only is metallic lathing valuable as a fire-stop, but it in-

sures stronger plaster-work. The wire meshes afford a good key for the plaster, and it is not likely to fall. The rooms containing the larger values, such as the parlor, art-gallery, library, etc., could be made almost fire-proof* by metallic lathing, especially if the doors were made of ordinary pine covered with tin, which, in turn, could be veneered with ornamental woods, and paneled so as to conceal the substantial protection beneath. It is well known to underwriters that an ordinary pine door covered with tin on both sides, the wooden frame also being so covered, the tin being laid on with folded joints and nailed in the joints so as to make a complete envelop for the wood, will resist fire much more thoroughly than an ordinary iron door, which costs more and is less effectual. Any carpenter can finish such a door with panels, etc., with ordinary beading, fancy moldings, etc., so that when painted no one could tell the difference between such a fire-proof door and the ordinary kinds which yield so quickly to flame. Such a door might protect a valuable library or art-gallery at an expense which would be merely nominal.

The ceilings of summer houses should be not less than eleven feet for the first story and ten feet for bedroom stories, and ventilation is improved if windows are carried close to the ceil- Height of ceilings
ings, not forgetting, however, that the sills should come near enough to the floor (say within thirty-two inches) to enable any one sitting in a rocking-chair to look out easily. The bottom of the glass in the

* The Japanese *kura*, a fire-proof storehouse for valuables, into the construction of which not a particle of iron, stone, or brick enters, is an illustration of what may be done by intelligent combination of such simple materials as ordinary clay and wood.

sash should not be higher from the floor than thirty-four inches.

Probably few persons are aware of the increase in the number of fires resulting from the modern practice of

Hard-wood finish,
wooden ceilings,
etc.

constructing buildings, especially offices and dwelling-houses, by substituting ornamental woods, often yellow pine with varnished surfaces, for ordinary lath and plaster. The latter is a resistant of fire; the woodwork, as may be well understood, contributes to its ignition and to its spread. Moreover, the necessity of oiling the woodwork from time to time, by servants ignorant of the dangers of spontaneous combustion, leads to many fires whose cause is never known or even suspected. It is natural for a servant to cast an oily rag, after using it, into some out-of-the-way place or rubbish-barrel, where the conditions of confined air insure a sufficient rise in temperature to cause spontaneous ignition. This is exceedingly liable in the case of linseed-oil or of any of the vegetable-oils, kerosene-oil alone being free from the danger of spontaneous ignition, though dangerous enough in other respects.

Wooden ceilings are bad enough where they are thoroughly backed up by plaster or mortar so as to prevent the draft incident to hollow spaces; but where, as is generally the case, the wooden ceiling is simply fastened to the under side of the wooden beams, the construction is most dangerous, and the progress of a fire exceedingly rapid, as in the case of the burning of the dwelling-house of Hon. Benjamin F. Tracy, Secretary of the Navy, in Washington, in 1890, in consequence of which Mrs. Tracy lost her life. In this instance, not only were the dados and ceilings of ornamental woods, but the parlor walls them-

selves were finished in hard wood from floor to ceiling, with air-spaces behind the panels. Notwithstanding that the fire caught in the morning, a few minutes before the breakfast-hour, while men-servants were actually at work in the adjoining dining-room, the spread of the flames was so rapid as to defy the efforts of the fire-department to save life and property.

Where economy is necessary, doors and windows should be what are called "stock" sizes, i.e., the regular sizes made by the mills of the vicinity in which the dwelling is to be located. To specify *Doors and windows* them will save the expense inseparable from unusual or irregular sizes. If, however, the house is so located as to have a fine view, it will be mistaken economy not to have one or more of the prominent windows wider and of plate-glass. Even if the house is intended for a permanent home, sight should not be lost of the fact that it may prove necessary to sell it, and its commercial value will be increased by a much larger amount than the cost of plate-glass for the front windows or doors. Have plenty of windows. Architects sometimes omit them for effect.

Systematic examination of the plans and specifications should be made to see that there is uniformity in the height of the doors and windows, for want of uniformity will detract from the appearance of the dwelling. Indeed, it will be found that the only sure way to detect faults or oversights will be to make specific search through the plans for various features one by one. If a general, cursory reading through of the plans and specifications is relied upon, something will be overlooked. A systematic examination should be made, therefore, to see that each of the different features of the building—

height of windows, height of doors, doors to closets, etc.—is provided for, checking off each in the order of the suggestions herein contained, to see that nothing has been lost sight of. If they are not examined for, one at a time, something will be forgotten.

The accompanying specifications have been carefully drawn, to insure that none of the points mentioned in this book shall be overlooked.

Windows opening on piazza. It is sometimes advisable to have windows which open on the piazza, especially from the dining-room and parlor, arranged in the form of sliding doors, running into the wall, on overhead tracks on trolleys. They are apt to leak unless opening on a piazza sufficiently wide to protect them; in fact, they should not be used on piazzas less than twelve feet in width. Folding windows, which open like double doors, are by some preferred to sliding windows. These are sometimes known as "French windows."

All bedroom doors should have transoms at least twelve inches high, of ground glass, with adjustable-lever transom-openers. Do not use clear glass.

Some experts claim that it is a bad practice in stone buildings to build the window-frames in with the stone masonry of the wall, and that the openings should be carefully made, the stone wall being brought to a proper face, thoroughly pointed, and the window-frames put in afterward, if a weather-tight job is desired.

In planning windows and doors to bedrooms, regard should be had to the importance of locating bedsteads and bureaus with reference to light and drafts, and windows should be arranged accordingly. It is sometimes discovered that the windows have been so injudiciously planned that there is no place for a bed to stand.

An easy way of planning for bedsteads, bureaus, etc., in rooms, is to cut pieces of cardboard of the proper size according to the scale of the rooms. This is usually one fourth inch to the foot. These pieces of card of the exact size of bedsteads, bureaus, buffets, etc., can be moved about on the architect's floor-plan of each room to determine the location of windows, doors, gas-brackets, etc.

Fly and mosquito screens for windows and doors may be included in the carpenter's specifications, but it is usually best to have them put in by parties who make a specialty of this work. The copper-wire netting, while most expensive, is the most durable.

Fly screens

If the dwelling is intended for summer occupation, to be closed during the winter, storm-shutters should be made and estimated for when the estimate is taken for the house. Full details for storm-shutters will be found in the accompanying specifications. It is customary to have small lights of glass in each, to enable one to find his way through a closed house for inspection purposes. Be sure to make these water-tight.

Storm-doors and
-shutters

CLOSETS are indispensable for comfort, and should be numerous. It is safe to assume that it is wise to sacrifice floor-space of rooms for closets, for they secure not only comfort, but order and neatness in the appearance of the house. The specifications should name the height and width of shelves, distance between them, size and arrangement of drawers, and should require hooks for hanging, which will cost little more if of brass or bronze instead of iron, and should be double. The door should not swing into a closet, thus doing away with half the

Closets

hanging room, to say nothing of injury to the contents; and yet this is a common fault with some architects and builders. Closets are improved if ventilated by small windows wherever possible. Examine the plans to see that the hooks in closets for hanging clothing are at the proper height from the floor, and that the shelves above the hooks start at a sufficient height above them to give room for removing garments. Any practical housekeeper will say that "a house cannot have too many closets."

A closet for storing woolen blankets, clothing, etc., may be lined with camphor-wood or with red cedar.

This must be carefully tongued and
Moth-proof closets grooved so that no cracks or joints are to be found anywhere.

It is best to ventilate all other closets with small windows or ventilators, if possible, and especially the soiled-clothes closets.

PRINCIPAL ROOMS

The planning of the rooms of a home is an important matter, and much depends on the judgment with which they are arranged with reference to each other, and with reference, as already suggested, to the prevailing breezes of the summer months.

THE DINING-ROOM, as already stated, should be on the cool side of the house, and a space should be arranged for the buffet, so that it may receive either a
Dining-room side light or a front light from windows.

It should not stand against a light window, with its back to the light, so to speak. Either a side light or a front light improves its appearance materially. If the outlook from the dining-room is upon a beautiful view the window on this side should be wide

and of plate-glass, and it is advisable to have a window opening on a piazza either in the form of a sash-door or a sliding window, running to the floor, of plate-glass. The kitchen should not be too near to the dining-room. Where it is necessary to have the kitchen under the dining-room—and it never ought to be in a summer house—the floor should be cold-stopped and the chimney should be entirely outside.

THE KITCHEN should be so located as to get the prevailing breeze in summer, with thorough ventilation—doors and windows on all sides if possible. In order to better ventilate the kitchen Kitchen the windows should be high, running as near to the ceiling as possible, as the hot air will pass out at this point, while the door should be low, to let in the outside and cooler air. The temperature will be improved, and objectionable odors cut off from the living-rooms of the house, by the use of a heat and odor extinguisher-hood, which can be pulled down over the range, so that any superfluous heat and bad odors will go up through the ventilating-flue of the chimney. This ventilating-flue should be provided for in the plans, and it will be found to be a very necessary feature. It will not add to the cost of the chimney when laying the bricks, as the bricks saved will offset the expense of arranging the flue. As much as twenty degrees of temperature will be saved on a hot day by these precautions at slight expense, and it should be remembered that upon the health and comfort of the cook largely depend the comfort of the proprietor of the house and his family. Such simple precautions, therefore, are not merely humane, but wise from a selfish and economic standpoint.

If it is intended to have a bedroom over the kitchen

(and it is advisable to avoid it) the floor should be deafened, with a ventilating space to prevent the heat of the kitchen from making the bedroom unendurable. It would be well in such case, also, to construct the kitchen chimney entirely outside of the wall, so that it will not unduly heat the sleeping-apartment.

The room over the kitchen would be better utilized for slop-room, linen-closet, trunk- or luggage-room, and for drying clothes in rainy weather.

If the house is a summer house, to be kept closed through the winter, it will be advisable to hang the storm-door of the kitchen on hinges, and have a Yale lock fitted on this and on the inside door, both worked by the same key. The key of the Yale lock is conveniently small, and to have one key to both locks will be found a great convenience when visiting the house for inspection while closed.

THE BUTLER'S PANTRY should be roomy. It should have an outside window and outside door, in order that its floor may be swept without sweeping either

Butler's pantry into the dining-room or the kitchen. It should also have a small door or slide window for passing dishes from the dining-room to the pantry; but this window should open into a closet on the dining-room side. (See accompanying plan for cottage.)

THE REFRIGERATOR should be located near to the butler's pantry, and also to the kitchen, and should be provided with a drip-pipe to carry off the water

Refrigerator from the melting ice outside of the building. It should, under no circumstances, however, be connected with the sewer-drain—a dangerous and highly objectionable arrangement. The better way is to connect it with drains which carry off

the roof water, unless these pass into the cistern, in which case it may be carried to some one of the surface gutters.

THE STORE-ROOM should be arranged, if possible, between the butler's pantry and kitchen. It may be made rat- or mouse-proof at small expense by inserting small-meshed galvanized-wire net-
Store-room
ting in the plaster of the side-walls and ceiling and between the double floors. A store-room thus constructed is like a rat-trap, with the decided advantage of having the rats and mice on the outside. The cost of this simple precaution will be only a few dollars. Do not neglect it. It will be well, also, to protect the feed-bins in your stable in the same manner with wire netting.

A thin layer of sheet-lead under the upper floor of each bath-room, inclined to a small gutter of lead to be run through the outer wall of the building,
Bath-rooms
with raised door-sills, would prevent any overflow of a bath-tub from injuring the building, although a double floor such as I have described, with waterproof paper between, would probably be sufficiently waterproof to insure that any surplus water would be safely carried outside of the walls. The overflow-pipe of the bath-tub, however, and of the wash-basin should be of sufficient size to carry off the combined flow of the hot- and cold-water faucets without other precautions being necessary. This important matter is often neglected by plumbers to save expense in the size of pipe.

Porcelain-lined or enameled-iron tubs have grown to be not merely a luxury, but a necessity, and will prove most economical in the long run. Those with roll (enam-

eled) rims are generally regarded as preferable. I prefer the wooden rims, on account of their not being so cold or slippery; but I find I am in the minority.

Enameled-iron tubs as they come from the manufactory are not painted on the outside, and the painting specifications should provide that two coats of best enamel paint are to be given to the outside of all enamel bathtubs. This will not cost over two dollars apiece, and if included in the specifications when estimates are taken it may not add anything to the cost, whereas if omitted and contracted for afterward it certainly will.

A small gold-leaf streak around the side near the top of the bath-tub is a neat and inexpensive ornament.

The latest form of bath-tub is without faucets, the water being admitted near the bottom of the tub, to prevent the drawing of water in buckets, pitchers, and other vessels by servants, a practice which endangers the enamel of the tub. It is better, however, to have the faucets supply the tub from the top, as the temperature of the water can then be regulated more easily while the tub is filling. Where the supply is at the bottom it is impossible to tell at what temperature the water is running after it is three or four inches in depth. The initial temperature is seldom that of five minutes later, the hot water always running hotter and the cold water sometimes running colder. Side-lever faucets are preferable to screw-faucets.

Bath-rooms should be wainscoted to a height of four feet. Tiling is preferable, but costs more money than plain yellow pine varnished, which is less expensive than other woods and makes a good finish.

Of course a bath-room wainscoted with tile or marble, and with a tile floor, is preferable to all others, but it is

much more expensive. A neat wainscot may be made of cement or some of the patent plasters, which are safer than wooden wainscots on account of fire. If one of these substitutes for tile is used, give it two coats of white-lead paint and one coat of zinc paint; the latter prevents the sulphur from turning the white lead yellow.

If the bath-room is tiled, two small gold tile-beads, one above and the other below any ornamental frieze, make a neat and handsome finish. Do not put the gold near the floor-tile, however; at that point it will look more like a defective joint of brown mortar than like gold.

A bath-room connected with each guest-room is a great luxury from an altruistic view-point.

If the owner can afford it he should provide a bath-room for the servants.

A friendly critic suggests that water-closets and bath-rooms should be separated. I do not agree with him, but mention the fact in case others may.

A toilet-room on the first floor, with water-closet and lavatory, is a great comfort and convenience, and can generally be arranged under the main staircase of the hall, in connection with a coat-closet, as shown on the accompanying plans of a summer dwelling. In this case the closet is under a bath-room and a more economical arrangement of piping is possible. Be sure to have a window in it.

Toilet-room on first floor

This is an important feature in the economy of a good housewife, and almost indispensable to her comfort and convenience. It should be of liberal size, and, if possible, should be so located as to have an outside window and be free from dampness.

Linen-closet

It is advisable to arrange a small room with an outside window, well ventilated, as a sewing-room, where the sewing-machine can stand and the seamstress can work to advantage. In the accompanying plan for a cottage the hall on the second floor, with the bay-window, makes an excellent sewing-room.

Sewing-room

A slop-closet, with galvanized-iron water-sink (a strong one of enameled iron is preferable) and a pipe of good capacity, is a desirable addition on every floor. It will be a convenient place for brooms, brushes, etc., and forms an important safety-valve for the water-closets, which will otherwise be used for emptying slops by careless servants.

Slop-closet

Owing to the negligence of servants in not properly flushing slop-closets, they ought really to be arranged in the same manner as a toilet-closet, so that a chain would need to be pulled in order to get water for rinsing vessels, and so flush the trap automatically at the same time. It is very important that slop-closets should be ventilated with an outside window.

It is very desirable to set aside one room, not above the second story, if possible, for a luggage- or trunk-room. The room over the kitchen is generally a warm room and can best be spared for this purpose. This room

Luggage- or trunk-room

may also be utilized for drying clothes on rainy days, by having strong hooks fastened to the studs for attaching the clothes-lines. The room need not be plastered, and where the kitchen is in an extension it is wise to make the extension two stories, so as to insure a slop-room, linen-closet, and trunk- or luggage-room.

It is quite convenient to have, somewhere on the first floor, a small room for bicycles—no unimportant feature where each member of the family, children included, and visiting guests also, have wheels. Bicycle-room

It may not be out of place to suggest provision for a dark room for developing photographs, and for such purpose a room may be framed in the attic, which would not be of use for any other purpose, yet admirably adapted for developing negatives. Dark room for photography

THE PLAY-ROOM should find a place in the plans of the house, and should be located where the noise of children would not interfere with afternoon naps or quiet reading in the library. A small extension on the first floor will be found preferable to a room in the upper part of the house, but it is not always practicable to make such an arrangement. Play-room

If, in addition to the rooms common to ordinary dwellings, the owner desires a billiard-room, it should be on the cool side of the house.

In localities where there is good hunting and fishing it may be well to have a gun-room, in which the guns and fishing-tackle may be kept.

A music-room is also a feature of modern houses, and can sometimes be planned to open off the parlor, at a higher level, with steps ascending from the parlor floor, so that the music-room forms a sort of balcony to the parlor itself.

Conservatories, picture-galleries, etc., would be arranged with reference to the taste of the owner, who

would hardly value suggestions on this score from any one, and they are therefore not offered here.

STAIRCASES

These should always be wide, not less than three feet six inches in the clear; four feet is better for the rear staircases—the front or main staircase may be wider. The risers should not exceed seven inches (better six and one half inches), to insure easy stepping; and the treads should not be less than ten inches in width, excluding the “nosing,” or projection of the step over the riser below. For rear staircases nine inches width of tread with seven-inch riser will answer. It is important to build the rear staircases wide enough to carry up furniture, trunks, etc., and so relieve the front and more ornamental staircases from injury and undue strains. It will not add materially to the expense of the building where contemplated in the estimate of builders, and will prove a lasting comfort and satisfaction.

It is unnecessary to suggest that if the staircases are wide the doors at the foot and head of the stairs should correspond in width; otherwise the advantage of a wide staircase is largely lost.

Under all stairs there should be a center carriage-timber to stiffen them when heavy weights are being carried over them, and also a carriage-timber inside of the front or unsupported string, and they should be strongly bracketed underneath every step. Unless the unsupported string is itself three by eight inches, it is not safe to rely upon the strength of the stringers or side-pieces only.

Staircases of wood may be rendered practically fire-

resisting if the spaces between stringers or carriages, lower joists of landings, etc., are "pugged" solid with mortar or other incombustible material, and the spaces between stringers closed, at intervals of three feet, by fire-stops of such material.

• THE COMFORTS OF HOME

HEATING

CONTRARY to the English idea, the first essential to comfort in the average American mind is ample warmth in all rooms. This may be by hot water, steam, or furnace. For summer houses a furnace is preferable, because of the readiness with which the temperature can be raised by burning a few sticks of wood on a cold morning or evening, often when it is desirable to let the fire out during the middle of the day.

Heating

The furnace should be a large one. It is better to force a large volume of warm air into a house than a small volume of very hot air.

Where the heating-pipes pass through hollow partitions or between floors they should be double, an inner and outer pipe, with an air-space of at least half an inch between the two. These are required by the New York building law. If they pass through such partitions within fifteen feet of the furnace it would be better to guard them with one-quarter-inch asbestos board.

The accompanying specifications require the separation of studs between which the hot-air pipes of the furnace pass so as to allow three inches of space. This is very important. They also provide that the lathing over

hot-air pipes shall be of metal. This costs little more and may save a midnight fire. If the partition or side-walls of the building are of brick or stone the hot-air pipes of the furnace should be carried up in the wall as it is built. This, of course, is the safest of all construction.

It will be observed that in the accompanying carpenter's specifications, as well as in the furnace specifications, provision is made for the separation of the joists. This is necessary to prevent oversight. Probably no important matter connected with construction is more generally overlooked by builders, architects, and others than this important one as to the carrying of hot-air furnace-pipes throughout the building.

THE COLD-AIR BOX which supplies the furnace should be of metal; galvanized iron with soldered joints is the best. Not only is this advisable on account of the danger from fire, but also to insure that the poisonous air of the cellar, from wet coal, decaying vegetables, etc., is not pumped through the living-rooms of the house, as it will be if a wooden cold-air box is used. Wood is apt to shrink and open seams or cracks with seasoning, changes of temperature, etc.

Provision should be made for evaporating water in the air-chamber, so as to moisten the air forced through the house. Most furnaces are provided with an evaporating vessel. It is a generally accepted but mistaken belief that furnace-heat is necessarily a dry heat, and that steam- and hot-water systems necessarily afford moist heat. The names of the two systems suggest the idea, but there is no other foundation for it. In neither of the two can steam or hot water get out of the pipes, which are of course water-tight. Even where provision

is made for permitting steam to escape at the valves, the valves are seldom opened, and when they are the odor of escaping steam is disagreeable; while, on the other hand, a good large furnace, forcing a large volume of warm, fresh air, instead of a small quantity of hot air, throughout the house, by means of an air-tight, galvanized-iron cold-air box, with hot water evaporating in the air-chamber, insures moist temperature, and at the same time better ventilation than either the hot-water or steam systems, which simply heat the air already in the rooms. Where, however, volumes of fresh air are forced over heating surfaces of steam-pipes or hot-water pipes the case may be different; but where reliance is placed on heating the air already in a room simply by steam or hot water in stationary radiators, and no provision is made for a continued circulation and supply, the hot-air furnace is preferable. In the case of a summer residence, especially, which needs artificial heat only for a few mornings or evenings in the spring or autumn, it will be found the most convenient and economical.

The sides and top of all brick hot-air furnaces should be kept at least four inches from beams, girders, or wooden partitions of any kind.

The walls of brick furnaces should be built hollow, with a space of four inches between the inner and outer wall.

All portable hot-air furnaces should be kept at least two feet from any wooden or combustible partitions or ceilings, whether the same be plastered or not. A suspended metal shield above the furnace costs little and is an admirable precaution. It should be so arranged as to be easily cleaned, as combustible material may collect on top.

The principal register of a furnace should always be so

secured that it cannot be closed, in order to prevent an accumulation of hot air and super-heating. A floor-register should never be placed directly over a furnace.

It will be wise to provide for electric-light wires and gas-pipes when constructing the building, if there is the slightest probability of either gas or electricity becoming available in the near future. It is perfectly safe and practicable to manufacture gas on the premises from gasolene, the tank or gasolene-holder being outside and underground, and the air-pump or regulator, so constructed as to be gas- and air-proof, in the cellar, in a light place, with a vent gas-pipe running outside, so that any back pressure from the tank would force any leaking gas outside of the building. A good gas-machine, constructed on these principles, is safer than ordinary kerosene lamps—quite as safe, in fact, as city gas. Beyond the initial cost of the plant, the cost of gas so manufactured is almost nominal, while the gas is so far preferable to lamps that it will add materially to the comfort and convenience of the family. Be sure to use a safe machine approved by underwriters.

Lighting

OUTLETS should be carefully planned with reference to bureaus, bedsteads, etc., in bedrooms, and reading-desks and tables in library, etc. Expense can be saved by dispensing with center outlets for chandeliers in bedrooms, using side-brackets only; but in view of the fact that any house may some day be offered for sale, and the further fact that it costs little to extend pipes and wires for center outlets of chandeliers, it may be wise to provide for them, as they might be desired by a purchaser.

Gas and electric-
light outlets

All electric installations should be in accordance with the rules of the underwriters, as these are kept constantly corrected to be in line with the latest discoveries in precautions for safety. Conduits or raceways for carrying the wires through the house should be of iron or other metal, in order that the wires may be easily withdrawn, repaired, and replaced, and in order that the danger of fire may be minimized.

The forcing of water to the tank will be most economically performed, as a rule, by a hot-air engine. This may be run by gas, where gas is procurable, or by the use of coal, requiring little more attention than a small stove.

A good windmill is also an economical appliance for country houses.

If it is necessary to have the tank in the house, as is generally the case, it should be strongly supported by the arrangement of the timbers beneath it.

Water-tank It should be of iron, or, if of wood, lined with tinned copper; and care should be taken to see that the overflow-pipe is of sufficient capacity to prevent damage to the building. An expansion-pipe should be provided, opening into the tank, to relieve any undue pressure on the pipe system.

The overflow from the tank should be so arranged as to return the water when the tank is full to the cistern, thus saving the water and aerating it, it being a great advantage to the water in the cistern to have it aerated in this way. The tank-room should be thoroughly ventilated.

Be sure to provide a drain-pipe for emptying the pipe, and save the labor of dipping out the two inches of water below the opening of the pipe which supplies the house.

Make the tank large enough—a cubic foot of water

is equal to 7.48 United States gallons, and the capacity of the tank can be estimated with knowledge of this fact.

It will be found a wise precaution to paint the timber-work of the attic where the tank is located, as well as the outside of the tank itself, with a good quality of fire-proof paint. Where the expense is objected to, white-wash may be used, with some common table-salt added. This will tend to make the woodwork less ignitable. Dry, unprotected wood (and it is always dry in an attic) is easily ignited, and fire flashes quickly over its surface. Plumbers are frequently inexcusably careless with their fire-pots, and the simple and inexpensive precautions suggested may prevent the rapid spread of a fire and the destruction of the building.

BELLS should be carefully planned with reference to convenience in using. It is well to have an electric bell to the servants' bedrooms, as well as to the kitchen, with a push-button near Electric bells the head of the bed of the mistress of the house; one also from the reclining-couch or divan in the library or sitting-room, and one from the table in the dining-room. This latter may be arranged by a flexible cord carried to the chair of the proprietress; also with a button in the floor, to press with the foot. A bell to the stable, with a push-button in both the bedroom of the proprietress and the library, is also desirable.

Speaking-trumpets from owner's bedroom to kitchen and furnace in cellar are advisable. The latter will enable owner to instruct the man at the furnace as to the amount of fire, especially when he hears him throwing in coal early in the morning.

Where electricians are not handy, pneumatic or pull bells are preferable to electric bells.

As a rule it is a mistake to economize in the selection of hardware, especially in the matter of door-knobs, locks, escutcheons, etc. These cost little

Hardware more if of brass or bronze than if of iron. Knobs, for bedrooms especially, are much neater if of wood. The round knobs are preferable. Inasmuch as the builder will be sure to estimate full price for finishing hardware, it is better to except this and provide that the owner will furnish it, being careful, however, to specify just what hardware the owner is to furnish, as otherwise misunderstandings are certain to arise. It is only necessary to specify that the owner will furnish all locks, knobs, hinges, sash-lifts, and sash-fasteners, the builder to furnish all other hardware. This will enable the owner to exercise his taste in that portion of the hardware for which he may be supposed to have preferences.

Metal chain will be much cheaper in the long run, especially for heavy windows, than sash-cords, no matter how good the latter may be. Where

Sash-weights and cords sash-weights exceed twenty pounds they should be of lead, which will cost about five cents a pound as compared with one cent for iron; but it is worth the difference, as heavy iron weights are clumsy and necessitate larger window-boxes. The axle-pulleys should be not less than two-and-a-half-inch wheels with flat-bottom channels or grooves.

The owner should require the architect to furnish details of the trim (by which is meant the wood finish, window-frames, door-frames, wash- or

Trim or finish base-boards, panels under windows, wainscoting, etc.) promptly,—in fact, simultaneously with the plans and other specifications,—

in order that the builder may have no excuse for not having all of the trim kiln-dried in time for finishing the building.

This is a more important matter than at first glance it may appear to be. Builders and contractors are often prevented from finishing their work in time through the negligence of architects in furnishing details, drawings, etc., and do not like to put the blame where it belongs; no builder likes to quarrel with an influential architect. In the accompanying contract with the architect this has been provided for, and the owner should see that all of the working plans, details, drawings, etc., are fully completed before taking an estimate for the work. He will thus get better prices, because each contractor will know exactly what he has to do, and will not make undue allowance for construction details as to which he may have to guess. Moreover, as already stated, it is vitally important to have the details of all standing trim at the earliest moment, so that it may be properly seasoned.

The owner, too, will find it advisable to go over the drawings of the standing trim, doors, patterns of the main staircase, etc., as in case they do not suit him it will be too late to remedy the matter after they have been prepared and brought to the building.

Do not, under any circumstances, consent to have your architect take estimates with the indefinite clause, "Details hereafter to be furnished."

Plenty of time should be given to the various estimating contractors to make their figures, and money will be lost if they are required to estimate without sufficient time for investigation—at least a week in any case.

It will be found that a pleasing, cheerful, and inexpensive finish will be a trim of ordinary natural-finish white pine,* treated with one coat of pure spirit shellac white, rubbed down with O O sandpaper, to have two coats of good quality of wood-varnish, neatly rubbed down with pumice-stone and water to a smooth dead finish. All of the main stairs, main hall, library, drawing-room, and dining-room floors should be finished with filler and two coats of floor-varnish. All hard wood should be treated the same as pine, except that it should have a coat of wood filler and an extra coat of varnish.

Painting

All exterior woodwork except shingles should have two coats of white lead and oil paint. If it is intended to have the shingles "weather gray," a dark-green paint on the cornice, blinds, etc., blends well with it and gives a rich, attractive effect.

All tin and galvanized-iron work should have two coats of best metallic paint, and the ceiling of piazzas and porches, front-vestibule doors, and piazza columns (if the latter are of natural wood) should be finished with a

* An expert friend of mine of great experience in the erection of buildings, who has also built two dwellings for himself, writes me as follows:

"Yellow pine, if carefully selected and treated, makes a beautiful trim for a house inside. It should be applied as a veneer to white pine. I find one coat of oil best; then let it stand for a year or two; then give it another coat; then, when it has become dark and rich in color, finish it in any way you like, wax or varnish rubbed down. Of course this can all be done when the house is occupied."

I prefer the light and cheerful color of white pine, but some of my readers, like my friend, may prefer the darker wood. The whole question of wooden trim and top flooring is one which each must settle for his own taste, not overlooking the dangers of wooden ceilings and dados already explained. (See page 40.)

coat of filler and two coats of best quality of spar varnish. A very satisfactory effect in the piazza is to have the columns of Georgia pine twelve inches in diameter. If the house is a large one these will be in keeping rather than to have columns built up square of boards, or solid turned columns of smaller size.

FINISHING WORK

PROBABLY no important question connected with dwelling-houses is the subject of greater diversity of opinion than that of whether or not lightning-rods are necessary. That it is advisable to have a good lightning-rod, well grounded, i.e., con-

Lightning-rods nected with moist ground, is the generally accepted opinion of those who ought to be best informed on the subject. I am fully aware that lightning-rods are regarded by a large number of people as affording no protection; indeed, a gentleman who has favored me with many valuable suggestions in the review of the proof of this book insists that a dwelling of his, destroyed by fire as a consequence of being struck by lightning, was rodded in the best manner. Notwithstanding his opinion, I advise every one to have a good lightning-rod, and to supplement its protection with a fire-insurance policy in a reliable insurance company. The Washington Monument was repeatedly struck and injured until it had been protected with a rod, and though repeatedly struck afterward, no damage was done.

The advantage of lightning-rods, however, is not confined to the conducting away of strokes of lightning.

They frequently, so to speak, tap the electricity in the atmosphere and conduct it quietly away to the ground, preventing its accumulation in sufficient volume for a stroke. For this reason the lightning-rod should have numerous points on the roof. It is a well-known fact that beech-trees are seldom struck by lightning, whereas oaks, hemlocks, and other trees are subject to frequent damage; and while this well-known fact is accounted for on the supposition that the rougher barks hold water, itself a good conductor, and that oak contains a great deal of iron in its composition, the exemption of the beech-tree is believed by many to be due to the fact that it has numerous pointed leaves and twigs, as well as a smooth bark.

The lightning-rod may be of iron or copper, and may be in the simple form of a hollow gas-pipe or in twisted wire cables, or it may be in a flat or taped surface. It is the surface which conducts the electricity, rather than the center or solid portion of the rod. Ordinary gas-pipe three quarters of an inch in diameter will make an excellent conductor. It may be fastened to the wooden sides of the wall or to the roof by strong iron staples. It is not necessary, although it is customary, to insert glass insulators, because the current will not leave the rod to enter woodwork, or forsake a good conductor for a poor one. The rod should be carried deep enough under the surface of the ground to reach moist soil. An excellent ground may be secured by connecting the bottom of the rod by copper wires, well soldered, to the pump-rod entering the water in the well.

The writer would advise all persons erecting dwellings in isolated locations to have rods. In cities they are not necessary. Continuous use of tin or other metal for roofs, water-pipes connected with the underground sys-

tem of the city, or drain-pipes with the sewers, are sufficiently good conductors to make rods unnecessary. Indeed, even in country dwellings, if leaders and gutters are connected with the points of the rod on the roof, they form sufficient channels for carrying the electricity or lightning to the ground, provided they are connected with moist ground or with the pump-rod in the well.

A poor rod, or one not properly connected with moist ground, or disconnected at points, is worse than none.

Only Portland cement mortar should be used in cisterns. The bottom or foundation, unless constructed as an inverted arch of brick, like the bot-

Cisterns tom of a flask, should be of best concrete, twelve inches thick, one part cement, two parts sharp sand, and four parts clean, well-washed gravel or clean broken stone; the side-walls built as per specifications (page 115). If the cistern is filled by pumping from a well, it is better to have the water pumped into the top, as this aerates the water. The top should be arranged to secure perfect ventilation.

The capacity of the cistern is an important matter, and may be easily computed by the following table:

CAPACITY OF CISTERNS OR TANKS, IN UNITED STATES GALLONS,
FOR EACH TWELVE INCHES OF DEPTH

4 feet diameter,	94	11 feet diameter,	711
5 " "	147	12 " "	846
6 " "	211½	13 " "	993
7 " "	288	14 " "	1115½
8 " "	376	15 " "	1322
9 " "	476	20 " "	2350
10 " "	587½	25 " "	3672

For example, a cistern twenty-five feet in diameter would contain 3672 gallons for every foot of depth; and if ten feet deep, 36,720 gallons, or 918 barrels.

A simple rule may be stated as follows: To find the

contents in United States standard gallons for each foot of depth of a cylindrical cistern with a circular base, multiply the square of the diameter (in feet) by five and seven eighths; the product will be the contents in gallons.*

For example, a cistern twenty feet in diameter and ten feet deep would contain $20 \times 20 \times 5\frac{7}{8} \times 10 = 23,500$ gallons (see table above).

Let no one persuade you to make separate contracts with various contractors—builder, plumber, mason, etc. Unless there is one responsible contractor for the whole work, each of the Contractors contractors will plead negligence on the part of one or more of the rest as an excuse for delays. The builder will insist that the mason did not get his foundations finished in time; the plasterer will insist that the roofer did not finish in time for him to commence his work with necessary protection against the weather, etc. Moreover,—and this is a serious matter,—any injury to the building by reason of neglect to protect against the elements will be a matter for which an owner who has various contractors will alone be responsible, whereas if he has one contractor, under obligation to finish and deliver the building in good condition, he will be relieved of protecting the building from storms, washouts, etc., and will also be relieved of the expense of paying watchmen for nights and holidays.

It ought to be unnecessary to suggest that it is important to investigate the reputation of contractors and

* The cubic contents, in feet, of a cylinder like a cistern, are obtained by multiplying the area of the circle by the depth in feet. Inasmuch as the area of a circle is obtained by multiplying the square of the diameter by .7854, and inasmuch as a cubic foot of water contains 7.48 gallons, it is only necessary to multiply the square of the diameter by the product of $7.48 \times .7854 = 5\frac{7}{8}$, to obtain the result in gallons, without the longer computation.

architects as to fidelity of performance before making contracts. Do not be satisfied with writing letters to parties who have employed them, but go in person; only in this way can confidential and important information be secured. It is very important to secure honest men. It is impossible to watch all details and secure conformity to the specifications if the builder is tricky. As already stated (page 2), it is well to employ an inspector for supervision. He will save his wages.

If it is desired to keep check upon all charges for extras, and the architect is not thoroughly reliable, the contract should stipulate that no
 Extras changes in the plans shall be made nor any extra work done unless upon written certificate of the architect and owner (not "architect or owner," the prevailing phrase).

LIENS can be avoided only by taking proper precautions. Much depends on the law of the State. In some States—New Jersey, for example—the
 Mechanics' liens, attachments, etc. law requires that a copy of the contract and of the specifications shall be filed with the county clerk, and that, this having been done, the owner will be liable only for payments made to contractors after having received written notice of liens; so that, in the absence of written notice, he is safe to make payments.

PENALTIES are practically uncollectable, and cannot be enforced, as a rule, because of pleas, which juries will consider, of exceptionally unfavorable weather, alterations in plans in matters of afterthought, delays of sub-contractors, etc. It almost invariably happens that some slight change is desired in the plans,—an extra door or window, for example,—and any change is

Per diem penalties
for failure to complete
within time of con-
tract

liable to defeat a claim for damages. The best way to enforce a penalty is by means of a bonus, making the contract for something less than the agreed price, the difference to be paid as a bonus if completed within the agreed time. For example, if a builder is willing to contract to finish a \$5000 building by the 1st of June, and to pay a penalty of \$25 per day for each day of delay after that date, he cannot consistently object to making his contract for \$4250 if finished by the 1st of July, with the agreement that he is to receive a bonus of \$750 if he finishes it by the 1st of June, the desired date, the bonus to be computed at the rate of \$25 per day for each day of earlier completion than the 1st of July. He will thus receive \$750 bonus, or \$5000, his actual contract price, if he finishes the building within the proper period. Such a contract can be enforced, because failure to complete will clearly deprive him of his right to the bonus. (See form of contract.)

From the moment you begin to use combustible material in your house and get beyond the foundations it should be insured in some reliable company. Dwelling-houses are liable to burn from many causes—unscrupulous enemies, tramps, insane persons, and other incendiaries. Rats, mice, and roaches cause fires by gnawing the ends of matches or by carrying greasy and ignitable substances near flues, hot furnace, or steam-pipes. Tinnerns and plumbers are sometimes careless as to their fire-pots on roofs or in dry attics. Painters leave oily rags or oily overalls where they are liable to ignite spontaneously. Kerosene lamps are liable to explode or to be dropped and broken while lighted. Children often cause fires in playing with

Insure against loss
by fire, lightning, tor-
nadoes, and wind-
storms

matches. Nearly ten per cent. of the total number of fires are caused by lightning; one fifth or fully twenty per cent. of the losses by fire are caused by defective flues; not a few are due to sparks alighting on shingle roofs and the burning out of soot in chimneys; many are caused by curtains or other drapery blown by currents of air from open windows or doors into burning gas-jets or open fireplaces. Hot ashes in wooden boxes or barrels cause many fires. Wood ashes particularly are liable to heat even after they are supposed to be cold, and to ignite wooden receptacles containing them. Clothes hung near stoves or ranges to dry sometimes fall or are blown upon the fire and ignite. In fact, no person having access to the statistics of a fire insurance company, and brought face to face with the hundreds of ways in which fires originate, would be willing to go uninsured in order to save the small sum of money for which an insurance company can afford to insure. Do not carry the risk yourself. When you find how small a sum it will cost you annually to insure, you will need only to multiply it by the number of years it would take you to accumulate a sufficient amount to pay a loss (not forgetting that the loss may come the first year) to demonstrate how foolish it would be for you to carry the risk yourself. No matter how well off you may be, it is very convenient, in case of a fire, to find the money ready to your hand for rebuilding.

During construction the builder may have an interest as well as yourself, and the insurance policy should be issued in the name of both, as follows: "John Doe, as owner, and Richard Roe as builder; loss, if any, payable as interest may appear."

When the house is finished and furnished, your wife

should be joined in the policy, inasmuch as she will own property in it as well as yourself, and this joint insurance will save both interests. The policy, therefore, should run to "John Doe, and Mary, his wife."

Select an insurance company which has a substantial net surplus. Good management as well as capital is a requisite of safety in an insurance company, and a substantial net surplus is one of the best evidences of good management.

A PRACTICAL EXAMPLE

THE following plans are of a summer cottage on a hillside fronting upon an ocean view. The prevailing summer wind blows toward the dining-room, which for that reason is located with reference to the fact.

It will be observed that the dining-room communicates with the butler's pantry both by a full-sized door and by an opening with small sliding door

Sample plans for a
cottage

from a closet for passing dishes. It will be observed also that the butler's pantry is of commodious size, and that it has a window at one end and a door at the other, so that its floor may be swept without sweeping either into the kitchen or dining-room.

The store-room is located, as it should be, between the kitchen and butler's pantry and dining-room. It is lined in the plastering on sides, overhead, and between floors with galvanized-wire netting one-eighth inch mesh, and is rat-, mouse-, and vermin-proof.

The rear stairs are three feet six inches wide in the clear.

The kitchen and laundry, although separate, are so

arranged as to assist in ventilating each other, thus practically increasing the size of both.

The main hall, which is in the center, as it should be in summer houses, is sixteen feet wide, and the doors from the parlor, library, and dining-room opening into it are double sliding doors. The effect is not only to make the house cooler, but more roomy in appearance.

The library is arranged with a large projecting plate-glass window five feet in width, giving a view upon the ocean, and at the same time affording the observer a full view of the fireplace, which, with its wood fire, would share his attention in stormy weather—the only time in summer when he would probably not be on the piazza. It will be observed that the corner opposite the plate-glass window has not been rounded with a bay-window, but left square; this is for a divan or lounging couch with pillows.

It will be observed that there is a toilet-room with water-closet and lavatory on this floor under the main staircase. (See page 49.)

The plan of the second floor has some of the features of the first, including the wide hall through the center.

The projection of the middle front room over the piazza below is to insure that this room shall have two side-windows, which it secures by this simple provision. Otherwise, like most middle rooms, it would not be properly ventilated for warm nights. This is an important feature for a summer house.

The two bedrooms on the northerly side of the house secure the prevailing breezes from the hall, with its bay-window on the southerly side, in the rear of the front bedroom. This hall forms an admirable sewing-room, where the seamstress has plenty of air and light from

the bay-window and it is always cool in summer. It will be observed that the staircase to the third or servants' floor does not ascend from this floor. It is a rear staircase. This insures the more thorough ventilation of the second floor, as a staircase running to the third would cut off breezes from the northerly bedrooms. It also insures immunity from the noise inseparable from the servants' quarters and their early rising.

It will be observed that closets have been liberally provided and that they are of generous size.

Each room has a fireplace.

The linen-closet and slop-closet are important features.

The two bath-rooms on the second floor can be connected each with its bedroom, so that the spare room has a separate bath-room into which it opens.

All important windows opening upon the view are wide and of plate-glass.

The house is built of cedar shingles, allowed to become "weather gray"; slate roof, "Pennsylvania," nine by eighteen slates; walls back-plastered; floors double, with salamander between. The floor-beams are all of them three by twelve; piazzas twelve feet wide, the piazza pillars twelve inches in diameter, Georgia pine, natural finish. The entire trim of the house is of plain white pine, finished with shellac, except the main staircase, which is quarter-sawn oak. All flues are surrounded by eight inches of brickwork, and in addition are lined with burnt-clay pipe, and all hollow partitions have "fire-stops." Metallic lathing on cellar and main ceilings forms admirable fire-stops and prevents incursions of vermin.

Plans of Dwelling

Trunk and Luggage Room

Linen Closet

Bath Room

Bed Room

Bed Room


Bed Room

Second Story Plan.

Second Story Plan.

1901

Plans for Dwelling



Third Story Plan.

11070

1921

Mans for Dwelling






Fig. 1. Elevation

U of M

3

1991



Perspective Front Elevation.

200

SAMPLE SPECIFICATIONS

THE following specifications can be used for separate contractors, or, as already recommended, for one contractor for the whole work, and, with slight modification, can be adapted to any kind of a building. Most of the requirements, especially those as to standing trim, flooring, etc., would be identical with those needed for mercantile or other occupancy. They call for the best forms of construction, in the belief that they should be so drawn in order that any one desiring to build after the most approved methods would be enabled to secure his wish, it being much easier to modify specifications to suit cheaper construction than to change phraseology intended for a simple and cheap building so as to provide for more elaborate and expensive construction.

HOW TO BUILD A CHEAPER DWELLING

If, therefore, the reader desires to construct a cheaper dwelling than is here provided for, he can, especially with the assistance of his architect or builder, go over the specifications, paragraph by paragraph, and strike out such requirements as he may be willing to dispense

with. He can, for example, have a narrower hall than sixteen feet in width; he can have one common chimney for the entire house, to save the expense of separate stacks and fireplaces, dispensing, if he chooses, with all fireplaces except that in the library or living-room, where an open fireplace is generally too much of a comfort and luxury to be dispensed with. He may arrange for one bath-room. He can substitute zinc, tin, or galvanized-iron flashing for copper (although he will do well to inquire the extra cost of copper, which is cheaper now than it used to be, before deciding). He can substitute ordinary white-pine flooring or North Carolina pine for comb-grain yellow pine, especially if his floors are to be entirely covered with carpets or matting. He can omit the requirement that risers and treads of staircases shall be plowed or tongued into each other. He ought not to omit the carriage-timber. He can substitute plain boxed columns, to be painted, for his piazza, instead of solid wood columns. If he decides upon a cheaper wood for his floor-beams than yellow pine, he should take white pine, spruce, or hemlock, in the order named; the latter is the poorest of all for the purpose. But unless his house is to be a small one, and the spans of his floor-beams are to be less than fifteen feet, he will make a serious mistake if he consents to two-by-ten-inch floor-beams instead of three-by-ten or three-by-twelve-inch. In small houses it is quite customary to put two-by-twelve-inch floor-beams for the first story, two-by-ten-inch for the second, and two-by-eight-inch for the third. Under no circumstances should a chimney rest upon such beams as these, nor, for that matter, upon any floor-beams, no matter how large; all chimneys should be built from the ground.

Under no circumstances should he consent to chim-

ney-flues with inside capacity less than eight inches square, nor should he consent to have them surrounded by less than eight inches of brickwork, with a terra-cotta or cast-iron flue-lining in addition.

As I write, numerous reports are being received of fires in dwellings from defective flues. Zero weather always brings to every insurance company scores of such claims. Within twenty-four hours of this writing a valuable dwelling, costing over \$50,000, has been destroyed, the owner and his family barely escaping from their beds, in the middle of the night, to take refuge in ice and snow from a ruined home. It will aggravate his sense of loss to reflect, when he learns the fact, that a few dollars spent in extra brickwork in his chimneys would have prevented the disaster; and he will be justified, probably, in claiming that he would not have thought of practising such short-sighted economy if the matter had been properly called to his attention by his builder and architect.

It is safe to say that ninety per cent. of the defective flues of the country are due to ignorance on the part of owners as to what is necessary for safety, and not to a short-sighted economy which would save a few dollars at the risk of life and property.

The best method of scaling down requirements to conform to the amount of money which an owner is willing to expend is to go carefully over the specifications and call for alternate estimates from his contractors, so that he may decide intelligently as to what he will omit. In many cases the difference in cost will be so slight that he will probably choose the better method, sacrificing, if necessary, those features of a building which are mere matters of style and appearance, and retaining those which make for comfort, stability, and durability.

SPECIFICATIONS FOR WOODWORK

In a frame-house, of course, this is the most important branch of the work, and everything depends on getting a conscientious and skilful builder.

The owner should endeavor to secure well-seasoned material. Time-seasoned lumber is better than kiln-dried lumber, although the modern improvements in kiln-drying are so great as to do away with the objections which formerly lay, with good reason, against kiln-dried material.

SPECIFICATIONS OF CARPENTER OR WOODWORK for a dwelling to be erected for JOHN DOE, Esq., located at —.

These specifications are to accompany drawings made by JOHN SMITH, architect, under whose supervision the work is to be done.

The drawings and specifications are to coöperate, so that anything shown on the drawings and not mentioned in the specifications, or vice versa, is to be done, the same as if shown on both drawings and specifications. The drawings and these specifications, moreover, are to be carried out to the full meaning and spirit.

In cases where there may be doubt as to exact measurements, or where the scale measurements differ from the figures, the figures are to govern, and the contractor is to verify all dimensions that relate to his work, or to the joining, fitting, or adjusting of his work thereto.

He is also to take careful and exact measurements, and compare and copy wherever or whenever any new work is called for to be a counterpart of or similar to the present work.

Also to verify all measurements at the building whenever his work is subsequent to existing new work, and he is to be responsible for same, unless written notice is given by him to the architect, so that proper adjustments may be made in time.

This contractor must coöperate with all other contractors of the several works, so that work will not be constructed prematurely, neces-

sitating its being taken down to allow the construction of work that should have been previously executed. He is also responsible for the proper adjustment of his work with other works, and to repair, join to, and make his work perfect.

This contractor is to furnish all materials for the work herein specified, and said materials are to be the best of their several kinds, unless otherwise specified, subject to the approval of the architect.

In case any materials are not approved by the architect, they shall, upon his request, be promptly removed from the premises.

All the work is to be done in the best manner, according to the full meaning of the plans and specifications, and subject to the approval of the said architect.

This contractor is to be responsible for any violations of the laws or ordinances, whether State or municipal, for the constructing of buildings, and is to hold the owner harmless from any expense or claims for damage to life, limb, or property arising from any violation of such laws, ordinances, or regulations, or caused by or in consequence of carelessness of himself or his employees.

He is to inclose the building securely with strong muslin on wooden frames, or with temporary doors, sashes, and glass, as may be necessary until the permanent sashes are put in; and he is to maintain the building properly inclosed and protected from the weather until finished.

He is to furnish the mason, stone, and terra-cotta workers with all centers, templates, etc., required for arches and other work.

He is to box all terra-cotta and stonework for protection, as directed by the architect, and to do all cutting of woodwork required by any of the other contractors.

He is to do all rough carpentry, such as centers for masons and stone-contractors, rough studding, grounds, lintels, etc., in fire-proof partitions, where such are provided for, and all wood-furring and bracketing that may be required.

He is to furnish and finish trim of all windows and doors, such as architraves, panel-backs, jambs and soffits, etc., for all walls and partitions and piers; all bases, chair-rails, picture-moldings, hand-rails, and balusters for stairways; and all necessary woodwork for plumbing.

LUMBER.—The lumber used throughout the building, except where otherwise specified, is to be of best quality, kiln-dried or time-seasoned, clear, white pine (poplar, especially yellow poplar, known in some sections as "white wood," is admirable, especially for framing; it

holds nails well and paints and stains well), free from sap, shakes, or knots, and to be primed as soon as put up.

BALLOON FRAME.—The house is to be put together with balloon frame in the strongest and best manner, and in accordance with the framing drawings and plans with interties and angle-braces; and there shall also be diagonal "long" braces or struts for the full length of story joists of each story, with the joist cut in to hold the foot of the strut.

The frame and roof sheathing shall supplement and protect the mason-work, and the water-table shall project over the face of underpinning and foundation.

The floor-beams of second and third floors shall be notched over the ribbon or girt, to tie the building, the ribbon strip being let into the floor-beam, and wherever they come against studs the floor-beams shall be nailed securely thereto with three nails.


By balloon frame, as heretofore explained, is meant a construction in which the inclosing studs in side-walls run in single lengths from the sill to the wall-plate, with proper interties. The studs should be securely spiked to the plate, and to the interties and girts or ribbons, with exterior sheathing and back-plastering, which insures two sets of lathing—lathing having more or less strengthening and tying effect. This, with the diagonal braces or struts, insures a very strong house.

BRACED FRAME.—A somewhat stronger and better but more expensive construction is known as the "braced" frame. In this case the floor-beams or joists are supported on timbers called "girts" and "dropped girts," framed into the corner posts, and pinned with wooden pins. Angle-braces are also relied upon at all angles. (See diagram illustrating opposite.)

If a braced frame is desired, the paragraph as to balloon framing should be omitted, and the following inserted:

BRACED FRAME.—The house is to be put together with a full-braced frame in the best and strongest manner. The first-story beams are to be sized and leveled upon the sill and upon the foundation wall, and their tops made level. They are to be well spiked to the sill. The beams of upper floors are to be notched down on to the girts and sized upon partition-caps, spiking them strongly to form ties across building.

All sills, girts, and posts are to be securely framed into each other, mortised and fastened, with hard-wood pins or treenails, and angle-



**BRACED FRAME SHOWING NAMES OF TIMBERS, SHEATHING
TRUSSED WINDOW, ETC.**

braces are to be used at all angles and corners, securely mortised, draw-bored,* and pinned.

TIMBER DIMENSIONS

BEAMS OR JOISTS.—All floor-beams or joists of first, second, and third stories shall be 3"×12" (3"×10" are cheaper, but not so good), 16 inches from centers, of yellow pine, and they shall be notched or sized on their supports, so that their upper surfaces shall be level.



CROSS BRIDGING OR STRUTS BETWEEN FLOOR BEAMS.

bone bridging, 2"×3" every 5 feet, between beams, firmly nailed with two nails in each end.†

All floor-beams above the first tier shall be notched over the girt or ribbon, to properly tie the building, the ribbon being let into the beam and into the studs; and the first tier of beams shall be notched so as to rest on the sill and also on the cellar walls or underpinning for a better bearing.

NOTE.—It is better to have a middle wall of brick in the cellar, 8 inches thick, to carry the ends of floor-beams, rather than to employ a girder with posts or brick piers. It costs more, but do not omit it. If wooden posts are used they should be set upon a stone above the level of the floor, to prevent rot. Never have stud partitions in a cellar, as they are liable to decay and to breed vermin.

RAFTERS.—Main rafters shall be 2"×6", set 16 inches on centers. Hip-rafters 4"×8", securely spiked to the plate and notched thereon.

All hip- and valley-rafters to be extra width if jack-rafters are employed, so that the lower edges of the latter will not project below the bottoms of the former.

NOTE.—If the main rafters are unsupported for a greater span than 18 feet, they should be 2"×9", 16 inches on centers; or if slate roof,

* i.e., the hole for the pin is bored nearer the shoulder of the stick or beam than the hole in the mortise. As a consequence driving the tapering pin draws the two together and makes a firm joint.

† Some builders simply nail plank with squared ends between the beams. This adds to the weight to be carried without strengthening the floor. The cross bridging strips should extend from the top to the bottom of beams, forming an X between them, strengthening them like a truss.

(The next best and cheapest timber is spruce, and the cheapest hemlock.) There shall be proper cross, herring-

3"×8", 16 inches on centers. I prefer 2"×12" rafters, 12 inches on centers, to 3"×8", 16 inches on centers. For longer spans the roof should be trussed by king-post or king- and queen-post bracing, with collar-beams and tie-beams.

HIPS.—The hips shall be 3"×10".

GIRTS.—The girts shall be 2"×6" (if braced frame, 4"×10").

INCLOSING AND PARTITION STUDS.—The partition and inclosing studding shall be 3"×4". (Some prefer 2"×6", especially with back-plastering.) Door and window studs, 3"×4", set double. Where partitions have no support beneath, there shall be 4"×6" struts from floor to floor in such partitions.

There shall be double studding at sides of all windows and doors, and the studding shall be trussed over all window- and door-frames more than three feet wide.

Where a partition of one story comes directly over a partition of the story below, the studs of the upper partition shall foot directly on the cap of the lower partition, or on the supporting girt of the floor-beams, and not upon the floor-beams; and in all cases where it is unavoidable to have a partition foot upon the floor-beams, the studs shall be arranged to come above the beams, and to foot upon a sole of yellow pine 1 inch thick and 6 inches wide, or 2 inches wider than the stud. This contractor is to set all studs, between which furnace hot-air pipes come, sufficiently wide apart to leave 3 inches of space between the hot-air pipe and any stud, and he is to confer with furnace contractor for dimensions.

SHRINKAGE.—The contractor is to see that equal quantities of shrinkable timber are under the vertical studs or posts of parallel walls or partitions in all cases.

NOTE.—This is very important. Beams and other timber laid horizontally shrink materially in thickness—it being remembered that timber shrinks crosswise, and not lengthwise. If there should happen to be 10 or 12 inches more of timber footing under the beams of one partition than under those of another, there will be irregular settling of the floor-beams and breaking of the plaster ceilings. It is easy to remedy this, for in cases where it is not possible to cut down the amount of timber on one side, the footings on the opposite side can be built up to equal it.

CENTER STUDS.—This contractor shall set a stud in the middle of each side-wall of the dining-room, parlor, hall, library, and principal bedrooms, to provide for the hanging of heavy mirrors, pictures, armor trophies, etc., except where such center space is occupied by a window or door or a chimney-breast.

No wood shall be inserted in a chimney-breast where it will be within 8 inches of the inside lining of a smoke-flue.

PLATES.—The plates shall be 4"×6". **POSTS.**—The posts shall be 4"×8".

SILLS.—The sills shall be 4"×8". (If balloon frame, 4"×6", i.e., 2"×6" double, and boxed sills shall be made in the strongest manner.) All sills shall be halved at corners with beveled joint and set in cement mortar on top of foundation wall.

ATTIC CEILING JOISTS shall be 3"×8", 16 inches on centers.

BRACES, 4"×6".

PLASTER GROUNDS AND FURRING.—Fur walls, etc., for plaster, and set $\frac{3}{8}$ -inch grounds for plasterer.* This contractor shall fur for back-plastering between exterior studding with 1"×1½" spruce furring strips. (If it is desired to back-plaster the rafters and attic, so specify.)


INTERTIES shall be 4"×10", framed into posts and spiked to studs.

VERANDA AND PLAZZA TIMBERS.—Beams shall be 4"×10", framed into sills, 3 feet from centers. Girders, 4"×8". Sills, 4"×10", or 2"×10" double. Joists, 2"×10", 12 inches on centers. Hip-rafters, 3"×10". Rafters, 2"×6", 16 inches on centers.

Ceilings of porches and balconies shall be of $\frac{3}{4}$ "×2½" planed, tongued, grooved, and beaded yellow pine, well seasoned, clear of knots, sap, and shakes. The ceiling on rafters to be finished with fillet and cove.

The floor shall pitch from building to the front of piazza $\frac{1}{4}$ inch to every foot of width.

Columns of veranda to be of best yellow pine, 12 inches in diameter (if smaller desired, so specify), natural-wood finish, well seasoned, and center-bored. (White wood is less expensive, and good enough if they are to be painted. Plain, boxed, painted columns are cheaper still.)




STIRRUP IRON FOR SUPPORTING HEADER.

HEADERS AND TRIMMERS, 4"×10", framed with mortise and tenon and tusk-joint, but if carrying more than three tail-beams they shall be secured to the trimmer-beams with wrought-iron stirrup-irons, sometimes called "bridle-irons."

FRAMING.—All framing to be substantial, properly braced and plumbed.

*Grounds are wooden strips set as guides for thickness of plaster surfaces.

All beams and joists shall have the crowning-edge placed upward, and shall be properly sized and securely fastened together. (NOTE.—As a result of seasoning it often happens that one side of a beam or joist will become convex or rounded. This is called the crowning-edge.) All trimmers and headers, if less than 4"×10", shall be framed double, and there shall be not less than 8 inches space between woodwork and the inside of any flue or chimney.



FIRE PLACE SHOWING HEADER, TRIMMER AND TAIL BEAMS.

SHEATHING.—The building is to be sheathed on the outside frame with good, sound, tongued, and grooved hemlock boards, free from loose knots or holes, planed one side, not exceeding 6 inches in width and not less than $\frac{3}{4}$ inch thick, nailed with two tenpenny nails to every bearing, and driven close together. The sheathing is to be placed on the studs of the frame horizontally, and not diagonally.

NOTE.—As stated on page 16, some experts prefer diagonal sheathing. I find the majority favor horizontal nailing. It is, moreover, less

expensive in material and labor. Let every man be fully persuaded in his own mind. Where clapboards are used the joints may occasionally coincide with the joints of the horizontal sheathing—an objection; with shingles it does not make any difference.

The outside of the sheathing shall be thoroughly covered with the best quality of building-paper, the joints well lapped and secured by shingle nails, protected with tin washers not less than $\frac{3}{4}$ inch in diameter. Use best quality of heavy, rosin-sized building-paper. (Tarpaper objectionable.)

SHINGLED SIDE-WALLS.—The shingles are to be first quality, 16-inch cedar shingles, uniform size, plain butts, clear of knots and cross-grain, and to be nailed with two galvanized nails in each shingle. They shall be laid 5 inches to the weather.

CLAPBOARDS.—Those portions of the wall indicated on the plans to be covered with clapboards shall be covered with pine clapboards, sap extra, laid to an even gage not more than $4\frac{1}{2}$ inches to the weather, to be securely nailed with galvanized nails, set in for puttying, to every stud.

EXTERIOR WOODWORK.—This shall be of best quality of white-pine lumber, as specified, and shall be well painted before being put up, with back primed.

ROOFS.—The roofs shall be covered with sound, tongued, grooved, and planed hemlock (or pine) boards, not over 6 inches wide, nor less than $\frac{3}{4}$ inch thick, well nailed to every rafter. These shall be covered with double thickness of best-quality, heavy sheathing-paper (quality to be approved by architect), well stretched, lapped, and nailed through tin washers $\frac{3}{4}$ inch in diameter.

All roofs and sides of dormers to be covered with first quality of Monson or Bangor slate (in some sections Pennsylvania slates are cheaper), 9"×18", properly trimmed, and provided with counter-sunk drilled holes, all slates to be laid in parallel courses, 7 inches to the weather, each slate to be nailed with two galvanized-iron nails with wide heads, and all nail-heads to be covered. Slates at all ridges, hips, valleys, and eaves are to be trimmed so that the bond will be uniform and, where necessary, mitered and set in slater's cement, except where copper ridge-rolls and ridges are specified. Put ridge-boards, 1"×8", and ridge-rolls to all ridges. (See illustration, page 91.)

NOTE.—If the slate is laid in mortar it makes a cooler roof and insures a better bedding for the slate, securing immunity from breaking. If decided upon, it costs something more, and should be specified at this point.

SHINGLE ROOF.—If a shingle roof is desired, the specifications should read as follows: "Roof to be covered with first-quality cedar shingles, of uniform size, plain butts, clear of knots and cross-grain, to be nailed with two galvanized-iron nails with wide heads in each shingle, and laid 5 inches to the weather. They shall be securely nailed to $1\frac{1}{2}$ " \times $2\frac{3}{4}$ " shingling strips, nailed 2 inches apart on the sheathing of the roof.

(These secure an air-space between the sheathing and the shingles, and will make the roof cooler and tend to prevent decay from moisture, which will be slow in drying where the shingles are applied flat to the sheathing. If it is desired to lay the shingles in lime mortar it should be here specified. It is a mistake to lay shingles in lead paint on the sheathing, as it tends to rot them.)

COPPER ROOF.—If a copper roof is desired, tinned copper should be specified, in order that joints may be soldered.

CORNICES.—Finish with fascia, belt, etc., as per detail drawings.

PIAZZAS, VERANDAS, ETC.—These shall be constructed in the strongest and best manner, in accordance with detail of working drawings to be prepared by the architect. Timbers to be of sizes already specified, and flooring to be best yellow pine, clear and free of sap, shakes, and knots, $1\frac{1}{2}$ inches thick and $2\frac{3}{4}$ inches in width, the joints to be laid in white-lead paint mixed thick. The floor shall incline to front $\frac{1}{4}$ inch to every foot. The piazza columns, where they rest upon the flooring, shall be laid in lead paint mixed thick, and the joint well puttied.

NOTE.—Be sure to avoid sap lumber in the piazza floors, as it decays rapidly when exposed to the weather.

FLOORS.—All floors are to be laid double, with an under floor of $\frac{3}{4}$ " \times 6" planed, tongued, and grooved hemlock (or North Carolina pine; this is pine with the pitch removed; it is cheap and better than hemlock), laid diagonally on floor-beams. On top of this floor is to be laid salamander or asbestos paper (specifying thickness desired). (Where a fire-stop is not desired, best quality of waterproof building-paper can be used, the kind to be specified.) The top floor shall be of best seasoned, clear, comb-grain yellow pine, free from sap, shakes, and knots, $\frac{3}{4}$ inch thick and $2\frac{3}{4}$ inches wide, tongued, grooved, and planed, blind-nailed in the tongue, without broken or defaced edges. In some sections white pine for floors is very much cheaper.

The under floor shall be carried between the studs to the outer sheathing, fitted closely to cut off drafts from story to story, and form support for fire-stop, brick "nogging," etc.

While all of the flooring is to be of the best quality, the contractor is to select the choicest for the parlor, dining-room, hall, library, and principal bedroom floors.

BORDERS TO HEARTHES.—There shall be neat borders, 3 inches wide, with mitered corners, laid around all hearths.

BASE-BOARDS to be as per detail, blocked behind, and laid close to floor, and plastered behind down to the floor.

FLOOR-DEAFENING.—All floors shall be deafened with a concrete 3 inches in thickness (2 inches if beams are 2"×10"), composed of one part in volume of cement, three parts sand, and five parts well-screened cinders, mixed with as little water as possible, and supported below each floor by deafening-boards on shoulder strips, $\frac{3}{4}$ "×2", nailed to the floor-beams 3 inches below the tops of same, said boards to be $\frac{1}{2}$ inch thick and nailed crosswise of the beam. (NOTE.—Mineral wool makes a good deafening for floors.)

DOORS.—The main front door (and any others specified to be of hard wood) shall be of clear white pine-core, 1 $\frac{1}{2}$ inch thick, veneered with quarter-sawn oak $\frac{1}{2}$ inch thick on both sides, the door to be paneled and molded on both sides, as per detail, the main entrance to have 2-inch solid rebated jambs of oak. (NOTE.—Hard-wood outside doors are best made built up of staves or flat pieces glued together.) All other doors shall be first-class four-panel "stock" doors, double-faced, made of best white pine, well seasoned, 1 $\frac{1}{2}$ inches thick. Where any inside door swings back against a furnace register or is exposed to stove or other heat it shall be a veneered door. All doors to have the usual trim, architraves on both sides, and to be hung with loose-joint butt-hinges large enough to swing clear of the architraves.

VENEERED DOORS.—Note, if other doors are desired veneered they should be specified.

DOOR-SILLS OR THRESHOLDS to be of hard wood (specify oak, yellow pine, etc., as desired). All sills to outside doors shall be fitted with rebates to keep out rain or snow.

SIZES OF DOORS as follows: first story, 7 feet 6 inches, etc.

All sliding doors shall run upon overhead trolleys, and the frames in which such doors run shall be well cased in pockets with $\frac{1}{2}$ -inch tongued and grooved material, especially above the trolleys, so as to prevent drafts of air.

Stop to be placed in pockets back of doors.

The door between dining-room and butler's pantry shall be a swing-

ing or fly-sash door, as shown on plan, the glass to be ground glass, except that it shall have a border of clear glass $\frac{3}{8}$ inch in width, with corners, key pattern. (This to enable persons approaching to see each other and to avoid collision. Any ornamental design may be specified, but a neat and inexpensive finish is the one indicated.)

BEDROOM DOORS.—All bedroom doors shall have ground-glass transoms or fan-lights, the glass to be not less than 12 inches high; all to be furnished with bronze adjustable-lever transom-openers.

BASE-KNOBS AND FLOOR-STOPS.—This contractor is to put rubber-tipped base-knobs behind all doors, of maple or the wood to correspond with the trim of the room. (This will add little to the bid of a contractor estimating, but will cost one hundred cents on the dollar if omitted and inserted afterward.)

HATCHWAY DOORS TO CELLAR.—These to be made of clear white pine $1\frac{1}{2}$ inches thick, tongued, grooved, and beaded, cross-battened on the back with four cross-battens of $1\frac{1}{2}$ -inch pine, $4\frac{1}{2}$ inches in width, beveled edges, the battens to be screwed on; the doors to properly lap the opening at the head and sides, and to shed water over the top-step stone. Hang the doors with three sets of best strap-hinges to each fold, and attach a strong oak bar with staples on the inside for fastening the same.

STAIRS.—All stairways shall be built where located on plans in the strongest manner, and shall be put up after plastering is dry. They shall have strong plank-strings not less than 2 inches in thickness, and if either string is not supported by a side-wall or partition it shall be $3'' \times 8''$. In all staircases there shall be a center carriage-timber not less than $3'' \times 8''$. The main staircase shall have treads not less than 12 inches wide, excluding the nosing, framed or housed into the string, with risers not more than $6\frac{1}{2}$ inches high, and the treads shall be not less than $1\frac{1}{2}$ inches thick. All treads and risers shall be properly wedged, glued, and blocked, and the treads shall be plowed or housed into the risers, and the risers plowed into the under side of treads. The main staircase treads, stringers, and risers shall be of the best quarter-sawn oak (if cheaper wood is desired, specify it), and finished as per detail. All staircases shall be strongly bracketed under each step.

The rear and attic stairs to be of best quality yellow pine. They shall not be less than 3 feet 6 inches wide in the clear.

OUTSIDE PIAZZA STEPS.—The outside steps shall be constructed of

strips $1\frac{1}{2}$ inches thick and 2 inches wide, placed $\frac{1}{2}$ inch apart, the outer strip of each step being 3 inches wide, to allow for projection or nosing.

(If it is preferred to have board treads, the specifications should here provide that they shall be bored with small auger-holes, ornamental pattern, to drain off the water.)

NEWELS, RAILS, BALUSTERS.—These shall be of the best quality of quarter-sawn oak for the main staircase, and of ash for all other staircases, as shown in the detail. All balusters shall be firmly dovetailed to the treads.

FIRE-STOPS.—All staircases shall be properly fire-stopped, to prevent the passage of fire through the interior from story to story.

INTERIOR FINISH.—Base-boards shall be put down in all rooms and halls, and shall be set upon the under floor if the floors are double, or tongued into the floor-plank if the floors are single (this is important, as it will prevent joints opening between the base-board and the floor as the wood shrinks), beads on all angles, the base 8-inch molded throughout, except in closets, where there shall be 6-inch base-boards. The window trim shall be pilaster finish, with base and turned-corner blocks and $5\frac{1}{2}$ inch rebated stool with apron, made of casings returned at each end.

Sweeping moldings shall be placed around the foot of bases in all rooms and closets.

All standing trim to have back primed before put in place (this important, as it will save injury to it from dampness in new plaster).

MANTELS.—These will be furnished by the owner and set by this contractor (if to be set by the mantel man, so specify).

PICTURE-MOLDINGS.—There shall be a 2-inch picture-molding, as per detail, fitted around all rooms of the house, including bath-room, excepting attic, kitchen, closets, laundry, and pantries. This to be of pine, or wood to correspond with finish. (If a gilt molding or hardwood molding is required, so specify.)

CLOSETS.—All closets and pantries shall be fitted up as shown on plans, with drawers, shelves, and neat hook-racks or cleats, planed and beaded, for the reception of double wardrobe hooks, which shall be of best quality bronze (or japanned iron, if preferred), the hooks to be furnished by contractor. The hooks, unless otherwise specified, shall be at the height from the floor of 5 feet 6 inches for the top rack and 4 feet 6 inches for the lower. There shall be shelves in all closets, 1-inch stuff, 14 inches in width, commencing 8 inches above the hooks,

and painted two coats. (NOTE.—It improves the shelves to be painted and costs little, protecting them from grease-stains, etc.)

The ceilings of all closets to be same height as those of rooms.

MOTH-PROOF CLOSET.—Here specify for cedar- or camphor-wood lined closet, if desired (see page 44).

LINEN-CLOSET.—There shall be drawers and shelves in closet, as shown on plans. Plan should show shelves and drawers.

BUTLER'S PANTRY.—This shall be of size shown on plans, and shall be fitted up with counter-shelf and closets with glass sliding doors, as shown; also with panel doors.

This contractor shall furnish all the trim for the butler's pantry, including dish-heater, and shall build drip- and frame-work for butler's sink, which latter is to be furnished by plumber, all as per details.

Shelves, wherever specified, shall be of $\frac{3}{4}$ -inch pine lumber, with turned supports, and shall be painted both sides.

KITCHEN.—Kitchen dresser shall be furnished the same as for butler's pantry; cupboards as shown.

Put neat clock-shelf in kitchen.

This contractor shall do the necessary framing for sink.

CLOTHES-CHUTES TO LAUNDRY, if provided, should be of metal, not wood.

DUMB-WAITERS.—The shafts for these should be, if of wood, lined with tin, with lap-welded or folded joints. In brick or stone houses it is well to have them constructed of incombustible materials, so that they will not carry flame from one story to another. There are convenient patent dumb-waiters in the market.

STORE-ROOM.—Behind the plastering of the walls and ceiling of the store-room, and between the double floors thereof, shall be inserted galvanized-wire netting, $\frac{1}{2}$ -inch mesh, securely lapped at corners and angles, so as effectually to exclude rats, mice, roaches, and other vermin.

WAINSCOTING.—The kitchen and bath-rooms shall be wainscoted, 3 feet 6 inches high, with $\frac{3}{4}$ -inch Georgia pine (or other hard wood, ash, etc., as may be preferred) 3 inches wide, planed, tongued, grooved, and beaded, with a molded cap, to be finished with filler, etc., as specified for interior woodwork.


NOTE.—If bath-rooms are desired to be more safe as to fire, they should be wainscoted with marble, tiling, or cement, and it should be so specified.

TANK.—The tank is to be located as shown in plans, and is to have a capacity of 500 gallons, measurements to be taken between the bottom of overflow and the pipe which supplies house. It shall be built in the best manner, of 2"×4" stuff, laid flat, woven at corners, and lined with 16-ounce tinned copper, the copper to be furnished and lined by plumber.

There shall be a scuttle near the same and a strong ladder with treads 4 inches wide, furnished by this contractor.

If iron tank is desired, so specify at this point.

CORNICES.—All outside cornices shall be constructed in the best manner, and shall be painted with three coats of best paint. (It is perhaps better to specify two coats, and have the third put on the following spring.)



CONSTRUCTION OF GUTTERS.

GUTTERS.—These to be of best-quality 16-ounce copper, secured by galvanized-iron hangers, securely fastened to the roof under the slate by galvanized-iron nails or screws. To be not less than 6 inches wide.

The arrangement of gutters is a more important matter than is generally supposed. They should be, if of wood, lined with metal, copper being best of all, on account of its exemption from rust, and the several pieces of which the gutter is composed should be tongued

into each other, the joints being set in white-lead paint. Fascia should be constructed to prevent water from backing up against the side of the building, and drip-points to all vertical pieces should be made so that water would drop from these points without running against and down the side-wall.

The matter is illustrated in the accompanying diagram.

Where hanging metal gutters are arranged great care should be observed in having the hangers of galvanized iron, and the gutters also, although copper is, of course, better.

Gutters should be so arranged as to be safe from injury by sliding snow from a pitch roof. While extending sufficiently beyond the line of shingles to catch the rain-water, the outer edge should be sufficiently lower than the line of the pitch roof to insure that snow and ice shall slide beyond the outer edge and not strike the gutter. This feature of the gutter can be tested by laying a straight edge on the slanting roof and observing that the outer edge of the gutter is below the line of the pitch.

LEADERS AND CONDUCTORS.—To be of 16-ounce copper, and to be not less than 3 to 4 inches in diameter, inside measurement. Furnish and insert copper basket-ball leaf-arresters in gutter-openings to leaders.

FLASHING.—All flashings shall be of 16-ounce H. C. rolled copper (if galvanized iron, tin, or zinc desired for cheapness, so specify, and paint both sides), and this contractor is to properly flash all valleys, hips, ridges, angles, or other places requiring flashing, the flashing of valleys in no case to be less than 14 inches wide. The flashing shall not extend less than 18 inches under the slate or shingles, on the upper side of chimneys, dormer-windows, or other places where snow or water is liable to back up against the roof; and in the case of chimneys it shall be securely cemented into groove or joint in the brickwork for a height of at least 8 inches above the roof, and lap over the flashing below, which shall extend up $7\frac{1}{2}$ inches from roof, but the lap shall not be within 1 inch of the roof. (NOTE.—This to prevent ascent of water by capillary attraction.) Where shoulders occur in roofs, tending to lodge snow, crickets or pitch roofs shall be made to slide snow beyond roof.

All ridge-rolls and hip-rolls shall also be covered with copper saddles extending over ridges.

HARDWARE, METAL-WORK, ETC.—All doors and windows are to be fitted complete with all hardware required, of best bronze, manufactured by——(state any manufacturer preferred), and approved by the architect.

The owner will furnish all locks for doors, striking-plates, escutcheons, belts, door-hinges, door-knobs, closet-catches, sash-lifts, and

sash-fasteners. This contractor is to furnish all other hardware and metal-work and fixtures for the building, including the metal sash-chain, which is to be of best quality of red metal, and all sash-weights. All sash-weights exceeding 20 pounds in weight shall be of lead. He is to accurately weigh each sash separately, to insure proper balance of weights.

This contractor is to attach and put in place all hardware furnished by the owner, as well as that furnished by himself, and to notify owner when it is wanted, giving list and description of that to be furnished by owner as above.

The front and outside doors are to have mortised bolts.

The bedroom doors shall have mortised bolts with brass knobs.

All sliding doors and sliding sash shall have bronze knobs, locks, etc., and all small closets, presses, and drawers shall have suitable locks and other hardware approved by the architect.

CLOCK-SHELVES.—Put neat clock-shelves in servants' rooms, as well as in kitchen (elsewhere provided for).

NOTE.—These are simple matters, but will practically add nothing to the cost of the house if included in the specifications.

WINDOWS AND SASH.—All window-frames, except where otherwise specified, shall be of stock sizes and shall be constructed in the best manner, as per working drawings. The pockets for weights shall be of proper size.

COPPER POCKETS TO WINDOWS.—The tops, sides, and bottoms of outside window-casings are to be covered with 16-ounce copper, tacked closely on the caps and sides of window-frames and run under the weather-boarding or shingling of the side-wall at least 3 inches. (Other metal, zinc, tin, etc., may be specified if economy is desired.)

If the side-walls of the building are of stone, some experts insist the window- and door-frames should not be inserted until after the walls are laid and the stonework brought to a smooth square finish for the openings.

All the lifting sashes throughout the building are to be carefully weighed and balanced, and hung with metal chain, approved by architect, all on grooved square, 2½-inch channel, noiseless axle-pulleys, furnished by this contractor.

All sashes to be of best, clear white pine, 1½ inches thick, except that where plate-glass is specified the sash shall be 2 inches thick, and all sash shall have weather-lipped meeting-rail and acorn-mold sash-bar.

It will be found convenient to fasten the stop-heads of windows to the frames with nickel-plated screws instead of nails, so that the sash may be removed more easily as occasion may require.

PANELS under windows shall be finished without any hollow spaces behind them, and plastered at this point down to the floor.

All frames shall be properly primed before being brought to the building.

All windows shall have the proper trim.

Architraves on windows on the outside walls and piers are to be set on the inside casings and window-boxes.

Specify height of window-sills from floor. (See page 39.)

CELLAR WINDOWS.—The frames to be of 2-inch clear white pine, to be built in the wall or underpinning when the same is being laid; window to be protected by an iron grating of galvanized-iron rods $\frac{3}{4}$ inch in diameter, placed perpendicularly and let into the frame at top and bottom, with storm-sash, as elsewhere specified.

GLASS.—All sash marked "plate" shall be best quality polished American plate. All windows not designated for plate-glass shall be glazed with double thick first-quality glass.

BLINDS.—All windows shall have best quality of outside blinds, with rolling slats, made of dry, clear white pine, $1\frac{1}{2}$ inches thick, hung on wrought-iron right-angle butts, and furnished with fastener and best quality of blind-adjuster; to be painted with best quality of paint—color as indicated by owner.

STORM-DOORS AND -SHUTTERS.—All doors, windows, and other openings on the first floor, and cellar openings, shall be provided with storm-doors and -shutters, made in the strongest manner, of tongued and grooved white pine, $\frac{3}{4}$ inch thick and 3 inches wide, nailed with galvanized wrought-iron nails clinched. Each shall be plainly marked to indicate the window or door to which it belongs. They shall be painted both sides with two coats of the best paint, inside white and outside to correspond in color with the window-frames of the house. (If desired, small glass lights may be let into the shutter. Be sure to have them water-tight.)

The storm-door of the kitchen shall be hung on hinges and fitted with a Yale lock, using the same key as the lock to the main kitchen door, which shall also be a Yale lock. (See page 46.)

PLUMBING.—The plumbing work of all basins, water-closets, and sinks is to be left exposed, so that no woodwork will be required. All

plumbing or other pipes running from story to story shall be protected by this contractor with wooden ducts or boxing of tongued, grooved, and beaded narrow stuff. (Here specify pine, oak, ash, or other wood decided upon.) It shall be fastened with screws, so that it can be removed to examine pipes at any time.

This contractor is to make all pockets and boxes that may be required for electric cut-outs; these to have hard-wood panel covers, secured with hinge, as directed.

RUBBISH.—At such times as the architect may direct, this contractor is to gather up all of his rubbish and surplus materials, and put same in barrels, to be removed from the premises. He is to leave his work clean and perfect on the completion of the building.

TEMPORARY PRIVY FOR WORKMEN.—This contractor is to construct proper roofed and inclosed privy, where directed, for workmen, and to remove same when building is finished.

COAL-BINS IN CELLAR to be built where shown and as per detail.

COLD ROOM.—Construct cold room for milk, food, etc., in cellar where shown on plan, the frame to be of pine, covered with fine-meshed copper wire. (If cheaper, green wire preferred, so specify; the difference in cost is slight.)

(If other closets desired in cellar, for wine, etc., here specify.)

PERSONAL SUPERVISION.—This contractor is to give his work his personal superintendence, and is to keep a competent foreman constantly on the premises, and he is not to sublet the whole or any part of his work without the consent in writing of the owner.

ALTERNATE ESTIMATES.—This contractor is to submit estimate for all the woodwork throughout the building to be of quarter-sawn oak, instead of pine. Also to submit estimate for woodwork in ash. Also to estimate for floors to be laid with best quality of North Carolina pine instead of best quality of yellow pine.

(Any other alternate specifications which owner may desire for cheaper or better construction may be here inserted, so that he may be able to decide on a more elaborate or more simple finish, if he chooses.)

MASON'S SPECIFICATIONS

SPECIFICATIONS OF MASON'S WORK, for a dwelling to be erected for JOHN DOE, Esq., located at —.

These specifications are to accompany drawings, made by JOHN SMITH, architect, under whose supervision the work is to be done.

The drawings and specifications are to coöperate, so that anything shown on the drawings and not mentioned in the specifications, or vice versa, is to be done the same as if shown on both drawings and specifications. The drawings and these specifications, moreover, are to be carried out to the full meaning and spirit.

In cases where there may be doubt as to exact measurements, or where the scale measurements differ from the figures, the figures are to govern, and the contractor is to verify all dimensions that relate to his work, or to the joining, fitting, or adjusting of his work thereto.

He is also to take careful and exact measurements, and compare and copy wherever or whenever any new work is called for to be a counterpart of or similar to the present work; also to verify all measurements at the building whenever his work is subsequent to existing new work, and he is to be responsible for same, unless written notice is given by him to the architect, so that proper adjustments may be made in time.

This contractor must coöperate with all other contractors of the several works, so that work will not be constructed prematurely, necessitating its being taken down to allow the construction of work that should have been previously executed. He is also responsible for the proper adjustment of his work with other works, and to repair, join to, and make his work perfect.

This contractor is to furnish all materials, including water, for the work herein specified, and they are to be the best of their several kinds, subject to the approval of the architect; also all tools, molds, scaffolds, planks, and plant necessary to carry out his contract.

All the work is to be done in the best manner, according to the full meaning of the plans and specifications, and subject to the approval of the said architect.

In case any materials are not approved, they shall be promptly removed from the premises.

This contractor is to be responsible for any violations of the laws or ordinances, whether State or municipal, for the constructing of buildings, and is to hold the owner harmless from any expense or claims for damage to life, limb, or property arising from any violation of such laws, ordinances, or regulations, or caused by or in consequence of carelessness of himself or his employees.

This contractor is to furnish everything necessary to enable him to do the work required in these specifications, and to comply with his contract, such as scaffolding, tools, derricks, inclosures, bridges, platforms, plankings, and planks for scaffolding for stone-contractors.

He is to keep the cellar free from water, and his work under this contract shall include all that shown on the drawings and set forth in the specifications, including the following items: excavations, all brickwork, all stonework, all fire-proof partition work and beam arches, if any, all concrete and deafening, except the concrete of the cellar floor, which is included in the plasterer's work. (Some prefer to have the mason do this work.)

LIME MORTAR.—Lime mortar, where specified, shall be mixed in the following proportions and manner: only the best quality of well-burned stone lime is to be used; no shell lime will be permitted. It shall be slaked in a water-tight box of planks, with plank bottom 12 inches deep, and the lime shall be introduced one cask at a time, to which shall be applied two barrels of water to one barrel of lime. The pen shall then be covered until the whole is reduced to a smooth uniform paste, after which clean sharp sand shall be added in the proportion of two parts in volume of sand to one part of lime paste. No mortar shall be mixed in the cellar after first tier of beams is laid. (See page 118.)

NOTE.—Under no circumstances should lime be slaked on the bare ground, or in a hollow made by an embankment of sand—and yet this is the common practice. The water is, also, frequently applied with a hose. It should be added to the lime in volume by upsetting a barrel as quickly as possible. After the lime paste is made it should be allowed to stand as long as possible before being mixed with the sand. The proportion of one part of lime paste to two parts in volume of sharp sand is about equivalent to one part of dry lime and four parts of sand. Where cement is added the mortar must be used immediately after mixing the cement, as it is liable to set rapidly.

The lime should be properly stirred while slaking, but much of the stirring will be saved and the mortar will be improved by the covering of it as quickly as possible.

Lime mortar made in this way may stand for weeks, but, as already stated, cement mortar must be used at once.

LIME AND CEMENT MORTAR.—Lime and cement mortar shall be mixed one part cement, one part lime, first reduced to lime paste, and two parts clean, sharp sand.

NOTE.—This does not give as strong a mortar as cement without the

lime, which, added, causes the mortar to set more slowly. It is a common error to construe the phrase "one half cement" to mean one part cement to two parts of lime; but what is meant is one cask of cement to each cask of lime, not half a cask of cement to one of lime. The proportions are those used for United States public buildings.

CEMENT MORTAR.—Cement mortar, where specified, shall be mixed in the following proportions: one part in volume of best domestic cement (except where Portland cement is specified) and three parts of clean, sharp grit sand (except that in walls below ground and in cisterns the proportion shall be two parts sand), well and thoroughly mixed together, in a clean box of boards, before the addition of water. It must be used immediately after being mixed. Cement mortar left overnight shall not be used. The sand and cement shall be approved by the architect.

CONCRETE.—Concrete, where specified, shall be made in the following manner: one part in volume of best domestic cement (brand selected by architect), three parts of clean, sharp grit sand, and four parts of best, clean, washed gravel or clean broken stone, the pieces of which shall be small enough to pass in any direction through a 2-inch ring; except that concrete for the bottom of cistern shall be mixed one part Portland cement, two parts clean, sharp grit sand, and four parts clean gravel or broken stone, as above specified. It shall be measured dry and thoroughly mixed before water is added, and shall be of a consistency, when ready for use, to be capable of standing on a steep slope without the water running from it. It shall be then rammed carefully in place until the surface is moist, and shall be protected from disturbance by walking or otherwise for at least twelve hours.

EXCAVATIONS.—This contractor shall excavate for the cellar as shown by the foundation plan and 8 inches in excess all around to a sufficient depth to secure the height of ceiling prescribed for the cellar between the top of the concrete floor and the under side of the first-story floor-beams—8 feet.

He shall excavate all trenches under walls, and remove, if required, dirt and rubbish made, and shall grade around building as required, carefully removing all top-soil and loam to a proper distance, where it will not be in the way of other grading or work, which he shall afterward replace and prepare with a suitable surface for seeding or sodding.

He shall, after mortar is dry, fill in the excavation and "water-ram" the earth about walls, using sufficient water to puddle and settle firmly.

DRAIN- AND SEWER-PIPE.—He shall excavate trenches not less than 3 feet deep for all drain- and sewer-pipes, the trench for the sewer-pipe to the cesspool or sewer to have a fall of $\frac{1}{4}$ inch to 1 foot. He shall coöperate with the plumber, who shall furnish and put down the drain-pipe required.

BRICKWORK.—Wherever brickwork is required the bricks shall be of the best quality Haverstraw or Matteawan (or other manufacture which the contract may specify), hard-burned, fine, compact and uniform in texture, regular in shape, and uniform in size. No bats, crooked, cracked, swelled, "salmon," or "pale" bricks will under any circumstances be allowed in the work, and if taken to the premises shall be promptly removed therefrom. (By pale brick is meant half-burned brick, not the light-colored bricks intended to be light in color, which may be thoroughly hard and well burned, and which sometimes produce pleasing effects.) The bricks shall be laid, unless otherwise specified, with close-rubbed or "shove" joints, and every sixth course shall be a course of headers,* so that the bond will consist of five courses of stretchers and one of headers, except in cistern walls, where they shall be laid alternately one course of headers and one course of stretchers. (If bricks laid in freezing weather, to be laid dry and warm and in cement mortar; and if laid in non-freezing weather, to be well wet before being laid.)

The masonry walls shall be carried up evenly; no part shall be carried more than 4 feet in advance of the rest. All angles shall be properly bonded.

No grouting shall be permitted unless expressly specified. (Grout is liquid cement usually poured into the wall to fill joints. It is objectionable in stonework, but may improve brick walls.)

Brickwork intended to be plastered shall be laid with rough joints.

FOUNDATION WALLS.—All brick in foundation walls shall be laid in cement mortar, and the exterior to the surface of the ground shall be plastered with cement, and, when dry, covered with liquid asphalt applied in two coats. All other walls shall be laid in lime mortar, except that chimney-tops above roof and cistern walls shall be laid in cement mortar.

FOUNDATION FOOTING COURSES.—This contractor shall prepare a

* A "header" brick is one laid in the wall so that only its end shows, the lengthwise of the brick being at right angles with the face of the wall. A "stretcher" is a brick laid lengthwise of the wall.

footing course of concrete 1 foot thick, or of sufficient thickness to safely bear the weight to be imposed thereon, and 1 foot wider than the foundation wall—concrete mixed, as hereinbefore specified. A footing course of broken stone will answer. (See page 6.)

PIERS.—No piers shall be less than 12 inches square if of brick, nor less than 20 inches square if of stone.

STONEMWORK.—All stonework shall be carefully laid, with proper bonds, no wall to be less than 18 inches thick, each stone to be laid on its natural bed; and in foundation walls both sides shall be brought to face; no projecting stones to be permitted; all joints to be well filled and pointed. (It is a fault of some masons to lay foundation walls roughly on outside, leaving projecting stone ends. This is bad and leads to leaking cellars. If either side of the wall is rough it should be the inside face.)

WEDGING.—No wedging of joints above piers, etc., shall be done with wood—only slate shall be used. (Wooden wedges shrink as they become dry.)


RETAINING-WALLS.—No retaining-wall, unless otherwise specified, shall be of less average thickness than one fourth of its height. They shall be battered back $\frac{1}{4}$ inch to foot of height, and provided with "weepers," or drains, near the bottom at intervals of 4 feet, to carry off water.

PORCH AND VERANDA PIERS.—All porch and veranda piers shall go at least 3 feet below ground, and to the porch sills above ground. They shall have good foundations of concrete, and each shall be capped with a 3-inch stone of the full size of the pier.

CHIMNEYS AND FLUES.—The chimneys shall be carried up, as per drawings, from the ground. Above the roof black cement mortar shall be used, and all smoke-flues shall be surrounded with 8 inches of good brickwork, and shall be lined on the inside with a burnt-clay or terracotta flue-lining, from the bottom of the flue or from the throat of each fireplace continuously to the extreme height of the flue. The ends of such lining-pipe shall be made to fit close together, and the pipe shall be built in as the flue or flues are carried up. All flues for fireplaces shall be of a capacity 8"×12", and the furnace- and range-flues shall also be 8"×12" inside capacity. (NOTE.—If 8"×8" flues be desired, so specify.) Vitrified drain-pipe makes good flue-lining.

All flues which are not lined shall have struck joints; no parging or

HOW TO BUILD A CHIMNEY.



SECTION OF CHIMNEY SHOWING TRIMMER ARCH UNDER HEARTH, PROPER CONSTRUCTION OF FIRE PLACE, FLUE AND FLUE LINING, ASH CHUTE, ETC.

plastering will be allowed on the inside of any flue. (See page 34.) All flues should be lined, however. (See page 31.)

FIREPLACES.—Here limit height of fireplace—I advise 25 inches. The back of all fireplaces shall be inclined toward the front, beginning six courses of brick from the floor of the hearth, as per drawings (see diagram opposite), to secure a good draft, and the fireplaces shall be lined with firebrick, laid with close-rubbed joints (or with cast-iron fireplace-lining, as per design and pattern specified, if cast-iron is preferred). The front opening of all fireplaces shall be supported by two iron bars $\frac{1}{2}'' \times 2''$, 9 inches longer than the width of the opening, and shall be fitted with automatic ash-dump grate. This to be furnished by mantel man.

It will also be observed in the accompanying drawing that a level shelf appears in the flue above the fireplace opening. Descending currents of air and smoke strike this shelf, rebound, and return up the chimney without puffing out into the room. It is possible, and sometimes necessary, to have a cast-iron plate resting on this shelf, so that it can be drawn forward as occasion may require, to contract the throat of the flue, the capacity of which, as already stated, should correspond somewhat with the size of the fireplace opening, to the extent of having an area about one tenth or one eleventh of the latter.

Furnish and set proper iron thimble in furnace-flue.

The tops of all chimneys shall be laid in black cement mortar and shall be capped with a 3-inch capstone, and the openings in the capstone shall correspond in size with the dimension of each flue, so that no shoulder or other projection will extend over the opening.

No chimney shall be enlarged where it passes the roof to form any overhanging or projection over the roof.

The chimney walls from the cellar to first floor shall be carried up to form ash-pits, securely inclosed with brickwork, these to have $12'' \times 16''$ iron doors, with frame, in cellar, to be built in during construction. This contractor to furnish said iron doors.

No chimney shall be started or built upon any floor or beam of wood, and in no case shall a chimney be corbeled out more than 8 inches from the wall, and in all such cases the corbeling shall consist of at least five courses of brick.*

All hearths shall be constructed with trimmer-arches extending 20

* This is a provision of the New York building law, and it ought not to be deviated from in any case.

inches from the chimney-breast to a "skew back" or wedge-shaped piece of wood spiked to the header-beam, and the top of the arch is to be filled with 2 inches of concrete to the top of finish floor. The header-beam shall rest securely in stirrup-irons to be furnished by carpenter, and there shall be no wooden lath or furring on the chimney-breast.

It will be observed, in the accompanying illustration, that the trimmer-arch abuts upon a wooden skew back or wedge of wood securely spiked to the header-beam. The skew back is in turn supported by a fillet of wood spiked to the beam. This is necessary to secure a proper arch. If the footing of the arch comes squarely against the wooden header-beam the shrinkage of the latter will in time release the arch and allow it to fall. It is unfortunately, however, the practice not only to omit this skew back, but to omit the trimmer-arch altogether, and to support the hearth directly upon the floor-joists. This is a most dangerous construction, and a fire is only a question of time. It seems incomprehensible that an honest builder having any decent regard for safety to life would build in this way; and yet fires from this cause are frequent. In one case coming under my observation serious damage was done to a handsome dwelling, where the builder had not only constructed the hearth in this way, but had actually swept the wooden shavings from the floors into the hollow spaces under the hearth. But for the fact that the fire was extinguished in time to discover this evidence of criminal indifference to human life, the guilt of this builder, who was no better than a would-be murderer, would never have been known. The writer cannot too earnestly impress upon his readers again the importance of watching the construction of chimneys, hearths, etc. It involves small expense, but important consequences.

The range shall have a ventilating-flue by the side of the smoke-flue not less than 8 inches square, in addition to the smoke-flue, which shall be not less than 8"×12", lined with tile.

RANGE.—The range will be furnished by the heater man and shall be set by him. It shall have a hearth projecting not less than 3 feet in front of the same and of the full width of the range, of best quality of rubbed slate, 3 inches thick (or stone or encaustic tile laid in a proper manner), to be furnished by this contractor.

The mantel over the range shall be of rubbed slate or stone, 10 inches wide.

FURNACE PIT AND FOUNDATION.—This contractor shall lay the brick-work and concrete for furnace pit and foundation and the cold-air box where same passes under the cellar floor.

BEAM-FILLING.—This contractor shall beam-fill all exterior walls between the beams with bricks laid in lime mortar to their top level, same thickness as wall.

FIRE-STOP.—This contractor shall provide fire-stops at each story in all hollow walls and hollow partitions. He shall fill in solid between all upright studs or timbers to the depth of the floor-beams with suitable incombustible materials, using, wherever possible, bricks and lime mortar for the purpose. Where it is impossible for any reason to use bricks and mortar he shall use sheet-tin, which shall be carefully and closely nailed to prevent the passage of flame. (See illustration, page 19.)

In all furred brick walls the course of brick above the under side and below the top of each tier of floor-beams shall project the thickness of the furring, to more effectually prevent the spread of fire.

TILE HEARTHS AND FACES.—These will be furnished by the owner and set by the mantel man, the hearths upon concrete or masonry, and the facings set to brick masonry.

CELLAR WINDOW AND DOOR-SILLS.—All cellar windows and doors shall have sills of stone projecting at least 2 inches beyond the wall.

CELLAR BOTTOM.—If it is preferred to have the mason concrete the cellar floor the specification for this work contained in the plasterer's specifications should be inserted here. The concreting of the cellar should be the last work done, and after the building is secure from intrusion by other workmen, and for this reason it has been included in the plasterer's specifications. Not infrequently the mason does both the plaster-work and the mason-work, in which case it may be left in the plasterer's specifications.

CISTERN.—This contractor shall build a cistern 12 feet in diameter and 12 feet deep, circular form, located, as specified, in the following manner: A bottom 32 inches wider than the internal diameter of the cistern shall be constructed of concrete 12 inches thick, after the ground has been well settled and puddled with water; the concrete to be mixed in the proportions and manner hereinbefore specified, except that there shall be two parts instead of three parts of clean, sharp grit sand. When thoroughly set, the side-walls of the cistern, 16 inches in thickness, shall be laid upon the outer edge of the concrete bottom to a height of 3 feet, from which point for a further height of 3 feet they shall be 12 inches in thickness, and thence 8 inches in thickness to the top, the top to be drawn in with bricks laid as headers, 8 inches in thickness, to a 24-inch manhole, which shall be surrounded by a brick

curb and covered with a 3-inch flagstone or iron cover, with holes for ventilation.* The brick in walls up to arch of cover shall be laid in alternate courses of headers and stretchers—first a course of stretchers, then one of headers.

All brickwork of cisterns shall be laid in Portland cement, and the whole of the interior and exterior shall be plastered with two parts of sand to one of Portland cement, and after the cistern is finished the excavation shall be filled in carefully by puddling the returned earth with water and ramming hard every foot in height.

NOTE.—Much depends on doing this thoroughly, as the resisting strength of the cistern needs the sustaining pressure of the earth.

If it is desired to have a brick bottom, the cistern may be constructed with an inverted arch or concave bottom in the form of the bottom of a flask, instead of concrete.

If the cistern exceeds 12 feet in diameter and 12 feet in depth the thickness of the side-walls should be increased 4 inches for each 4 feet of excess over 12 in width or depth.

CESSPOOL.—Build cesspool, circular form, where specified, 12 feet deep. Lay walls in brick, dry, 8 inches in thickness, or 18 inches (dry) if of stone. Draw in the walls toward the top to a manhole 2 feet in diameter, the masonry of the arch top to be laid in cement mortar, and cover the manhole with a flagstone 3 inches in thickness and a cast-iron vent-pipe 4 inches in diameter. Return earth around sides when mortar is dry, and ram each foot hard, settling with water. The bottom to be of earth.

If there is any way of draining a cesspool it should be constructed with an inner and smaller chamber to retain the solids and permit the liquids to drain away. Be sure to have it far enough from the well.

SUPERINTENDENCE.—This contractor is to give his work his personal superintendence, and is to keep a competent foreman constantly on the premises, and he is not to sublet the whole or any part of his work without the consent in writing of the owner.

PLASTERER'S SPECIFICATIONS

SPECIFICATIONS OF PLASTERER'S WORK, for a dwelling to be erected for JOHN DOE, Esq., located at —.

* The cover should be so secured as to secure ventilation without permitting access to the water by insects, reptiles, or malicious persons.

These specifications are to accompany drawings made by JOHN SMITH, architect, under whose supervision the work is to be done.

The drawings and specifications are to coöperate, so that anything shown on the drawings and not mentioned in the specifications, or vice versa, is to be done the same as if shown on the drawings and called for in the specifications. The drawings and these specifications, moreover, are to be carried out to the true intent and full meaning of the specifications.

In cases where there may be doubt as to exact measurements, or where the scale measurements differ from the figures, the figures are to govern, and the contractor is to verify all dimensions that relate to his work, or to the joining, fitting, or adjusting of his work thereto.

He is also to take careful and exact measurements, and compare or copy wherever or whenever any new work is called for to be a counterpart of or similar to the present work; also to verify all measurements at the building whenever his work is subsequent to existing new work, and he is to be responsible for same, unless written notice is given by him to the architect, so that proper adjustments may be made in time.

This contractor must coöperate with all other contractors of the several works, so that work will not be constructed prematurely, necessitating its being taken down to allow the construction of work that should have been previously executed. He is also responsible for the proper adjustment of his work with other works, and to repair, join to, and make his work perfect.

This contractor is to furnish all materials for the work herein specified, and they are to be, except where otherwise specified, the best of their several kinds, subject to the approval of the architect; also all tools, molds, scaffolds, planks, and plant necessary to carry out his contract.

All the work is to be done in the best manner, according to the full meaning of the plans and specifications, and subject to the approval of the said architect.

In case any materials are not approved they shall be promptly removed from the premises.

This contractor is to be responsible for any violations of the laws or ordinances, whether State or municipal, for the constructing of buildings, and is to hold the owner harmless from any expense or claims for damage to life, limb, or property arising from any violation of such

laws, ordinances, or regulations, or caused by or in consequence of carelessness of himself or his employees.

This contractor is to examine all ceilings, partitions, and side-walls, and to notify the carpenter of any necessary work to be done to conform to these specifications.

METAL LATHING.—He is to cover with metal lathing (or wire lathing of Roebling patent, or Clinton stiffened lath, or Stanley V-ribbed lathing, or expanded metal lathing, as may be preferred) all walls, ceilings, girders, soffits, window-heads, and wherever furred off with iron or wood-furring, or wherever necessary to span other chases or iron-work, if any, and fasten in a most substantial manner.

Wherever the wire lathing is attached to wooden beams it shall be fastened thereto with iron staples driven not less than $1\frac{1}{4}$ inches into the beam.

It is best to use metal lathing on the soffits or under sides of stair cases.

WOOD LATHING.—Wherever wood lathing is specified the laths shall be the best quality of pine (spruce is cheaper, but not so good) laths, and each lath shall be securely nailed to each stud. No lathing shall be permitted to extend behind the studding from one room to another, and the lath and plaster shall extend behind all wainscoting and skirt or base-boards and all panels under windows, clear down to the floor in every case. The laths shall be well seasoned and of even thickness, sound, true, free from dead knots and bark. They shall be laid perfectly horizontal, at a distance of $\frac{3}{8}$ inch apart, and shall break joints every six courses. All laths shall be laid horizontally and none shall be laid vertically or diagonally.

Do all lathing about window-heads or elsewhere and about skylight, curbs, and stairways, finishing up the plastering in a proper and workmanlike manner.

The first coat of mortar for plastering shall be mixed with best long goat- or ox-hair. It shall be well beaten and soaked before using, in the proportion of $2\frac{1}{4}$ pounds to a bushel of mortar (where cement or patent plaster is used this specification not required), and the lime shall be slaked and mixed into the mortar with one part of lime to three parts of clean, grit, bank sand for two weeks before applying under shelter, but no plaster shall be made or stacked in cellar.*

* The mixing or stacking of wet plaster or mortar in the cellar of a building is liable to seriously injure the floor-beams and the flooring of the first floor, and should not be allowed under any circumstances.

CORNICES, CENTERS, ETC.—Molded cornices, centers, etc., as per details and designs selected.

NOTE.—It is quite customary nowadays to omit cornices in rooms, and center-pieces; they add to the expense without materially improving appearances.

PLASTERING.—(NOTE.—About three casks of lime, three single horse-loads of sand, and two bushels of good hair, with two thousand laths, are needed for a square of one hundred yards of three-coat plastering. With these quantities in mind an estimate can be made of cost.) The ceilings in cellar and all walls not furred to be plastered two coats; ceilings, partitions of all rooms, closets, light-shafts, furred walls, and stairways and soffits throughout, from cellar to superstructure, to be plastered with three coats, the last or white coat to be troweled smooth and true. (If patent plaster is to be used it should be so specified at this point.) If patent plaster is used, it should be mixed according to directions on barrel-heads; the first coat to be properly applied with sufficient force to secure good clinches, and the white coat troweled and brushed to a smooth hard finish.

(Plastering should be and is usually applied in three coats. The first is called the "scratch" coat, which forms the clinch in the lathing; the second is called the "brown" coat; and the third or last is called the "hard" or "white" or "skin" coat. Where the plastering is on brick or stone walls, the scratch coat is usually omitted.)

Run a Keene's cement wainscot in all bath-rooms.*

Do all repairing and patching after carpenters, plumbers, electric-light men, marble-masons, mantel-setters, tilers, and other workmen, and leave all places sound, clean, and perfect at the completion of the building.

The cellar side-walls are to be lime-washed—two good coats.

BACK-PLASTERING.—This contractor is to back-lath and -plaster between the exterior studs on all stories from sill to plate (carpenter to do the furring). (See page 94.) This to be one heavy coat, lathing to be as usual for King's cement, adamant, or similar plaster.

NOTE.—If it is desired to back-plaster in the attic and below the rafters it should be here specified. It will be a good and inexpensive feature of a summer or winter home.

* The owner may prefer, on account of expense, to have a wooden wainscot of yellow pine shellacked, or he may prefer, regardless of expense, to have a marble wainscot.

The fire-stop or brick nogging between inner plastering and outer sheathing, at each story, to be finished before back-plastering.

CONCRETE CELLAR FLOOR.—This contractor is to level off cellar bottom, thoroughly settle and put down 3 inches of good concrete, the concrete to be made of one part good domestic cement (brand selected by architect), one part clean, sharp grit sand, and five parts clean, coarse gravel, or clean broken stone, not larger than will pass in every direction through a 2-inch ring, thoroughly washed; all to be by measure thoroughly mixed dry and water added afterward. The finish coat to be 1 inch thick in addition to the above, and to be of equal parts of good Portland cement and clean, sharp grit sand, all worked up flush and true and protected until hard. The surface of the floor shall incline toward the drain for carrying off any water.

Clean-mortar off all floors and windows, and remove all rubbish from premises.

SUPERINTENDENCE.—This contractor is to give his work his personal superintendence, and is to keep a competent foreman constantly on the premises, and he is not to sublet the whole or any part of his work without the consent in writing of the owner.

HEATING SPECIFICATIONS

SPECIFICATIONS FOR HEATING, for a dwelling to be erected for JOHN DOE, Esq., located at —.

HOT-AIR FURNACE.—This contractor is to furnish and set in the cellar of the house of John Doe one No. — (specify make preferred) gas-tight, self-clearing, portable furnace, having fire-pot 54 inches in diameter, heavy castings, fitted with all modern improvements, and warranted to have a heating capacity sufficient to maintain a temperature in all rooms and halls having registers of 70 degrees in zero weather; furnished with galvanized-iron casings, lined with corrugated iron, to prevent the heating of the cellar, and to be connected with the smoke-flue in the chimney with the best heavy galvanized-iron pipe, fitted with patent damper to regulate draft. He is further to furnish all tin cellar heating-pipes of best (one cross) tin, and connect with the wall-pipes of the house, and to furnish all registers required (fourteen in number), best standard make (specify make preferred), of color and finish as may be desired, and where they come in the floor or in contact

with woodwork to fit same with slate or marble borders, all to have register-boxes and casings.

All hot-air pipes shall be provided with a damper or valve at the furnace and shall be of the sizes specified. The principal register shall be fastened open so that it cannot be closed. The heating-pipes throughout the house to the various registers are to be constructed of the best (one cross) tin, and wherever they pass between floors or other hollow partitions are to be made double, with an air-space of $\frac{1}{2}$ inch between the inner and outer pipe. The wood studs nearest the pipe shall be lined with bright tin with air-space. The lathing from stud to stud on both sides between which the pipes pass is to be of metal, and no hot-air pipe shall be nearer than 3 inches to any wooden studs; and this contractor shall notify the carpenter as to studs between which hot-air pipes are to pass, to secure requisite separation. This contractor is to furnish said metal lathing and attach the same; and any hot-air pipe entering a wooden partition or passing between a wooden floor and the ceiling below within 10 feet of the furnace shall be made double, and shall be wrapped with $\frac{1}{2}$ -inch asbestos board to a point 15 feet distant from such furnace.

An admirable protection is to fill the space with mortar mixed with equal quantity of plaster of Paris—i.e., highly gaged mortar.

The furnace is to be set in a first-class and satisfactory manner ready for lighting the fire. It is to be set in the middle of the cellar as nearly as may be.

This contractor is also to furnish a cold-air box of 24 B B gage, galvanized iron of the best workmanship, double-seamed and well braced, fitted with regulating damper so secured that the cold air cannot be cut off by negligence or otherwise, the outer opening to be protected with wire netting; and the inlet for cold air shall be so arranged as to supply an adequate amount of air to the hot-air chamber of the furnace, and shall be at the top of the furnace between the cover of the hot-air chamber and the cover of the furnace, in order to prevent the overheating of the furnace cover near the ceiling or woodwork.

The registers are to be set as follows:

First floor: one in dining-room, one in hall, one in parlor, one in library, one in butler's pantry. The registers in the parlor, library, and hall are to be 12"×15".

Second-floor: one in each of the four bedrooms, one in each of the two bath-rooms, and one in the southern hall.

Third floor: one in the hall, one in the servants' bath-room.

This contractor is also to furnish a metal shield of galvanized iron 1 inch larger in diameter than the top of the furnace, and suspend the same from the ceiling above the furnace so as to leave an air-space between the shield and the ceiling.

PLUMBING SPECIFICATIONS

PLUMBING SPECIFICATIONS for dwelling to be erected for JOHN DOE, Esq., in accordance with plans and specifications prepared by JOHN SMITH, architect, and attached hereto.

NOTE.—If the contract with the plumber is a separate one, then the general provisions applicable on page 107 as to masons should be included.

All pipes and other material to be of the best quality, and the workmanship to be first class.

The plumber will have no work outside of the house, except to furnish and lay the main drain-pipe to cesspool or sewer. This is to be of well-burnt, salt-glazed vitrified pipe, 4 inches in diameter, laid as nearly as possible in straight lines, necessary curves to be of large radius, and joints to be made with best Portland cement.

The main soil-pipe of the house is to be 4-inch cast-iron,* 13 pounds to the foot, connecting with the outside drain; to be thoroughly coated inside and outside with asphaltum before putting up. All joints are to be calked with oakum and melted lead; and it is to be secured in the strongest manner with stays and iron hooks. It is to be carried with Y branches for connection with various air-traps straight through and 2 feet above the roof, protected at the top with ventilating-hood and wire netting, and, where it passes through the roof, with a flange or flashing of 16-ounce tinned copper, 18 inches square, properly soldered so as to protect the roof. (The vent at roof must not be less than 4 inches in diameter.)

All service pipes are to be put on 1-inch plank strips. These to be furnished by carpenter, who is to do all cutting.

All the piping is to be arranged in plain sight, so as to be accessible for examination, and shall be carried from story to story in wooden ducts, to be made by carpenter, the cover secured with brass screws.

* Wherever wrought-iron pipes are run under ground they should be galvanized.

TANK.—This is best made of iron, but if of wood to be made by carpenter; this contractor in such case to line the tank with 16-ounce tinned copper, properly soldered, and 3-inch copper overflow through roof to nearest conductor is to be provided. There shall also be an emptying-pipe at the bottom of tank.

The tank is to hold 500 gallons net capacity, measurements to be taken between the overflow and the top of the distributing supply-pipe for the house.

FASTENINGS.—All lead pipes are to be secured with hard-metal tacks and screws; hooks must not be used. All connections between iron and lead pipes through brass ferrules soldered to the lead pipes; calking with oakum run with molten lead. All joints in lead pipes are to be wiped joints. No cup joints allowed.

Hot- and cold-water pipes shall be kept $\frac{1}{2}$ inch apart throughout the building.

All iron pipes to be secured in the strongest manner with iron hooks and stays.

SUPPLY-PIPE.—Run $1\frac{1}{2}$ -inch A A lead pipe from tank to bath-rooms and other connections, leaving out branches for separate work as follows, viz.: (name supplies you want). There must be shut-off cocks in cellar for each bath-room, and for draining all the piping of the house. All pipes to be so inclined as to drain the entire system.

(It is important to have the main supply-pipe of sufficient capacity to supply faucets when two or more are running at the same time in different parts of the house, as is often the case.)

WATER-CLOSETS.—Use embossed pedestal closets, manufactured by the — Co., with nickle-plated flush. This contractor is to set them properly, and connect with soil-pipes with 8-pound lead bends with brass floor-plate. Cisterns to be supplied with $\frac{5}{8}$ -inch A A lead pipe.

Cisterns to be of paneled oak (or other preferred wood), and the seats of closets to correspond with cisterns.

TEST.—The contractor, before plastering is finished, is to plug up all openings in pipes and fill them with water, leaving them full for twenty-four hours, so that owner may see that all are tight.

PEPPERMINT TEST.—If it is desired to apply the important test of peppermint, the specifications should read as follows:

When the pipes and traps are ready, the traps are to be filled with water, all air-pipes and other outlets are to be closed, and the con-

tractor is to pour six ounces of oil of peppermint into the top of the main soil-pipe on the roof, and follow it with three gallons of hot water, immediately closing the top of soil-pipe. If any odor of peppermint is perceptible in any part of the house, the plumber is, at his own expense, to search for and find the defects and repair them. After repairing, the test is to be repeated until everything is perfect. This test is to be made in the presence of architect and owner or some person designated by owner. The peppermint-oil is not to be carried through the house unsealed.

RANGE.—The plumber is to make connections for range between same and water-back with 1-inch finished brass pipe and fittings, setting it in place; the mason to do the brickwork.

BOILER.—The plumber is to furnish a 63-gallon galvanized-iron boiler, dome head, set on galvanized stand.

NOTE.—It is true economy to have a good-sized boiler, especially if there is more than one bath-room.

(If copper boiler preferred, here specify.)

It is to be set in the proper manner by contractor and supplied with $\frac{3}{4}$ -inch A A lead pipe; furnish $\frac{3}{4}$ -inch sediment-cock and $\frac{3}{4}$ -inch A A lead pipe connected with nearest waste so as to empty boiler for cleaning. Place $\frac{3}{4}$ -inch stop-cock on supply-pipe, and run a $\frac{3}{4}$ -inch A A lead expansion relief-pipe from top of boiler to top of tank.

Run a $\frac{3}{4}$ -inch A A lead relief-pipe to hot-water pipe at highest point, and connect below boiler, inside sediment-pipe and sediment-cock, for the purpose of securing circulation of hot water rising from head of boiler.

There shall be no depression in any of the pipes.

KITCHEN SINK.—This to be of galvanized iron, 18"×36".

NOTE.—If enameled iron preferred, here specify.

Supply through $\frac{5}{8}$ -inch A A lead pipe and 2-inch lead waste and DuBois trap.

Supply with hot and cold water through $\frac{3}{4}$ -inch flange and thimble bibbs of finished brass, one bibb to have screw for filling.

Furnish back and air chamber, and support with brackets.

BUTLER'S SINK.—This to be of 16-ounce tinned copper, 16"×24", with Italian marble, 1 $\frac{1}{2}$ -inch drip and back, as per plan.

Supply $\frac{5}{8}$ -inch A A lead pipe for hot and cold water. Furnish upright nickel-plated pantry cocks, together with nickel-plated chain, stay, and plug. Lead waste-pipe 2 inches, and 2-inch DuBois trap.

WASH-TUBS.—Furnish three Yorkshire, brown-glazed wash-tubs or trays in laundry, supplied with hot and cold water through $\frac{5}{8}$ -inch A A lead pipe, with $\frac{5}{8}$ -inch bibbs or faucets, $1\frac{1}{2}$ -inch brass plug and chain, 2-inch waste, with 2-inch (specify kind desired) traps to all sinks, connecting with main soil line through 2-inch cast-iron pipes. Trays to be supported with galvanized-iron standards.

Wooden tops to wash-tubs are liable to become water-soaked and to have a disagreeable odor, which may be avoided by having roll-top tubs.

WASH-BASINS.—These to be oval, 14"×17", marble Wedgwood ware, set in counter-sunk blue-veined marble slab, with marble back, 12 inches high, and overflow. Furnish $\frac{1}{2}$ -inch silver-plated basin-cocks, —'s patent, side lever, and nickel-plated plug, chain, and stay. (If it is desired to do away with chain and plug on account of cleanliness, the "standing waste with concealed overflow" may be specified.) Hot and cold-water pipes to be $\frac{5}{8}$ -inch A A lead, with $1\frac{1}{2}$ -inch waste and $1\frac{1}{2}$ -inch Sanitas traps, all safely and properly connected with soil-pipes. Slabs to be supported with nickel-plated brass brackets.

SLOP-SINKS, shown on plan, to be of enameled iron, placed where shown. (If galvanized preferred for cheapness, here state.) Hot and cold water supplied through $\frac{1}{2}$ -inch brass bibbs, with 2-inch D lead waste and 2-inch DuBois traps.

BATH-TUBS.—These to be five feet long, except the third-floor tub, which is to be 4 feet 6 inches; best quality of enameled iron, manufactured by the — Manufacturing Co., of —. Hot and cold water to be supplied through $\frac{5}{8}$ -inch strong lead pipe, nickel-plated brass bibbs, No. 4 $\frac{1}{2}$, and empty through 2-inch lead waste and 2-inch DuBois traps into main soil-pipe. Plugs, chains, and chain-stays, and other fixtures to be nickel-plated. Overflow connections shall branch into dips of traps.

The outside of bath-tubs shall have two coats of best enamel paint, with gold band. This work by painter.

VENTILATION.*—Back air-pipes. Furnish lines of 2-inch lead pipe or 2-inch iron pipe from crowns of each trap, and continue to points 2 feet above waste connections, where connect with main soil line by branches. Ventilate with —'s anti-siphon vent for distances exceeding 4 feet; vents to be located near fixtures and connect with crown of trap of $1\frac{1}{2}$ -inch pipe.

* See a very instructive treatise, "Plumbing Simplified," by Wm. Paul Gerard, C. E.

EXPOSED PLUMBING.—All plumbing pipes, including traps, to be exposed, and to be neatly silvered at completion.

TRAPS.—The wastes of all lines to be trapped with separate Sanitas or DuBois traps. Access to traps shall be had through pockets made in floor, and plumber is to see that carpenter under his contract does this work properly.

FLASHING.—All pipes passing through roof shall be flashed with 16-ounce tinned copper, 18 inches square (or 4-pound lead, if cheaper desired), so secured that no leak shall occur.

BIBBS.—Connect all bibbs properly; also all cocks for wastes and shut-off.

CHAINS for all fixtures to be No. 2 nickel-plated.

JOINTS.—All soldered joints are to be wiped joints.

WEIGHTS OF LEAD PIPES.—All lead pipes used shall weigh per lineal foot:

SUPPLY-PIPE*		WASTE- AND VENT-PIPE	
$\frac{1}{2}$ inch,	2 lbs.	1 inch,	2 lbs.
$\frac{3}{8}$ "	2 $\frac{1}{2}$ "	1 $\frac{1}{2}$ "	2 $\frac{1}{2}$ "
$\frac{1}{2}$ "	3 $\frac{1}{2}$ "	1 $\frac{3}{4}$ "	3 $\frac{1}{2}$ "
1 "	4 $\frac{1}{2}$ "	2 "	4 $\frac{1}{2}$ "

NOTE.—If it is desired to have brass hot-water pipes, specifications should so state. They are better than lead, but cost more.

GAS-FITTING SPECIFICATIONS

The house to be piped for gas in the best and most thorough manner, and in accordance with municipal regulations, if any there be, or with the regulations of the gas company, and in accordance with the following specifications.

OUTLETS shall be as indicated on plans, all piping to be of best wrought-iron, and all fittings malleable galvanized iron.

If the lighting is to be by gas-machine, the piping shall be in accordance with the rules of said gas-machine company.

All pipes are to be connected with red lead, capped, tested and proved perfectly tight before plastering is finished, in the following manner:

Caps shall be put on and the whole system made air-tight. Air shall

* Do not economize in the strength and weight of supply-pipe; one leak will cost more than the extra lead.

then be forced into the pipes at a pressure which will raise a column of mercury at least 6 inches high in a glass tube. This height shall be maintained for at least thirty minutes.

Pipes shall be of the following sizes:

GREATEST NUMBER OF FEET TO BE RUN	SIZE OF PIPE	GREATEST NUMBER OF BURNERS TO BE SUPPLIED
20 feet	$\frac{3}{8}$ inch	2
30 "	$\frac{1}{2}$ "	4
50 "	$\frac{3}{4}$ "	15
70 "	1 "	25
100 "	$1\frac{1}{2}$ "	40

Piping shall be substantially secured in place with iron holdfasts. All center pipes shall rest on solid supports secured to timbers near their tops. Side wall-brackets shall be from the floor to outlet, and in no case shall descend from overhead pipes.

NOTE.—This is necessary to secure return of condensed material, gasoline, etc., to meter or gasoline tank.

All branch outlet pipes shall be taken from the sides or tops of running lines, never from the bottom. Bracket pipes shall be 5 feet 6 inches from floor, except in halls and bath-rooms, where 6 feet. Nipples shall not project more than $\frac{1}{2}$ inch from face of plastering. (As lath and plaster are about $\frac{3}{4}$ inch thick, this would mean $1\frac{1}{2}$ inches from face of studding.)

No floor timbers shall be cut, except where necessary, and then by carpenter only; and no timber shall be cut at a greater distance from bearing than 2 feet, nor shall the timber be notched for a greater depth than $1\frac{1}{2}$ inches.

No gas-fitters' cement shall be used under any circumstances.

Gas-pipes must not be placed at bottoms of floor-joists, where they cannot be examined. Pipes shall be run for gas logs where marked.

This contractor is to see that the whole system of piping shall be so arranged as to drain perfectly to the meter or gasoline tank, leaving no obstruction in pipes by shoulders, depressions, or otherwise to prevent perfect drainage of the system.

SPECIFICATIONS FOR ELECTRIC-LIGHT INSTALLATION

This contractor is to properly wire the building throughout for electric lighting, with outlets as shown on plans, materials to be of the

best quality and workmanship, furnishing all wires, conduits, switches, cut-outs, etc., so that the installation will comply in all respects with the requirements of the National Board of Fire Underwriters; and until this contractor furnishes a certificate from the local board of underwriters having jurisdiction of the territory in which the building is located, that said installation is in accordance with the rules, no amount shall be payable under this contract.

NOTE.—If it is desired to install conductors or wires in raceways or conduits so that they can be removed or replaced from time to time, if necessary (the best method of installation), it should be here stipulated, and the particular raceway or conduit to be used must be mentioned. It is best to require that all installations shall be in accordance with the rules of the underwriters, as new precautions for safety are discovered from time to time, and the underwriters keep abreast of such improvements, and their rules are always up to date.

TINNING AND COPPERSMITH SPECIFICATIONS

These, if it is intended to have a separate contractor, should specify the material to be used for angles, valleys, ridges, ridge-rolls, decks, finials, etc.,—whether tin, zinc, lead, galvanized iron, or copper. They should provide that all places which require flashing shall be flashed, whether specified or not, and should provide that all leaks shall be stopped after other workmen, and everything left water-tight at completion of the building.

PAINTER'S SPECIFICATIONS

All of the paint, oil, turpentine, and other materials to be of the best quality. It is best to specify the name and grade of each article for the purpose to be used.

All hard-wood floors and borders are to have one light coat of linseed-oil, and to be finished with hard wax, applied in the best manner, thoroughly rubbed in. All other woodwork to be finished with an oil filler, rubbed down with OO sandpaper, with two coats of (specify make desired) wood-finish varnish, neatly rubbed with pumice-stone and water to a smooth dead finish. All hard wood to be given the same treatment, except that it is to have a coat of filler and an extra coat of varnish. (If any particular make is preferred, it should be stated.)

Owner to select color of paint for inside and outside work. (This is

ELECTRIC BELLS AND SPEAKING-TRUMPETS 129

a matter as to which tastes vary, and the owner, with his architect, will have to draw the specifications in each instance.)

GLAZING.—This is usually a part of the carpenter's work, but if to be done by the painter, the quality of glass and sizes of lights should be specified. For ordinary cheap dwellings "stock" sash are the least expensive; that is, the sizes kept in general stocks.

The specifications should require that all glass "shall be well bedded, tacked, puttied, and back-puttied."

SPECIFICATIONS FOR ELECTRIC-BELL AND SPEAKING-TRUMPET WORK

This is generally included in the carpenter's specifications, and should require that electric bells shall be placed, with push-buttons, in the various rooms desired, with an annunciator in the kitchen, the push-buttons to be of pearl, nickel-plate, or plain metal, as desired.

It is well, in addition to the bell from the front door to the kitchen, connecting also with the servants' rooms, to have a bell from the owner's bedroom, near the head of the bed, to the kitchen and to the servants' rooms; one from the dining-room, with a push-button attached to the chair; one from the lounge in the library or sitting-room to the kitchen (when the mistress of the house is indisposed this will be found convenient, and possibly save her an uncomfortable walk across the room to touch the button to summon a servant); and one from both the library and the owner's bedroom to the stable.

A speaking-trumpet to the stable, and also to the cellar near the furnace, will be found convenient.

It is also well to have a bell from the spare or guest's room to the kitchen.

Where the house is not conveniently near to a mechanic understanding electric wiring, the specifications should require that wires for pull-bells shall run through small lead conduits in the plastering.

SOME GENERAL FORMS OF CONTRACT FOR THE ENTIRE WORK

THE following contract has been carefully prepared, with the best legal advice. It will suit any form of construction, even that of an elaborate fire-proof building, no matter what its purpose or occupancy, while most of the requirements are applicable to the cheapest construction. It leaves nothing to memory or verbal understandings, which are always dangerous; and while it may be regarded as longer than necessary, there is not a paragraph in it which has not been carefully considered in the light of experience and which is not intended to prevent misunderstandings, disputes, and litigation.

EQUITABLE CONTRACT

It ought not to be necessary to suggest that an owner who expects fair dealing at the hands of his contractor should be perfectly fair with him, and that he should avoid all tricky clauses in his contract. Such clauses are sometimes inserted with "drag-net" intention to cover any possible laches or neglect on the part of the architect and the owner. The following clause, for example, ought not to be inserted:

"The contractor will also do any and all patching where the work is damaged by other mechanics and for ANY CHANGE THAT MAY BE MADE BY THE OWNER OR ARCHITECT, no matter how much is done, make all work good, without any extra cost to the owner whatsoever."

An honest owner would not put such a clause in his contract, and an intelligent contractor would not consent to it, unless he is as dishonest in his intentions as he is shrewd in his interpretation.

Another objectionable clause is the following:

"Any work shown on the drawings and not mentioned in the specifications, or vice versa, must be done by the contractor without any extra cost to the owner, and (here comes the objectionable part), ANYTHING NECESSARY TO COMPLETE THE JOB, WHETHER HEREIN STATED OR NOT, SHALL BE DONE WITHOUT EXTRA CHARGE."

It was good advice given by an honest man to his son on starting out in life: "Never be half as sharp as you know how to be." The man who digs a pit for his neighbor deserves to fall into it himself. Endeavor to draw the contract so that it will be just to both parties and thoroughly plain in its terms and meaning. It is an old rule of law that if any one should suffer for want of a clear and unmistakable contract, it should be he who has the drafting of it. It is a fundamental law of contracts, as old as the writing of Vattel in his "Law of Nations," that "if he who could and ought to have explained himself clearly and plainly has not done it, it is worse for him; he cannot be allowed to introduce subsequent restrictions which he has not expressed."

It is therefore in the interest of all that the contract and the specifications should be explicit, and omit nothing which would define the duty of the owner, on the one

hand, or insure honest work and good construction by the contractor, on the other. There are some builders who cannot be relied upon to call the owner's attention to oversights or mistakes in architect's specifications; they prefer rather to take advantage of the loopholes which they perceive for cheating. For this reason defective, indefinite, and carelessly worded specifications generally result in securing a tricky and dishonest contractor, who becomes the successful bidder. A conscientious bidder who knows how, and intends to do, good work, bases his estimate on his intention and makes his figures accordingly, while the sharper, seeing opportunities for cheating, underbids honest competitors, secures the job, and a poor building is inevitably the result. Do not fail, therefore, to specify fully all work required and the manner in which it is to be done, leaving nothing whatever to verbal understandings.

GENERAL FORM FOR CONTRACT WITH BUILDER

AGREEMENT made this fifth day of November, 1896, between JOHN DOE (hereinafter called the owner), party of the first part, and RICHARD ROE, of the city of New York (hereinafter called the contractor), party of the second part, WITNESSETH:

That the owner and contractor, for and in consideration of the sum of one dollar each to the other in hand paid, and other valuable considerations, the receipt whereof is hereby acknowledged, have agreed as follows:

FIRST: The contractor agrees to do and perform all the work and furnish and supply all the materials required to finish and complete the mason-work, carpenter-work, iron-work, exterior marble, interior granite, elevators, interior marble, steam (if any), heating, and ventilating apparatus, marble and tiling work, plumbing and gas-fitting, terra-cotta and plastering, painting, speaking-tube and bell work and hard-wood finish, mentioned and referred to in and called for by the drawings and specifications made by JOHN SMITH, architect, and signed by the owner and contractor, relating to the building to be constructed and erected on lots belonging to said owner, and known as in the city of New York, which drawings and specifications are hereto annexed and made a part of this contract, in consideration of the payment to the said contractor by the said owner of the sum of dollars, at the dates and in the manner hereinafter provided. And the contractor further agrees to perform the work aforesaid in a good and workman-like and substantial manner, under the direction and to the satisfaction and approval of the said JOHN SMITH, architect, his successor or successors.

SECOND: The contractor further agrees that all materials furnished and provided by him shall be of the kind and quality described in said

specifications, and further agrees that all materials required to be furnished and supplied which are not described in said specifications shall be of the best quality and shall be approved by said JOHN SMITH, architect, his successor or successors.

And the contractor further agrees to furnish whatever temporary heat may be necessary to keep the inclosed parts of the building above the freezing-point during the performance of this contract, at his own expense and without extra charge; and further agrees to furnish all elevators and hoisting apparatus that may be necessary or required for the due performance of the work called for by this contract, and run and operate the same at his own expense and without extra charge.

THIRD: The contractor agrees to begin work under this contract on the first day of January, 1897, and to fully perform, complete, and finish all work, and furnish and supply all materials embraced in this contract and said drawings and specifications, in strict accordance with the terms and requirements of this contract and said drawings and specifications, by the first day of June, 1897, and that in the event of his failure so to do, he will pay to the party of the first part, as liquidated and stipulated damages, and not by way of penalty, the sum of fifty dollars (\$50) for every day that the work called for by this contract shall remain uncompleted and unfinished subsequent to June 1, 1897, up to and including the fifteenth day of July, 1897, and will pay to the owner the sum of seventy-five dollars (\$75) a day as liquidated and stipulated damages, and not by way of penalty, for every day that the work called for by this contract shall remain uncompleted and unfinished, subsequent to said fifteenth day of July, 1897; and the said contractor further agrees that the said owner may deduct and retain said liquidated and stipulated damages out of any moneys due him under the terms of this contract at the date said damages, or any part thereof, shall accrue, or out of any moneys that may thereafter become due to said contractor under the terms of this contract.

As already stated, penalties are difficult to collect. If the plan suggested of stipulating for a bonus (see page 68) is decided upon, the following should be the wording:

"The contractor agrees to begin work, under this contract, on the first day of January, 1897, and to fully perform, complete, and finish all work and furnish and supply all materials embraced in this contract and said drawings and specifications, in strict accordance with the terms and requirements of this contract and said drawings and speci-

fications, by the first day of July, 1897; but it is further understood and agreed that, in the event that he shall complete the building and comply with all of the terms and requirements of this contract as above specified by the first day of June, 1897, he shall receive a bonus of \$1500, or at the rate of \$50 per day for every day of earlier completion than the first day of July above specified, not exceeding in all the sum of \$1500, if completed by the first day of June as aforesaid."*

It is further understood that in the event of his failure to fully perform, complete, and finish the work embraced in this contract by the first day of July, he will pay to the party of the first part, as liquidated and stipulated damages, and not by way of penalty, the sum of fifty dollars (\$50) for every day that the work called for by this contract shall remain incomplete and unfinished subsequent to July 1, 1897.

FOURTH: The contractor agrees that he will, at his own expense, provide and furnish any and all materials (including water), labor, scaffolding, tools, implements, molds, models, and cartage, of every description, necessary to the due performance of said work and the full and complete performance of this contract.

FIFTH: The contractor further agrees that he will proceed with the said work, and every part and detail thereof, in a prompt and diligent manner, and at such reasonable times as may be necessary and proper in order to complete and finish the same, and every part and appurtenance thereof, in a durable and substantial manner, on the said first day of June, 1897 (if bonus form above, should be July 1st), and without the performance of any part of the said work in unsuitable weather.

SIXTH: The contractor further agrees that he will not at any time suffer or permit any lien, attachment, or other incumbrance, under any law of this State or otherwise, to be put or remain on the building or premises upon which the aforesaid work is to be done and for which the aforesaid materials are to be furnished under this contract for such work or materials, or by reason of any claim or demand against him, the said contractor; and that should any such lien, attachment, or incumbrance be placed or filed upon said building or materials, the said contractor shall not, until such lien, attachment, or other incumbrance shall be removed, satisfied, and discharged, be entitled to claim, demand, or receive any payment whatever under or by virtue of this contract.

* If the contractor declines to agree to this, it may safely be assumed that he sees the loopholes in the usual penalty clause and expects to escape through them.

SEVENTH: The contractor further agrees that the plans, drawings, and specifications hereinbefore mentioned are intended to coöperate so that any matter or thing contained or shown by one and not by the other shall be of the same force and effect as if contained in and shown by both; and that he will perform any work, and furnish all materials shown by either without any extra charge, claim, or demand whatsoever.

EIGHTH: The contractor further agrees that the owner may at any time during the progress of the work alter, change, deviate from, and add to said drawings and specifications, and that any such alteration, change, deviation, or addition shall in no way affect the validity of this contract. Provided that if such alterations, changes, or deviations, or additions shall decrease the aggregate cost of said work and materials, then the amount of such decrease in cost shall be deducted from the said sum of \$ and the said owner shall only be liable to pay to the contractor the balance remaining after making said deductions as aforesaid, and provided further that if such alterations, changes, deviations, or additions shall increase the aggregate cost of said work and materials beyond said balance remaining after making the deductions aforesaid, then the said owner shall pay to the said contractor the amount of such excess in cost, with ten per cent. on said excess, in addition to said balance.

NINTH: And the contractor further agrees that he shall not be entitled to claim, demand, or receive any pay for extra work, unless the necessity for such extra work shall be certified to by the said JOHN SMITH, or his successor or successors, in writing; and the price to be paid for such extra work shall have been fixed and determined, before the same shall have been performed, by a written memorandum, ordering the extra work to be done and stating the price to be paid therefor, signed by the owner.

TENTH: The contractor further agrees that if he shall at any time neglect or refuse to supply a sufficient number of workmen of requisite skill, or to furnish materials of the kind and quality called for by this contract and said specifications, or shall fail in any respect to prosecute the said work with promptness and diligence, or shall be in default in the performance of any covenant in this contract contained on his part to be kept and performed for the period of three days after notice in writing, signed by the owner, of such default shall have been served upon him, either personally or by leaving the same at his residence or place of business, then, and in such event, the said owner shall

have the right and power to employ other persons to perform the work and furnish the materials required by this contract, and to complete the same in every respect, and the cost and expense thereof at the reasonable market rates in excess of the unpaid balance of the contract price shall be a charge against him, the said contractor, and he will pay the same to the said owner; and he, the said contractor, shall have no claim or demand against the owner for said unpaid balance or by reason of the non-payment thereof; and the said owner, and all persons employed by him to complete the said contract, shall have the use of all scaffolding and fixed tackle of any kind belonging to, or used by, the said contractor prior to said default on his part, free of charge, and until the said contract shall have been fully performed and completed.

ELEVENTH: The contractor further agrees that the said JOHN SMITH, or his successor or successors, may condemn any materials furnished and reject any work performed under this contract, and require the same to be taken down and removed from the premises by and at the expense of the said contractor; and that said JOHN SMITH, and his successor and successors, may also direct the time of doing the several portions of work called for by this contract.

TWELFTH: The contractor further agrees that no certificate given or payment made under this contract shall operate as, or be held to be, an admission on the part of the owner that this contract, or any part thereof, has been complied with, or that any detail of the work has been properly performed, or that the materials furnished are of the quality called for by the specifications, in case the fact shall be otherwise; nor shall any such certificate or payment stop or preclude the said owner from claiming damages against the said contractor, should the work and materials hereby required not be performed and furnished in every particular in a substantial and workmanlike manner, and in strict fulfillment and compliance with the requirements of this contract and said drawings and specifications.

THIRTEENTH: The Contractor further agrees that he will bear and be liable for all loss or damage that may happen to the said materials by fire, storms, or otherwise, prior to the time they have been actually used and entered into the construction of said building, and that he will repair all damage and injury to said work and materials occasioned other than by fire, storms, or otherwise, during the performance of this contract and prior to the completion and acceptance of the same, and without extra charge.

FOURTEENTH: The contractor further agrees to indemnify and save harmless the said owner from all and every claim of damage or injury to person or property occasioned by his negligence, carelessness, or want of skill, or that of his servants or employees, or that of his sub-contractors or their employees, while engaged in the performance of the said work, or otherwise; and further agrees to indemnify and save harmless the said owner from every claim and demand for the violation by him, his servants, or sub-contractors and their servants, of any statute or municipal ordinance regulating or relating to the work called for by this contract; and further to indemnify and save harmless the owner from all damage or injury occasioned by his negligence, carelessness, or unskillfulness, or that of his sub-contractors, or his or their servants or employees, in supporting, protecting, or shoring up of the adjoining walls or buildings.

FIFTEENTH: The contractor further agrees that in case the said JOHN SMITH shall die, resign, be removed, or refuse to act, then the said owner may appoint a successor or successors, and such successor and successors shall have like power and perform like duties as are conferred and imposed upon the said JOHN SMITH by this contract.

SIXTEENTH: The owner agrees to pay to the contractor for performing said work and furnishing and supplying said materials as aforesaid the sum of dollars in instalments, as the performance of this contract progresses, and as follows: On the twenty-fifth day of each and every month the contractor shall furnish to the architect or his successor or successors a statement of the work done and the materials furnished during the thirty days next preceding, and thereupon the architect or his successor or successors shall verify said statement and furnish to the contractor a certificate in writing, signed by him, of the value of the work done and materials furnished and supplied and actually used and applied in the construction of said building during said preceding thirty days; and upon the presentation of the said architect's certificate the said owner will pay to the contractor 85 per cent. of the amount so certified by the architect, and will make such payment within ten days after the presentation of such certificate as aforesaid. When the last instalment shall be certified to by the architect, there shall be added to the amount so certified the aggregate of the 15 per cent. deducted from the prior instalments, and the amount of the said instalment, with such additions, shall be paid to the said contractor by the said owner when, and not before, the said contractor

has complied with the conditions mentioned in the next succeeding paragraph of this contract.

SEVENTEENTH: The contractor agrees that he shall not be entitled to demand, receive, sue for, or collect the amount of said last instalment, or any part thereof, until he has presented to the said owner the certificate in writing, signed by the said JOHN SMITH, his successor or successors, to the effect that this contract has been fully completed and performed, and also the certificate of the county clerk of the county of —, that no mechanics or other liens are of record upon said building, for work done or materials furnished by any person or persons for, or on behalf of, said contractor or any sub-contractor, or his or their employees, and also only upon evidence being furnished by the contractor satisfactory to the owner, that no claim or demand exists in favor of any person or persons for work done or materials furnished or supplied in the performance of this contract.

EIGHTEENTH: It is further mutually agreed between the contractor and owner that, should any dispute or question arise respecting the true construction or meaning of the drawings or specifications, the same shall be decided by JOHN SMITH, his successor or successors, and his or their decision shall be binding and conclusive. But should any dispute arise respecting the cost of any change, alteration, deviation, or addition with respect to the work to be done and the materials to be furnished under this contract, the same shall be submitted to two arbitrators, one to be chosen by the contractor and the other by the owner, whose decision, if they agree, shall be final and conclusive, and who, in case they cannot agree, shall have the power to choose a third arbitrator, and the decision of the three arbitrators or a majority of them, shall be binding and conclusive upon the said owner and the said contractor.

NINETEENTH: It is further mutually agreed between the owner and contractor that the owner shall not in any manner be answerable for any loss or damage that shall or may happen to the work done or materials furnished under this contract during the performance thereof, or for any loss or damage that may at any time happen to the materials, tools, and appliances used and employed in the performance of the work called for by this contract.

TWENTIETH: It is further mutually understood and agreed between the owner and the contractor that the contractor shall have the right to make sub-contracts, but only with such person or persons, corpora-

tion or corporations, as shall have been first approved in writing, signed by the owner, and that the contractor shall not assign this contract, or any interest therein, without the consent of the owner in writing shall have been first had and obtained; it being understood and agreed that this contract is for the personal service and skill of the said contractor, and that if such contractor shall make any such assignment without such consent, then at the option of the owner this contract shall cease, determine, and be null and void.

TWENTY-FIRST: This contract shall bind and inure to the benefit of the owner, his successor or successors, and the contractor, his heirs, executors, and administrators.

FIRE-INSURANCE.—It is usual to insert in the contract a provision that the owner shall maintain fire-insurance, payable both to himself and the contractor, as interest may appear. Insurance should be taken also against tornado and lightning. If it is desired to have an insurance clause, it should read as follows:

“Insurance shall be maintained by the owner in the joint names of the owner and this contractor, loss, if any, payable as interest may appear, during the process of the work, and to 80 per cent. of the value thereof, in the following form:

“John Doe and Mary R., his wife, as owners, and Richard Roe, as contractor; loss, if any, payable as interest may appear.”

IN WITNESS WHEREOF, the contractor and owner have caused these presents to be duly executed the day and year first above written.

JOHN DOE, Owner.

RICHARD ROE, Contractor.

SCHEDULE

It is understood and agreed that, in accordance with the terms of the agreement, dated the fifth day of July, 1897, between JOHN DOE, as owner, and RICHARD ROE, as contractor, the following alterations, changes, deviations, and additions have been made to the said contract and the original drawings, plans, and specifications thereto annexed, in accordance with the terms of the contract, and that these changes have occasioned an increase or decrease in the contract price in the sum or amount stated respectively in the column below headed “Increase” or “Decrease.”

CONTRACT WITH ARCHITECT

This agreement between JOHN SMITH, architect, and JOHN DOE, owner, entered into this — day of —,

WITNESSETH, That the said JOHN SMITH is to draw plans and specifications of a dwelling to be erected for the said JOHN DOE at —. The drawings are to be complete and to include front, rear, and side elevations to scale $\frac{1}{4}$ inch to foot, details of standing trim, framing and joining plans, etc., plans of foundation and all floors, roof and attic plans, together with all other necessary and proper papers and drawings, four copies of each, before —, 189—, and before taking estimates, in order that each one estimating may know what will be required. The said plans and drawings are to be the property of the said JOHN DOE, owner.

Said architect is further to give supervision to the work throughout its progress, to visit the premises at least once every day and carefully inspect every portion of the building. He is further to furnish a superintendent who shall spend at least two hours every day at the building. He is to carefully inspect and test all material and finished work, and to protect the interests of the owner in every way.

In consideration for which service, the said JOHN DOE is to pay the said JOHN SMITH, on the completion of the drawings, plans, specifications, details of standing trim, framing plans, etc., the sum of — dollars, and the further sum of — per cent. on the money due and payable to various contractors under their contracts, said percentage to be payable at the time payments under said contracts are by their terms due and payable.

Witness our hands and seals this — day of —, in the city of —.

(Signed) JOHN DOE (L. S.).

JOHN SMITH (L. S.).

RECAPITULATION

NOTE.—The following summary of points to be observed in building a house has been prepared to enable an owner to check off his plans and specifications, to see that all of the points explained in this book have been provided for, as suggested on page 41. To enable him the better to understand the brief references here given, the page of the book where the matter is more fully explained has been inserted. In the absence of such page reference, the reader can easily find the text by the index. He will do well, however, to compare the phraseology of his specifications with that used in the book, pages 88 to 129.

GRADING.—Dig trenches 8 inches wider than walls, and prepare footing courses, pages 10, 109.

Remove and preserve top soil and loam, page 4, 109.

If house is on side-hill, build wide rather than deep, page 4.

Locate dining-room according to prevailing breeze in summer, page 4.

Provide blind drains around foundation, page 6.

Provide double system for carrying surface water—gutters and sub-soil pipes, page 5.

MASONRY.—Specify quality of bricks, page 10.

Provide for laying bricks in freezing weather dry and warm in cement mortar; in non-freezing weather wet, page 11.

- Lay foundation-walls in cement mortar, page 10.
- Plaster outside with cement and asphalt, page 10.
- Have footing courses, page 10.
- If stone walls, have both sides brought to face, especially side next earth-bank, page 111.
- Retaining-walls. Thickness should be at least one fourth height, page 12.
- Provide weepers, pages 12, 111.
- Should be battered back against bank, page 12.
- CELLAR.—Have high underpinning or areas to secure windows, giving light and ventilation, pages 9, 105.
- Should be full size of house, page 7.
- Should have ceiling 8 feet high, page 7.
- Ceiling should be plastered on wire lathing, page 7.
- Provide for two coats whitewash on side-walls.
- Concrete floor, pages 7, 115.
- Provide drain in floor before laying concrete or building wall, page 8.
- Avoid partitions in cellar or wooden pillars, page 92.
- Provide interior carrying walls rather than piers, page 92.
- Provide for coal-bins, wine-closets, cold room with wire netting, pages 8, 106.
- FRAMING.—Provide for balloon frame or braced frame, pages 13, 90, 91.
- Provide for angle-braces, page 91.
- Cross bridging between floor-joint or -beams, pages 15, 92.
- SHEATHING.—Should be tongued, grooved, and thickened, pages 15, 95.
- Nail horizontally, pages 15, 95.
- Cover with heavy building-paper nailed with tin washers, page 96.
- SIDE-WALLS.—Cover with shingles or clapboards; cedar shingles best; clapboards to be sap extra, pages 15, 95, 96.
- Use galvanized nails, page 16.
- BACK-PLASTERING.—Provide for in wooden houses, page 16.
- SHRINKAGE.—Keep equal thicknesses of timber under footing of parallel partitions, pages 14, 15, 93.
- See that partition studs do not set on floor-joists, but that they pass through and foot on partition below.
- FIRE-STOPS.—Provide in all hollow partitions spaces in side-walls, furred walls, and staircases, pages 16, 17, 18, 100, 115.
- FLOOR-JOISTS OR -BEAMS.—Should be 3"×12", page 21.

Yellow pine, spruce, or hemlock, in order named as to cost and desirability. The first tier of beams should bear on wall as well as on sill.

FLOORS.—Should be double. Lower of hemlock, $\frac{3}{4}$ " \times 6", tongued and grooved, page 21.

Under flooring should be nailed diagonally, except for parquette flooring.

Carry under floor to outer sheathing to support fire-stop, page 97.

Upper floor may be of oak, maple, comb-grain Georgia pine, North Carolina pine, white pine, or spruce, according to expense.

Specify clear lumber, time-seasoned or kiln-dried—the former best.

Provide for sorting, to put best on hall, library, parlor, and dining-room.

Sweeping-moldings, provide for, page 24, 100.

Deafening—provide for this, especially servants' floor, pages 24, 98.

Provide mitered borders for hearths, page 98.

Base-knobs and door-stops, page 99.

PIAZZA.—Have 12 feet wide if possible, and extend part way around sides, page 24.

Avoid sap lumber in flooring, pages 25, 97.

Incline floor to front $\frac{1}{4}$ inch to foot, page 97.

Putty joints between base of columns and floor, page 26.

Make tight joint at house wall.

Columns.—Specify solid natural wood or white wood, to be painted or boxed columns as desired, page 94.

Have balusters in railing large enough.

Avoid resting-places at eaves for birds' nests, etc.

Make outside steps of strips or bore with auger-holes to prevent warping, pages 24, 99.

ROOF.—Should be well braced, pages 28, 29.

Should be sheathed with 6-inch tongued and grooved hemlock.

Cover sheathing with heavy roof-paper, nailed with tin washers.

See that rafters are notched on plate.

If shingle roof, nail shingles on shingling strips, to prevent rot.

Lay shingles 5 inches to weather, page 97.

Do not lay shingles in lead paint; it rots them. If painted at all, they should be painted on top, as they are nailed, page 97.

If dipped in creosote, should be drained dry before nailing, page 15.

Nail shingles with galvanized nails, wide heads.

Slate.—If slate roof, should be laid in mortar, 7 inches to the weather, 9" × 18," square ends, page 96. Round ends cost more and do not look any better.

Avoid lodging-places for snow on roof by making "crickets," if necessary, page 29.

GUTTERS.—Should be copper, or, if wood, lined with metal, page 102.

Fasten with galvanized-iron hangers.

Furnish and insert basket-half leaf-arresters of copper wire in gutter-openings of leaders.

Should be below line of snow-fall, page 102.

LEADERS AND CONDUCTORS.—Better of copper or galvanized iron, at least 3 inches in diameter, page 103.

ATTIC.—Should be ventilated, page 27.

Paint woodwork with fire-proof paint.

FLASHING.—Use copper, zinc, lead, tin, according to expense; copper cheapest in long run, page 29, 86.

See that specifications require that flashing is carried well under shingles and slate and up sides of chimneys, pages 29, 103.

RIDGE-ROLL, FINIALS, ETC.—Should be covered with copper, page 29.

BALCONY DECKS.—Use lead or zinc instead of painted canvas or tin, page 30.

Have wooden slat floor for walking, page 30.

Should incline, to throw water from building.

CHIMNEYS.—Should be built from ground, never from floor-joint.

If corbeled out of brick walls, should be not over 8 inches from wall and by five courses of brick corbel, page 113.

Make walls of flues 8 inches thick.

Line with burnt fire-clay lining-pipe, page 33.

Be sure to have enough fireplaces, page 33.

Incline back of fireplace forward, to insure draft.

Make flues large enough—8" × 12"—for wood-fires and furnace.

Carry up flues as straight as possible, page 33.

Cope chimneys with stone, page 33.

See that openings in capstone are as large as flue-openings before hoisting to top of chimney.

Avoid overhang or enlargement of the chimney at the roof, page 33.

Use only cement mortar in brickwork of chimneys above roof (only

cement mortar will stand the weather). The joints will look better if cement is colored black.

Do not allow any parging or plastering on inside of flues, page 35.

Provide for ash-pits, they cost nothing, page 113.

FIREPLACES.—Should not be too high, page 113.

Size for cord wood, if desired, page 35.

Should be lined with fire-brick or cast-iron, page 37.

Front or arch should be supported with iron bars, page 113.

HEARTHES.—Should rest on trimmer-arches, pages 32, 113.

The header should rest in bridle-iron on the trimmer-beams, pages 32, 113.

Mitered borders should be provided around hearths, already referred to, page 98.

CHIMNEY-BREASTS.—Avoid wooden lathing and furring; only metallic lathing should be used, page 37.

MANTELS.—Should not, if of wood, project too far over fire, page 38.

CENTER STUDS.—For supporting deer-heads, heavy pictures, etc., pages 37, 93.

PLASTERING.—Metallic lathing preferable, especially for ceilings over cellar and main floor, under side of staircases, and chimney-breasts, and over furnace-pipes, page 38.

Provide for $\frac{3}{4}$ -inch grounds, page 94.

Stipulate that plaster shall not be stacked or made in cellar; it injures floor-beams, page 118.

Avoid wood ceilings and side-walls, page 40; if used, back up solid with plaster.

If wooden lathing, stipulate as per specifications, page 118.

If hair-plastering, be sure enough hair is provided—good long cattle-hair, page 118.

See that plaster is made at least two weeks before using and in manner prescribed, page 118.

Patent cement, page 38; should be applied as per directions on barrel-heads; so stipulate, page 118.

Back-plastering—already provided for.

HEIGHT OF CEILINGS.—Recommend 8 feet for cellar, 11 for first story, 10 for second, and 9 for third.

DOORS.—Front door and any door exposed to heat on one side should be veneered, page 98.

NOTE.—The front door may be a Dutch door, if preferred, i.e., divided into two parts.

Specify "stock" sizes, to save expense of unusual sizes, which have to be made to order.

Provide ground-glass transoms, 1 foot high, pages 42, 99.

Examine to see doors are of uniform heights; some, however, prefer doors to closets in rooms lower than the doors of exit. See that specifications call for double studs to all doors and windows.

See that specifications require that all doors and windows over three feet wide shall be trussed, to relieve the door of the weight above it.

Door-sills should be of hard wood, oak or maple, page 98, and the front door-sill should be rebated, to prevent snow and rain blowing in, page 98.

Cellar door, hatchway, etc.—provide as specified, page 99.

WINDOWS.—Should be "stock" sizes, except for fine views, where wider and of plate-glass, page 41.

Should be uniform heights, page 41.

If opening on piazza, may be either sliding or French windows, page 42.

Examine to see that room is left for bedsteads, bureaus, buffets, etc., page 43. Have low window-sills.

Stipulate for metal pockets and flashing, to prevent leaks, page 104. (See "Hardware.")

Provide for double studs and trussing, as already explained.

Stipulate for iron bars to cellar windows, page 105.

FLY AND MOSQUITO SCREENS, page 43.

OUTSIDE BLINDS.—Specify clear wood, primed, painted two coats, and best angle-hinges, page 105.

STORM-DOORS AND -SHUTTERS.—Should be nailed with wrought nails, clinched, page 43.

Should be marked to correspond with openings, page 43.

May have small glass lights, page 43.

Door to kitchen to have same key as inner door, page 46.

CLOSETS.—Be sure to have enough, page 43.

Ceilings should be same height as that of rooms.

Doors should not open into closets.

Specify shelves, width, and distance between; drawers; height of hooks, etc., pages 43, 100.

Ventilate with windows wherever possible, especially linen-closet, page 44.

Moth-proof closets, of cedar or camphor, page 44.

DINING-ROOM.—Should be on coolest side of house, pages 4, 44.

Should not be over or near kitchen, page 4.

Have floor of passage between dining-room and kitchen level.

Should have fly or swing door to butler's pantry, ground glass, but a narrow border of clear glass, to enable parties approaching to see each other, page 43.

Arrange for location of push-button to bell and have wire inserted before laying floor.

See that space is left for buffet, page 44.

KITCHEN.—Should be on cool side of house, page 45; well ventilated, high windows, and low door.

Should have "heat and odor-extinguisher," page 45.

Should have ventilating-flue in chimney next smoke-flue (it costs nothing), page 45.

Should have storm-door hung on hinges, with Yale lock, same key as inner door, already referred to, page 46.

Should have dresser, closet for pots and kettles, and architect should prepare details before taking estimates.

Should have small clock-shelf.

Should have wide-rubbed slate hearth to range.

Should have galvanized-iron or enameled-iron sink.

Hot-water boiler should be large—63 gallons—of copper or galvanized iron (latter good enough), page 124.

LAUNDRY.—If possible, arrange so that both kitchen and laundry help to ventilate each other, with doors opposite, page 73.

Arrange for laundry stove, and see that mason's specifications provide for thimble in flue for stovepipe.

Soiled-clothes chutes, if any, should be of metal.

BUTLER'S PANTRY.—This is convenient, even if you keep no butler.

Should have outside door, page 46, and window for ventilation and light.

Should have marble sink and galvanized-iron or enameled-iron tray. Should be large.

Should have opening for passing dishes into dining-room closet.

REFRIGERATOR.—Should be convenient to butler's pantry, dining-room, and kitchen, and therefore between the last two.

Should have drip-pipe to outside of house, not connected with sewer, page 46.

STORE-ROOM.—Should be convenient to kitchen, have an outside window, and be of good size.

Should be rat- and mouse-proof by inserting cheap galvanized-wire netting behind plaster and between floors, page 47.

BATH-ROOM.—Should have waterproof floors, with small lead-pipe drain to outside, page 47.

Should have wainscot of marble, tile, King's Windsor cement or Keene's cement, painted or hard wood or yellow pine, shellacked, etc.

Have bath-room systems over each other, to save piping.

If tiled with gold-bead ornament, do not have any gold bead near the floor, page 49.

Have 2-inch waste and trap, to prevent overflow.

Provide for supplying tub at top or bottom, page 48.

Have enameled-iron tubs, either enameled roll tops or wooden tops, page 47.

Paint outside of bath-tubs, pages 48, 125.

WATER-CLOSETS.—Have ventilating back air-pipe, and be sure to have soil-pipe to the roof not less than 4 inches in diameter, page 122.

SLOP-CLOSETS.—Should have outside window.

Should have automatic flush, enameled-iron basin, etc., page 49.

TOILET AND LAVATORY, FIRST FLOOR.—Can be arranged under main staircase, page 50.

Be sure to have outside window.

SEWING-ROOM.—Provide one, page 50.

STAIRCASES.—Front or main staircase should be quarter-sawn oak, page 99.

Should have wide treads and 6½-inch risers.

All staircases should have center carriage-timber, page 52.

The outside or unsupported stringer should be 3"×8," page 52.

Plaster under side of staircase on metallic lathing, and insert fire-stops, pages 52, 118.

Rear staircases should be extra strong, for carrying up furniture, etc., 3 feet 6 inches wide, and should have wide doors top and bottom.

Be sure to require architect to furnish detail main staircase in time to decide as to railing, balusters, and newel posts.

HEATING.—Have large furnace, page 54.

Should be in center of cellar.

Should have double pipes in walls, page 54.

Should have galvanized cold-air box, pages 55, 121.

Lathing over hot-air pipes should be metallic, pages 55, 121.

Cover pipes with asbestos board, page 54.

Have suspended shield over furnace to protect floor-beams above, page 122.

Have principal register fastened open, or without valve, page 56.

Do not have a floor register directly over the furnace, page 57.

LIGHTING.—If by gasoline gas, get specifications from the gas-machine company, page 126.

Be sure to have piping arranged to completely drain the entire system to the tank or meter, page 127.

All side-lights or bracket-lights should be supplied from below, page 127.

Plan outlets, especially for side-light brackets, with reference to bureaus, writing-desks, etc., page 57.

Have gas-pipes of proper size, page 57.

ELECTRIC LIGHTING.—Get rules of underwriters and base your specifications on these, page 128.

ELECTRIC BELLS.—Have push-buttons conveniently located as suggested, pages 59, 129.

SPEAKING-TRUMPETS to kitchen and cellar, pages 59, 129.

WATER-TANK.—Specify if of iron or wood, page 58.

Have overflow to cistern to save water, pages 58, 123.

Be sure to have drain-pipe at bottom, to empty tank in the fall, pages 58, 123.

Be sure to have tank large enough, page 58.

Paint timber and woodwork in attic around tank with fire-proof paint, page 59.

NOTE.—If house is near a hill with higher ground, it will pay to have a brick cistern on hill, to relieve house of the weight of a water-tank and insure a larger supply of water, which can be pumped into it from well as easily as into a tank on the roof.

HARDWARE.—It is best for you to select, and therefore to furnish, the finishing hardware specified, pages 60, 103.

Select round wood knobs for up-stairs doors.

Have metal sash-chains, especially for plate-glass windows, with 2½-inch pulleys, page 60.

Stipulate windows to be weighed and balanced with weights.

Have all weights over 20 pounds of lead, page 104.

STANDING TRIM, ETC.—This should be time-seasoned or kiln-dried.

It should be back-primed before brought to premises, page 100.

Be sure to have architect furnish full details before taking estimates, page 61.

PICTURE-MOLDING.—Provide for, page 101.

PAINTING.—Specify colors, etc., by having samples. If pieces of wood painted, cut in two, and give half to painter, retaining half for yourself.

Require best materials.

Finish floors in wax, varnish, or otherwise, as you prefer.

LIGHTNING-ROD.—Must be of proper size, page 64.

Must reach moist ground or the water in well.

Must have numerous points on roof, page 64.

DUMB-WAITER.—See page 101.

PLUMBING.—Compare your specifications carefully with plumbing specifications, page 122.

Be sure to have lead supply-pipe of proper strength, page 123.

Be sure to have 2-inch wastes and traps.

Be sure to have main water-supply pipe to house from cistern, tank, or city water, of large size, not less than $1\frac{1}{2}$ inches, and of galvanized iron or lead, page 123.

Be sure to have soil-pipe carried through roof at least 4 inches in diameter; it is liable to have its capacity reduced by frost and ice, page 122.

Be sure to have your plumbing in sight, and where it passes from floor to floor, incased in ducts, with removable doors or sides, page 122.

LUGGAGE-ROOM.—Insert strong iron hooks for clothes-lines for drying, page 50.

CISTERNS.—Should be carefully constructed as per directions, pages 66, 115.

CRESSPOOL.—To be constructed as per directions, page 116.

Be sure to have it a safe distance from your well—at least 100 feet. Sometimes this is not a safe distance in other than sandy soil, where the dip of rock strata or clay-beds would hold and carry seepage.

Have the water of your well analyzed by a good chemist.

Typhoid fever is always swallowed.

TEMPORARY PRIVY FOR WORKMEN, page 106.

BUILDING DEPARTMENT.—If your building comes within the rules of the Building Department, see that your plans are approved before taking estimates or signing contracts; it costs nothing to be sure, and it is better to be sure than sorry.

ALTERNATE ESTIMATES, page 106.

SPECIFICATIONS.—Have specifications signed when contract is signed—your copy especially.

AUTHORITIES CONSULTED

The reader who desires wider reading as to the best methods of construction, the rules of framing, joining, etc., will do well to read any or all of the following books:

- "Building Superintendence," by T. M. Clark.
- Baker's "Treatise on Masonry Construction."
- "Building Construction and Superintendence," by F. E. Kidder.
- "The Suburban Cottage," by W. B. Tuthill.
- "The Disposal of Sewage in Country Houses," by William Paul Gerard.
- C. E.
 - Tredgold's "Carpentry and Joining."
 - "American House Carpenter," by Hatfield.
 - "How to Frame a House," by Owen B. Maginniss.
 - "The Art and Science of Carpentry Made Easy," by William E. Bell.
 - Hallett's "Specifications."
 - "Guide and Assistant for Carpenters," by H. G. Richey.
 - "Laws Relating to Building," by W. J. Fryer.

The building law of New York may be regarded as an educational textbook in correct construction. I think it will be conceded that much of its great merit is due to Mr. Fryer. Its few faults are those necessarily incident to compromises of conflicting interests and views, always to be expected where enactment is by committees and conventions.

An elaborate set of construction details, prepared for the use of students of the Massachusetts Institute of Technology, Boston, by Professor F. W. Chandler, published by the Heliotype Printing Co., Boston, is also worthy of careful study.

A comprehensive treatise on construction, with numerous illustrations, will be found under the head of "Building," in the "Encyclopædia Britannica."

INDEX

A

Alternate Estimates, 106.
 Angle-braces, 91.
 Arch, Trimmer-, 112, 113.
 Architect, Select Competent and Honest, 1; Contract with, 141.
 Art-gallery, 39.
 Asbestos, 23.
 Asphalt, 10, 110.
 Assorting Flooring, 23.
 Attic should be Painted, 59.
 Attic should be Ventilated, 27.

B

Back-air Pipes, 125.
 Back-plastering, 16, 119.
 Balconies, 30.
 Balloon Frame, 13, 90, 91.
 Balusters, 100.
 Base-boards, 98, 100; -knobs, 99.
 Basins, 125.
 Basswood Shingles, 27.
 Bath-rooms, 47; -tubs, 47, 125; Wainscot, 48, 101.
 Beam-filling, 115.
 Beams or Joists, Size of, 21, 92.
 Bedroom Doors, Transoms, 42, 99.
 Bells, 59, 129.
 Bicycle-room, 51.
 Billiard-room, 51.
 Birds' Nests, etc., 25.
 Blind Drains, 6.
 Blind-nailed, 25.
 Blinds, 105.
 Boiler, Hot-water, 124.
 Bonus, 134, 135.
 Borders to Hearths, 98.
 Braced Frame, 13, 90, 91.
 Braces, 94.
 Bracing Roof, 28.
 Brickwork, 10, 110.
 Bridging, 15, 92.
 Bridle-iron, 32, 94.
 Buffet, 44.

Building Departments, 6.
 Butler's Pantry, 46, 101; Sink, 101, 124.

C

Carpenter Specifications, 88, 89, etc.
 Carriage-timber, 52.
 Causes of Fires, 69.
 Ceilings, Height of, 39.
 Cellar, 7, 8; Doors, 99; Windows, 105; Brick Wall in, 92; Floor of, 7, 115, 120; Drain, 8.
 Cement, 10.
 Cement Mortar, 109.
 Center Joist or Stud, 37, 93.
 Cesspool, 116.
 Chandeliers, 57.
 Cheaply, How to Build, vii, 85, 86.
 Chimneys, 31, 111, 113; -shoulder at Roof, 33, 113; How Built, 112, 113; should be Coped, 33; from Ground, 113; -breast Plastered, 37; Specifications, 111; Smoking, 36.
 Cisterns, 66, 115; Capacity of, 66.
 Clapboards, 96.
 Clock-shelves, 104.
 Closets, 43, 100; Moth-proof, 44, 101; Specifications, 100; Linen-, 101.
 Clothes-chute to Laundry, 101.
 Clothes Drying, 46.
 Coal-bins, 8, 106.
 Cold-air Box of Furnace, 56, 121.
 Cold Room, 9, 106.
 Collar-beam, 28.
 Comb-grain Yellow Pine, 22.
 Concrete, 7, 100; Floor, 109.
 Conductors, 103.
 Contract, General Form of, 130-133; with Architect, 141.
 Contractor, Have One for Whole Work, 67; Investigate, 68.
 Coping, 33.
 Copper for Flashings, etc., 29.
 Corbel for Chimney, 113.
 Cornices, 102; Plaster Cornices, 119.
 Creosote Stains, 15.

Crickets, 29.
Cross-bridging, 15, 92.
Crowning Edge, 95.

D

Dark Room for Photography, 51.
Deafening, 24, 98.
Decks for Balconies, 30.
Defective Flues, 34, 69.
Details, Trim, etc., 61.
Diagram of Frame, 91.
Dining-room should be on Cool Side, 4, 44.
Dippers, 20.
Door-knobs, 60.
Door-sills, 98.
Doors, Stock Sizes, 46, 98; Specifications, 98; Sliding, 98; Cellar, 99; Fire-proof, 39; Veneered, 98.
Drain in Cellar, 8.
Drain-pipe, 5, 109.
Drainage, 5, 16.
Draw-bored, 92.
Dropped Girts, 13.
Dry Room, 50.
Dumb-waiters, 101.

E

Electric Lighting, 57; Specifications, 127; Bells, 59.
Enameled-iron Bath-tubs, 47; Paint Exterior, 48.
Equitable Contract, 130.
Estimates, Alternate, 106.
Examination of Plans, Systematic, 41, 142.
Excavations, 1, 3, 109.
Exposed Plumbing, 105, 125.
Extras, 68.

F

Faucets, 47.
Finish, 100.
Finishing Hardware, 60, 103.
Fire-extinguishing Appliances, 20.
Fire-insurance, 69.
Fireplaces, Number of, 36, 37; Back of, 36; Smoking, 36; Height, etc., 36; Hood, 36; Specifications, 95, 113; How Built, 36, 95.
Fire-proof Library, 39; Doors, 39.
Fires, Causes of, 69; from Defective Flues, 33, 70.
Fire-stops, 16, 17, 18, 19, 100, 115.
Fire-wood Stored in Cellar, 8.
Fish-plates, 14.
Flashings, 29, 103, 126.
Floor-deafening, 24, 98.
Flooring, 21; of Plaza, 25.
Floor-joists and Beams, 21; should be "Bridged," 15, 92; Size, 21.
Floor-stops, 99.
Floors should be Deafened, 24.
Floors should be Double, 21, 22.

Flues should be eight inches thick, Lined, 33, 34, 111; 8x12, 35; Plastering in, 34.
Fly Screens, 43; Door, 43.
Footing Courses, 10, 110.
Foundation Walls, 10, 110.
Frame Dwellings Healthiest, 13.
Framing, 28, 95.
Freezing Weather, 11.
French Windows, 42.
Furnace, 54, 55, 56; Pit, 114, 120.
Furring on Chimney-breasts, 37, 94.

G

Gallon of Water, 67.
Galvanized Nails, 16.
Gas-fitting Specifications, 126.
Gas Outlets, 57.
Gasolene Gas, 57, 127.
Girders, 21.
Girts, 13, 93.
Glass, 105.
Glazing, 129.
Grading, 1, 3.
Grounds for Plaster, 94.
Grouting, 110.
Gun-room, 51.
Gutters, 5, 102, 103.

H

Hard Wood, 40.
Hardware, 60, 103.
Hatchway, 99.
Header-beams, 32, 94; Bricks, 110.
Hearths, 32, 98; Trimmer-arch, 32, 112, 113, 114.
Heating, 54; Specifications, 120.
Height of Ceilings, 39.
Hill-sides, 4, 5.
Hips, 83.
Hood, Heat and Odor Extinguisher, 45.
Hose, Fire, 20.
Hot-air Pipes to Furnace, 54; Engine, 58.

I

Inspector, Employ, 2.
Insurance, 69.
Interior Finish, 100.
Interties, 94.

J

Japanese *Kura*, 39.
Joist- or Floor-beams, Size of, 21, 92; should be Cross-bridged, 15, 92.

K

Keene's Cement, 48.
King-post, 28, 61.
Kitchen, 44, 101; Bedroom over, 45; Floor, 24; Storm-door to, 46, 105.
Knobs, etc., 60.
Kura, Japanese, 39.

L

Lath, 38, 118.
 Laundry, 125.
 Lavatory on First Floor, 49.
 Lay of Land, 3.
 Lead for Decks, 30; for Bath-rooms, 47.
 Lead-pipes, Weights, 126.
 Leaders, 103.
 Leaf-arresters in Leaders, 144.
 Library, 39.
 Liens, Mechanics', 68, 135.
 Lighting, 57.
 Lightning-rods, 64.
 Lime Mortar, 108.
 Lime, Slaking, 108.
 Linen-closet, 49, 101.
 Loam and Top Soil, 4.
 Luggage-room, 50.
 Lumber, 89.

M

Mantels, 38, 100.
 Mason's Specifications, 107, 108, etc.
 Metallic Lathing, 38, 118.
 Moldings, 101.
 Mortar, Lime, 9, 10, 108; Cement, 10, 109; Lime and Cement, 109.
 Mortar, Roof in, 26, 96.
 Mosquito Screens, 43.
 Moth-proof Closets, 44, 101.
 Music-room, 51.

N

Newels, 100.
 North Carolina Pine, 22, 97.

O

Outlets for Gas, etc., 57, 126.

P

Pails of Water, 20.
 Paint, Fire-resisting, 59.
 Painting, 62; Specifications, 128.
 Panels to Windows, 105.
 Pantry, 46, 101.
 Parging, 35.
 Parquet Flooring, 23.
 Penalties, 68, 134, 135.
 Peppermint Test of Plumbing, 123.
 Photograph Room, 51.
 Piazza, 24; Steps, 25, 99; Columns, 26, 63, 94; Windows Opening on, 42; Timbers, 94.
 Picture-gallery, 51.
 Picture-moldings, 100.
 Piers, 21, 111.
 Plans, Sample, 72, 73, 74, 75.
 Plastering, 38; Grounds, 94; Back-, 16, 119; in Flues, 35; Specifications, 116.
 Plates, 94.
 Plate-glass, 41, 105.
 Play-room, 51.

Plumbing, Open, 105; Specifications, 122, 123.
 Pockets to Windows, 104.
 Porcelain-lined Tubs, 47; Paint Exterior, 48.
 Posts, 91, 94.
 Prevailing Breeze, 4.
 Priming, 100, 105.
 Privy, Temporary, 106.
 Pumping, 58.
 Putty Piazza, 26.

Q

Queen-post, 29.

R

Rafters, 92.
 Rails, 100.
 Range, 113, 124.
 Rat-proof Store-room, 47, 101.
 Refrigerator, 46.
 Registers, Furnace, 56, 120.
 Retaining-walls, 12, 111.
 Ribbon, 13, 90.
 Ridge-roll, 29, 30.
 Road-boxes, 5.
 Roof, 26, 96; should be Braced, 28, 29, 91; Shingle, 26, 97.
 Rubbish, 106.

S

Salamander, 23.
 Sample Plans, 72, 73, 74; Specifications, 85.
 Sand, Sharp, 9, 10.
 Sap Side of Flooring, 22; Sap Lumber on Piazza, 25.
 Sash-weights, 60, 104; -cord, 60; -chain, 80.
 Screens, Fly, 43.
 Select Flooring, 23.
 Sewing-room, 50.
 Sheathing on Side-walls, 15, 95; Nail Horizontally, 15, 95.
 Shingled Side-walls, 15, 95; Roof, 26, 97.
 Shingles, 26.
 Shoulders to Chimney at Roof, 33, 113.
 Shrinkage of Wood, 14, 15, 93.
 Sills, 94; Door-sills, 98.
 Sink, Kitchen, 124.
 Skirt-boards or Base-boards, 98.
 Slaking Lime, 108.
 Slate Roof, 26, 96.
 Sliding Doors, 98.
 Slop-closet, 49.
 Smoking Fireplaces, 35, 36.
 Soil-pipe, 122, 125.
 Soil, Top, Save, 4, 109.
 Sorting Flooring, 23.
 Sparrows' Nests in Piazza, 25.
 Speaking-trumpet, 59, 128.
 Specifications, for Woodwork, 88; Mason's, 106; Plasterer's, 116; Plumbing, 122.

Staircases, 52; Wide, 52; Fire-stops
in, 52, 118; Specifications, 88, 99.
Standing Trim Primed, 100.

Steam, 56.

Steps to Piazza, 25, 99.

Stirrup-irons, 82, 94.

Stock Sizes, 41.

Stone for Walls, 11; Piers, 11, 111.

Stone-work, 111.

Store-room, Rat- and Mouse-proof,
47, 101.

Storm-shutters and -doors, 43, 46,
105.

Stove-pipes, 34.

Stretcher Brick, 110.

Studs, 93; Center, 37.

Supervision, 2, 106.

Supply Pipe, Water, 123.

Surveyor, Employ, 2.

Sweeping Moldings, 24, 100.

Systematic Examinations of Plans,
etc., 41.

T

Tail-beams, 32, 95.

Tank, 58, 102, 128.

Test of Plumbing, 123.

Thresholds, 98.

Tile in Bath-room, 49.

Tinning Specifications, 128.

Toilet-room on First Floor, 49.

Top Soil, Save, 4, 109.

Tracy, Hon. B. F., 40.

Transoms, 42, 90.

Traps, 126.

Trim, 60; Architect should Furnish
Detail, 60; Yellow Pine, 62; should
have Back Primed, 100.

Trimmer-arch, 112, 113.

Trimmer-beams, 32, 94, 95.

Trumpet-speaking, 59, 109.

Trunk-room, 50.

Tuba, Bath-, 47, 125; Wash-, 125.

U

Underpinning, 9.

Underwriters' Rules, 58.

V

Veneered Doors, 98.

Ventilating-flue in Kitchen Chim-
ney, 45, 114.

Veranda, 94. See Piazza.

W

Wainscot Bath-rooms, etc., 48, 101.

Walls, Foundation, 10, 11.

Wash-basins, 125.

Wash-tubs, 125.

Water-closets, 123; on First Floor, 49.

Water-pails, 20.

Water-tank, 58, 59.

Weather Gray, 15.

Wedging, Slate, 111.

Weepers, 12, 111.

Wind, Prevailing, 4.

Windows, 42; Stock Sizes, 41, 104;

Planning, 42; Panels, 42, 106; Have

Enough, 42; French, 41; Pockets

for, 104.

Windows in Stone Walls, 42; Cellar,

105.

Wooden Ceilings, 40.

Wooden Dwellings, 13.

Woodwork, 88; Specifications for, 88.

Y

Yale Locks, 46, 105.

Yellow-pine Finish, 62.

1344
150

a =

$$\frac{ay}{100}$$

$$80$$

